Accessory Design Guidelines for Apple Devices

Release R28

Contents

Overview 22

1. Introduction 23

2. Requirements 24
2.1 Developer Preview 24

3. Terminology 25
3.1 Device 25
3.2 Accessory 25
3.3 Component 25
3.4 Control Surface 26
3.5 Direct User Action 26
3.6 Built-In Cable 26
3.7 Apple MFi Program 27
3.8 Accessory Interface Specification 27

Accessories 28

4. All Accessories 29
4.1 Scratches and Damage 29
4.2 Compliance Testing 29
4.3 USB-B Receptacles 29
4.4 User Supplied Cables and AC Power Adapters 29
4.5 TDMA Noise 30
4.6 Attachments 30
4.7 Magnetic Interference 30
4.8 Radio Frequency (RF) Performance 32
4.8.1 Materials and Coatings 32
4.8.2 Antenna Keep-Out 32
4.8.3 Over The Air (OTA) Transmission/Reception 32
4.8.4 Specific Absorption Rate (SAR) 33
4.8.5 Near Field Communication (NFC) 33

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

4.9 Thermal Management 34
4.10 Tripod Connections 35
4.11 Anthropometric Considerations 35

5. Cases 36
5.1 Product Design 36
5.1.1 Device Protection 36
5.1.2 Access to Inputs and Interconnects 37
5.1.3 Dock Compatibility 43
5.1.4 Wireless Power 43
5.2 Acoustics 43
5.2.1 Call Quality 43
5.2.2 Speaker to Microphone Coupling 44
5.2.3 Speaker/Microphone Openings 44
5.3 Ambient Light Sensor and Proximity Sensor 46
5.4 Haptics 46
5.5 Magnetic Interference 46
5.6 Touch ID 47
5.7 Camera 47
5.7.1 Geometry 47
5.7.2 Color 48
5.7.3 Surface Finish 48
5.7.4 Image Degradation Examples 48
5.8 Reliability 49
5.8.1 Device Insertion and Removal 49
5.8.2 Colorfastness 49
5.9 Environmental 49
5.10 Verification 50
5.10.1 Device Models 50
5.10.2 Product Design 72
5.10.3 Camera Control 74
5.10.4 Haptics 75
5.10.5 Touch ID Sensor Overlays 76
5.10.6 Camera 76
5.10.7 Near-Field Communication (NFC) 80
5.10.8 Compass 81
5.10.9 Acoustics 82

6. Covers 85
6.1 Device Protection 85

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

6.2 Magnetic Interference 85
6.3 Smart Covers 85

7. Screen Overlays 87
7.1 Product Design 87
7.1.1 Optical Transmission 87
7.1.2 Infrared Transmission 88
7.1.3 Transmission Haze 88
7.1.4 Dynamic Island 89
7.2 Edge Swipe Gestures 89

8. Camera Attachments 90
8.1 Magnetic Interference 90

9. Adapters 91
9.1 Headset Adapters (Lightning to 3.5 mm) 91
9.2 USB-A/USB-C to Lightning Headset Adapters 91
9.3 Lightning to USB Micro-B Adapters 91

10. AC Power Adapters 93
10.1 Converter Switching Frequencies 93
10.2 YCAP AC Capacitor 93
10.3 Impedance Stability 93
10.4 Fuse Protection 94
10.5 Short Circuit Response 95

11. Battery Packs 96

12. Headsets 97
12.1 Product Design 97
12.2 Audio Interface 97
12.3 Remote Controls 98
12.4 USB-C Headset Identification 98

13. Strobes 99

14. Keyboards 101
14.1 Requirements 101
14.2 Examples 106
14.2.1 Example HID Report Descriptor 106

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

15. Trackpads 107
15.1 Requirements 107
15.1.1 Integration with Keyboards 107
15.1.2 HID Report Descriptor 107
15.1.3 Coexistence 108
15.1.4 Performance 108
15.1.5 Input Confidence 109
15.1.6 Click to Wake 109
15.2 Examples 110
15.2.1 Example HID Report Descriptor 110
15.2.2 Example Trackpad 113

16. Braille Displays and Keyboards 116
16.1 Requirements 116
16.1.1 Braille Keyboards 118
16.1.2 Screen Reader Controls 119
16.2 Examples 122
16.2.1 Example HID Report Descriptor 122

17. External Storage 127
17.1 Overview 127
17.2 Apple ProRes 4K 127
17.3 Verification 128
17.3.1 Apple ProRes 4K 128

18. AirPods Accessories 129
18.1 Charging Case Covers 129
18.2 Chargers 130
18.3 AirPods Max Accessories 130
18.3.1 Sleep Mode 130
18.4 Magnetic Flux Probe 131
18.5 Verification 132
18.5.1 MagSafe Charging with Case Cover 132

19. Apple Vision Pro Accessories 133
19.1 Apple Vision Pro Storage Cases 133
19.2 Apple Vision Pro Battery Holders 133
19.3 Apple Vision Pro Bands 134
19.4 Verification 134
19.4.1 Equipment 134

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

19.4.2 Peel Force 134

20. Watch Bands 136

20.1 Requirements 136
20.2 Example Apple Watch Lug Assembly 137
20.3 Apple Watch Band Interface (49 mm) 140
20.4 Apple Watch Band Interface (42 mm & 46 mm) 141
20.5 Apple Watch Band Interface (41 mm & 45 mm) 142
20.6 Apple Watch Band Interface (40 mm & 44 mm) 143
20.7 Example Apple Watch Lug (49 mm) 144
20.8 Example Apple Watch Lug (42 mm & 46 mm) 145
20.9 Example Apple Watch Lug (41 mm & 45 mm) 146
20.10 Example Apple Watch Lug (40 mm & 44 mm) 147

21. Apple MagSafe Charger Mounts 148

21.1 Mechanical 148

22. StandBy Mounts 149

22.1 Product Design 150
22.2 Verification 151
22.2.1 Equipment 151
22.2.2 Enable StandBy 151
22.2.3 Product Design 151

23. Continuity Camera Mounts 152

23.1 Product Design 153
23.2 Apple TV Mount 154
23.3 MacBook Mount 155
23.4 iMac or Display Mount 156
23.5 Verification 157
23.5.1 Equipment 157
23.5.2 Setup 157
23.5.3 Product Design 158
23.5.4 Center Stage 158
23.5.5 Desk View 159

Features 161

24. Accessory Power (USB-C) 162

24.1 Available Current 162
24.2 VCONN 163
24.3 Fast Role Swap (FRS) 163
24.4 Verification 164
24.4.1 Maximum Accessory Power 164
24.4.2 VCONN 165

25. Accessory Power (Lightning) 167

26. App Discovery 168

27. App Launch 169

28. App Match 170

29. Bluetooth HFP Siri and Battery Reporting 171
29.1 HFP Command AT+XAPL 171

30. Bluetooth Headset Battery Level Indication 172
30.1 HFP Command AT+IPHONEACCEV 172

31. Bluetooth Low Energy Battery Service 173
31.1 Overview 173
31.2 All Accessories 173
31.2.1 Hands Free Profile (HFP) Accessories 174

32. Device Power (USB-C) 175
32.1 External Power Source 175
32.2 Power State Changes 176

33. Device Power (Lightning) 177
33.1 Direct Power Source 177
33.2 External Power Source 177
33.3 Declaring Capability 178
33.4 Providing Power using USB Connectors 178
33.5 Labeling Multiple Connectors 178
33.6 Fast Charge for iPhone (20 W) 179
33.7 Overcurrent and Short Circuit Protection 180
33.8 Overcurrent and Short Circuit Protection Resets 181
33.9 Power State Changes 181

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

34. Device Power (Inductive) 182
34.1 Qi Wireless Power 182
34.2 MagSafe 183
34.3 Electromagnetic Compatibility (EMC) 184

35. Ethernet over USB 186

36. External Accessory Protocol 187

37. HID Headset Remote 188
37.1 Requirements 188
37.2 Examples 189
37.2.1 Headset Remote Example HID Report Descriptor (Telephony) 189
37.2.2 Headset Remote Example HID Report Descriptor (Media Playback) 189
37.2.3 Headset Remote Example HID Report Descriptor (Telephony and Media Playback) 190

38. Location Information 192

39. MagSafe Attach 193
39.1 MagSafe Case Magnet Array 194
39.1.1 Product Design 194
39.1.2 Mechanical 195
39.1.3 Magnetic Interference 198
39.2 MagSafe Accessory Magnet Array 198
39.2.1 Product Design 198
39.2.2 Mechanical 198
39.3 MagSafe Accessory Enclosure Geometry 207
39.4 Verification 208
39.4.1 MagSafe Case Magnet Array 208
39.4.2 MagSafe Accessory Magnet Array 211

40. Media Library Access 213

41. Musical Instrument Digital Interface (MIDI) 214
41.1 Requirements 214
41.2 Verification 214

42. Now Playing Updates 215

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

43. Out-of-Band Bluetooth Pairing 216

44. Siri 217
44.1 Enabling Custom Siri Commands 217
44.2 Obtaining Siri Availability Information 217
44.2.1 Obtaining Status Information at Connection 217
44.2.2 Receiving Siri Availability Updates from the Device 218
44.3 Initiating a Siri Session 219
44.3.1 Initiating a Session from the Accessory 219
44.3.2 Initiating a Session from the Device 220
44.3.3 Ending a Session from the Accessory 221
44.4 Siri Eyes Free Mode 222
44.4.1 HFP Command AT+APLEFM 222
44.5 Improving Voice Recognition 222
44.5.1 Wide Band Speech Support 223
44.6 Optimizing the Siri Experience 223
44.7 Common Siri Applications 224
44.7.1 Initialization Procedure After Connection is Established 224
44.7.2 Phone Dialing Using Siri 225
44.7.3 Audio Routing and Media Playback Using Siri 225
44.7.4 Turn-By-Turn Directions Using Siri 226
44.8 User Interaction with Siri Eyes Free in a Vehicle 226
44.9 Enabling/Disabling Siri from the Device 228
44.10 Verification 229
44.10.1 Siri Eyes Free 229

45. Wi-Fi Information Sharing 234

Protocols 235

46. USB Power Capability Vendor Request 236

47. USB D+/D- Resistor Networks 237
47.1 Declaring Power Source Capability 237
47.2 Identifying Power Source Current Limit 238

48. USB Power Delivery (PD) 240

49. USB Type-C Current 241

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

50. Advanced Audio Distribution Profile (A2DP) 242
50.1 Bluetooth A2DP Specification 242
50.1.1 AVDTP Transactions 242
50.2 SubBand Codec (SBC) 242
50.3 MPEG 2/4 AAC Codecs 243
50.4 Verification 244
50.4.1 Audio Quality 244
50.4.2 Audio Switching 244
50.4.3 HFP Interaction 245
50.4.4 Siri 245
50.4.5 Video Playback 245

51. iAP2 246

52. Human Interface Device (HID) 247
52.1 Requirements 247
52.1.1 Report Descriptor 248
52.1.2 USB 248
52.2 Verification 248
52.2.1 General 248

Transports 250

53. Wi-Fi Aware 251
53.1 Overview 251
53.2 Requirements 251
53.3 Peer as a Subscriber 252
53.4 Peer as a Publisher 253
53.5 Privacy 254
53.5.1 Service & Device Discovery 254
53.5.2 Frame Identifiers 255
53.6 Improving Quality of Service (QoS) 255

54. Bluetooth 258
54.1 Enhanced Data Rate 258
54.2 Adaptive Frequency Hopping 258
54.3 Sniff Mode for Low Power Consumption 258
54.4 Role and Topology Management 259
54.5 Extended Inquiry Response 260

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

54.6 Secure Simple Pairing 260
54.7 Pairing Button 260
54.8 Class of Device (CoD) 261
54.9 Link Supervision Timeout 261
54.10 Delay Reporting 261
54.11 Profiles 261
54.11.1 Device ID Profile (DID) 261
54.11.2 Service Discovery Protocol (SDP) 262
54.11.3 Hands-Free Profile (HFP) 262
54.11.4 Message Access Profile (MAP) 264
54.11.5 Audio/Video Remote Control Profile (AVRCP) 265
54.11.6 Advanced Audio Distribution Profile (A2DP) 267
54.12 Audio Routing 267
54.12.1 Audio Data Received using HFP Profile 267
54.12.2 Audio Data Received using A2DP Profile 267
54.13 HID 269

55. Bluetooth Low Energy (BLE) 270
55.1 Role 270
55.2 Advertising Channels 270
55.3 Advertising PDU 270
55.4 Advertising Data 270
55.5 Advertising Interval 271
55.6 Connection Parameters 272
55.7 Data Packet Length Extension 272
55.8 Privacy 273
55.9 Permissions 273
55.10 Pairing 273
55.11 MTU Size 274
55.12 Services 274
55.12.1 Generic Access Profile Service 274
55.12.2 Generic Attribute Profile Service 274
55.12.3 Device Information Service 275
55.12.4 Available Services 275
55.13 GATT Server 275

Modules 277

56. Apple USB-C Analog Headset Module 278

56.1 Overview 278
56.1.1 Additional Specifications & Support 279
56.1.2 Procurement 279
56.2 Mechanical 279
56.2.1 Shielding 279
56.3 Pad Assignments 280
56.4 Electrical 281
56.4.1 DAC Characteristics 281
56.5 C125 Dimensions 283
56.6 C125 Recommended Clamshell Shields 284
56.7 C125 Recommended Rear Shield 285

Components 286

57. Headset Remote and Microphone Transmitter 287
57.1 Overview 287
57.2 Requirements 287
57.3 Usage 296
57.3.1 Pin Assignments 297
57.3.2 Maximum Voltage and Current Ratings 297
57.3.3 Electrical Characteristics 298
57.3.4 Theory of Operation 299
57.3.5 Button Mode 300
57.3.6 Tone Mode 301
57.4 Button Detection Circuitry Usage 304
57.4.1 Button Detection Circuitry Adjustments 307

Connectors 308

58. USB-A Receptacle 309
58.1 Mechanical 309
58.2 Electrical 309

59. USB-C Plug 310
59.1 Overview 310
59.2 Mechanical 310
59.3 Electrical 311
59.3.1 Drawing Power 311

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

59.3.2 Providing Power 312
59.4 Verification 312
59.4.1 Mechanical 312
59.4.2 Drawing Power 312

60. USB-C Receptacle 313
60.1 Overview 313
60.2 Mechanical 313
60.3 Electrical 313
60.3.1 Drawing Power 313
60.3.2 Providing Power 314
60.4 USB-C receptacle accessory keep-out 315
60.5 Verification 316
60.5.1 Drawing Power 316
60.5.2 Providing Power 317

61. Headset Plug (3.5 mm) 318
61.1 Mechanical 318
61.2 Pins 320
61.3 Example Circuitry 320
61.4 Verification 322
61.4.1 Connectivity 322
61.4.2 Microphone 322
61.4.3 Controls 323
61.4.4 Audio Quality 323

Tools 324

62. Accessory Developer Assistant (ADA) 325
62.1 Autofocus & Optical Image Stabilization Test Profile 326

References 327

63. Device Dimensional Drawings 328
63.1 iPhone 17 Pro Max, 1 of 4 333
63.2 iPhone 17 Pro Max, 2 of 4 334
63.3 iPhone 17 Pro Max, 3 of 4 335
63.4 iPhone 17 Pro Max, 4 of 4 336

Copyright © 2025 Apple Inc. All Rights Reserved.

63.5 iPhone 17 Pro, 1 of 4 337
63.6 iPhone 17 Pro, 2 of 4 338
63.7 iPhone 17 Pro, 3 of 4 339
63.8 iPhone 17 Pro, 4 of 4 340
63.9 iPhone 17, 1 of 4 341
63.10 iPhone 17, 2 of 4 342
63.11 iPhone 17, 3 of 4 343
63.12 iPhone 17, 4 of 4 344
63.13 iPhone Air, 1 of 4 345
63.14 iPhone Air, 2 of 4 346
63.15 iPhone Air, 3 of 4 347
63.16 iPhone Air, 4 of 4 348
63.17 iPhone 16e, 1 of 2 349
63.18 iPhone 16e, 2 of 2 350
63.19 iPhone 16 Pro Max, 1 of 4 351
63.20 iPhone 16 Pro Max, 2 of 4 352
63.21 iPhone 16 Pro Max, 3 of 4 353
63.22 iPhone 16 Pro Max, 4 of 4 354
63.23 iPhone 16 Pro, 1 of 4 355
63.24 iPhone 16 Pro, 2 of 4 356
63.25 iPhone 16 Pro, 3 of 4 357
63.26 iPhone 16 Pro, 4 of 4 358
63.27 iPhone 16 Plus, 1 of 4 359
63.28 iPhone 16 Plus, 2 of 4 360
63.29 iPhone 16 Plus, 3 of 4 361
63.30 iPhone 16 Plus, 4 of 4 362
63.31 iPhone 16, 1 of 4 363
63.32 iPhone 16, 2 of 4 364
63.33 iPhone 16, 3 of 4 365
63.34 iPhone 16, 4 of 4 366
63.35 iPhone 15 Pro Max, 1 of 3 367
63.36 iPhone 15 Pro Max, 2 of 3 368
63.37 iPhone 15 Pro Max, 3 of 3 369
63.38 iPhone 15 Pro, 1 of 3 370
63.39 iPhone 15 Pro, 2 of 3 371
63.40 iPhone 15 Pro, 3 of 3 372
63.41 iPhone 15 Plus, 1 of 3 373
63.42 iPhone 15 Plus, 2 of 3 374
63.43 iPhone 15 Plus, 3 of 3 375

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

63.44 iPhone 15, 1 of 3 376
63.45 iPhone 15, 2 of 3 377
63.46 iPhone 15, 3 of 3 378
63.47 iPhone 14 Pro Max, 1 of 3 379
63.48 iPhone 14 Pro Max, 2 of 3 380
63.49 iPhone 14 Pro Max, 3 of 3 381
63.50 iPhone 14 Pro, 1 of 3 382
63.51 iPhone 14 Pro, 2 of 3 383
63.52 iPhone 14 Pro, 3 of 3 384
63.53 iPhone 14 Plus, 1 of 3 385
63.54 iPhone 14 Plus, 2 of 3 386
63.55 iPhone 14 Plus, 3 of 3 387
63.56 iPhone 14, 1 of 3 388
63.57 iPhone 14, 2 of 3 389
63.58 iPhone 14, 3 of 3 390
63.59 iPhone 13 Pro Max, 1 of 2 391
63.60 iPhone 13 Pro Max, 2 of 2 392
63.61 iPhone 13 Pro, 1 of 2 393
63.62 iPhone 13 Pro, 2 of 2 394
63.63 iPhone 13, 1 of 2 395
63.64 iPhone 13, 2 of 2 396
63.65 iPhone 13 mini, 1 of 2 397
63.66 iPhone 13 mini, 2 of 2 398
63.67 iPhone 12 Pro Max, 1 of 2 399
63.68 iPhone 12 Pro Max, 2 of 2 400
63.69 iPhone 12 Pro, 1 of 2 401
63.70 iPhone 12 Pro, 2 of 2 402
63.71 iPhone 12, 1 of 2 403
63.72 iPhone 12, 2 of 2 404
63.73 iPhone 12 mini, 1 of 2 405
63.74 iPhone 12 mini, 2 of 2 406
63.75 iPhone SE (3rd generation) and iPhone SE (2nd generation) 407
63.76 iPhone 11 Pro Max 408
63.77 iPhone 11 Pro 409
63.78 iPhone 11 410
63.79 iPhone XS Max 411
63.80 iPhone XS 412
63.81 iPhone XR 413
63.82 iPhone X 414

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

63.83 iPhone 8 Plus 415
63.84 iPhone 8 416
63.85 iPhone 7 Plus 417
63.86 iPhone 7 418
63.87 iPhone 6s Plus 419
63.88 iPhone 6s 420
63.89 iPhone 6 Plus 421
63.90 iPhone 6 422
63.91 iPhone SE and iPhone 5s 423
63.92 iPhone 5c 424
63.93 iPhone 5 425
63.94 iPad Pro 13-inch (M5) and iPad Pro 13-inch (M4), 1 of 5 426
63.95 iPad Pro 13-inch (M5) and iPad Pro 13-inch (M4), 2 of 5 427
63.96 iPad Pro 13-inch (M5) and iPad Pro 13-inch (M4), 3 of 5 428
63.97 iPad Pro 13-inch (M5) and iPad Pro 13-inch (M4), 4 of 5 429
63.98 iPad Pro 13-inch (M5) and iPad Pro 13-inch (M4), 5 of 5 430
63.99 iPad Pro 11-inch (M5) and iPad Pro 11-inch (M4), 1 of 5 431
63.100 iPad Pro 11-inch (M5) and iPad Pro 11-inch (M4), 2 of 5 432
63.101 iPad Pro 11-inch (M5) and iPad Pro 11-inch (M4), 3 of 5 433
63.102 iPad Pro 11-inch (M5) and iPad Pro 11-inch (M4), 4 of 5 434
63.103 iPad Pro 11-inch (M5) and iPad Pro 11-inch (M4), 5 of 5 435
63.104 iPad Air 13-inch (M3) and iPad Air 13-inch (M2), 1 of 5 436
63.105 iPad Air 13-inch (M3) and iPad Air 13-inch (M2), 2 of 5 437
63.106 iPad Air 13-inch (M3) and iPad Air 13-inch (M2), 3 of 5 438
63.107 iPad Air 13-inch (M3) and iPad Air 13-inch (M2), 4 of 5 439
63.108 iPad Air 13-inch (M3) and iPad Air 13-inch (M2), 5 of 5 440
63.109 iPad Air 11-inch (M3) and iPad Air 11-inch (M2), 1 of 5 441
63.110 iPad Air 11-inch (M3) and iPad Air 11-inch (M2), 2 of 5 442
63.111 iPad Air 11-inch (M3) and iPad Air 11-inch (M2), 3 of 5 443
63.112 iPad Air 11-inch (M3) and iPad Air 11-inch (M2), 4 of 5 444
63.113 iPad Air 11-inch (M3) and iPad Air 11-inch (M2), 5 of 5 445
63.114 iPad (A16) and iPad (10th generation), 1 of 7 446
63.115 iPad (A16) and iPad (10th generation), 2 of 7 447
63.116 iPad (A16) and iPad (10th generation), 3 of 7 448
63.117 iPad (A16) and iPad (10th generation), 4 of 7 449
63.118 iPad (A16) and iPad (10th generation), 5 of 7 450
63.119 iPad (A16) and iPad (10th generation), 6 of 7 451
63.120 iPad (A16) and iPad (10th generation), 7 of 7 452
63.121 iPad mini (A17 Pro), 1 of 6 453

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

63.122 iPad mini (A17 Pro), 2 of 6 454
63.123 iPad mini (A17 Pro), 3 of 6 455
63.124 iPad mini (A17 Pro), 4 of 6 456
63.125 iPad mini (A17 Pro), 5 of 6 457
63.126 iPad mini (A17 Pro), 6 of 6 458
63.127 iPad Pro 12.9-inch (6th generation), 1 of 5 459
63.128 iPad Pro 12.9-inch (6th generation), 2 of 5 460
63.129 iPad Pro 12.9-inch (6th generation), 3 of 5 461
63.130 iPad Pro 12.9-inch (6th generation), 4 of 5 462
63.131 iPad Pro 12.9-inch (6th generation), 5 of 5 463
63.132 iPad Pro 11-inch (4th generation), 1 of 5 464
63.133 iPad Pro 11-inch (4th generation), 2 of 5 465
63.134 iPad Pro 11-inch (4th generation), 3 of 5 466
63.135 iPad Pro 11-inch (4th generation), 4 of 5 467
63.136 iPad Pro 11-inch (4th generation), 5 of 5 468
63.137 iPad Air (5th generation) and iPad Air (4th generation), 1 of 5 469
63.138 iPad Air (5th generation) and iPad Air (4th generation), 2 of 5 470
63.139 iPad Air (5th generation) and iPad Air (4th generation), 3 of 5 471
63.140 iPad Air (5th generation) and iPad Air (4th generation), 4 of 5 472
63.141 iPad Air (5th generation) and iPad Air (4th generation), 5 of 5 473
63.142 iPad mini (6th generation), 1 of 6 474
63.143 iPad mini (6th generation), 2 of 6 475
63.144 iPad mini (6th generation), 3 of 6 476
63.145 iPad mini (6th generation), 4 of 6 477
63.146 iPad mini (6th generation), 5 of 6 478
63.147 iPad mini (6th generation), 6 of 6 479
63.148 iPad (9th generation), iPad (8th generation) and iPad (7th generation), 1 of 4 480
63.149 iPad (9th generation), iPad (8th generation) and iPad (7th generation), 2 of 4 481
63.150 iPad (9th generation), iPad (8th generation) and iPad (7th generation), 3 of 4 482
63.151 iPad (9th generation), iPad (8th generation) and iPad (7th generation), 4 of 4 483
63.152 iPad Pro 12.9-inch (5th generation), 1 of 5 484
63.153 iPad Pro 12.9-inch (5th generation), 2 of 5 485
63.154 iPad Pro 12.9-inch (5th generation), 3 of 5 486
63.155 iPad Pro 12.9-inch (5th generation), 4 of 5 487
63.156 iPad Pro 12.9-inch (5th generation), 5 of 5 488
63.157 iPad Pro 11-inch (3rd generation), 1 of 5 489
63.158 iPad Pro 11-inch (3rd generation), 2 of 5 490
63.159 iPad Pro 11-inch (3rd generation), 3 of 5 491
63.160 iPad Pro 11-inch (3rd generation), 4 of 5 492

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

63.161 iPad Pro 11-inch (3rd generation), 5 of 5 493
63.162 iPad Pro 12.9-inch (4th generation), 1 of 5 494
63.163 iPad Pro 12.9-inch (4th generation), 2 of 5 495
63.164 iPad Pro 12.9-inch (4th generation), 3 of 5 496
63.165 iPad Pro 12.9-inch (4th generation), 4 of 5 497
63.166 iPad Pro 12.9-inch (4th generation), 5 of 5 498
63.167 iPad Pro 11-inch (2nd generation), 1 of 5 499
63.168 iPad Pro 11-inch (2nd generation), 2 of 5 500
63.169 iPad Pro 11-inch (2nd generation), 3 of 5 501
63.170 iPad Pro 11-inch (2nd generation), 4 of 5 502
63.171 iPad Pro 11-inch (2nd generation), 5 of 5 503
63.172 iPad Air (3rd generation), 1 of 3 504
63.173 iPad Air (3rd generation), 2 of 3 505
63.174 iPad Air (3rd generation), 3 of 3 506
63.175 iPad Air (3rd generation) with Cellular, 1 of 3 507
63.176 iPad Air (3rd generation) with Cellular, 2 of 3 508
63.177 iPad Air (3rd generation) with Cellular, 3 of 3 509
63.178 iPad mini (5th generation), 1 of 3 510
63.179 iPad mini (5th generation), 2 of 3 511
63.180 iPad mini (5th generation), 3 of 3 512
63.181 iPad mini (5th generation) with Cellular, 1 of 3 513
63.182 iPad mini (5th generation) with Cellular, 2 of 3 514
63.183 iPad mini (5th generation) with Cellular, 3 of 3 515
63.184 iPad Pro 12.9-inch (3rd generation), 1 of 3 516
63.185 iPad Pro 12.9-inch (3rd generation), 2 of 3 517
63.186 iPad Pro 12.9-inch (3rd generation), 3 of 3 518
63.187 iPad Pro 11-inch (1st generation), 1 of 3 519
63.188 iPad Pro 11-inch (1st generation), 2 of 3 520
63.189 iPad Pro 11-inch (1st generation), 3 of 3 521
63.190 iPad Pro 12.9-inch (2nd generation) 522
63.191 iPad Pro 12.9-inch (2nd generation) with Cellular 523
63.192 iPad Pro 12.9-inch (2nd generation) Magnet/Hall Effect Sensors, 1 of 2 524
63.193 iPad Pro 12.9-inch (2nd generation) Magnet/Hall Effect Sensors, 2 of 2 525
63.194 iPad Pro 10.5-inch 526
63.195 iPad Pro 10.5-inch with Cellular 527
63.196 iPad Pro 10.5-inch Magnet/Hall Effect Sensors, 1 of 2 528
63.197 iPad Pro 10.5-inch Magnet/Hall Effect Sensors, 2 of 2 529
63.198 iPad (5th and 6th generation) with Cellular 530
63.199 iPad (5th and 6th generation) Magnet/Hall Effect Sensors, 1 of 2 531

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

63.200 iPad (5th and 6th generation) Magnet/Hall Effect Sensors, 2 of 2 532
63.201 iPad Pro 9.7-inch 533
63.202 iPad Pro 9.7-inch with Cellular 534
63.203 iPad Pro 9.7-inch Magnet/Hall Effect Sensors, 1 of 2 535
63.204 iPad Pro 9.7-inch Magnet/Hall Effect Sensors, 2 of 2 536
63.205 iPad Pro 12.9-inch (1st generation) 537
63.206 iPad Pro 12.9-inch (1st generation) with Cellular 538
63.207 iPad Pro 12.9-inch (1st generation) Magnet/Hall Effect Sensors, 1 of 2 539
63.208 iPad Pro 12.9-inch (1st generation) Magnet/Hall Effect Sensors, 2 of 2 540
63.209 iPad mini 4 541
63.210 iPad mini 4 with Cellular 542
63.211 iPad mini 4 Magnet/Hall Effect Sensors 543
63.212 iPad Air 2 544
63.213 iPad Air 2 with Cellular 545
63.214 iPad mini 3 and iPad mini 2 546
63.215 iPad mini 3 and iPad mini 2 with Cellular 547
63.216 iPad Air 548
63.217 iPad Air with Cellular 549
63.218 iPad mini 550
63.219 iPad mini with Cellular 551
63.220 iPad (4th generation) 552
63.221 iPad (4th generation) with Cellular 553
63.222 iPod touch (7th generation) and iPod touch (6th generation) 554
63.223 iPod touch (5th generation) 555
63.224 Apple Watch Ultra 3 & Apple Watch Ultra 2, 1 of 3 556
63.225 Apple Watch Ultra 3 & Apple Watch Ultra 2, 2 of 3 557
63.226 Apple Watch Ultra 3 & Apple Watch Ultra 2, 3 of 3 558
63.227 Apple Watch Series 11 & Apple Watch Series 10, 46 mm 559
63.228 Apple Watch Series 11 & Apple Watch Series 10, 42 mm 560
63.229 Apple Watch SE 3 & Apple Watch SE 2, 44 mm 561
63.230 Apple Watch SE 3 & Apple Watch SE 2, 40 mm 562
63.231 Apple Watch Series 9, 45 mm 563
63.232 Apple Watch Series 9, 41 mm 564
63.233 Apple Watch Ultra, 1 of 3 565
63.234 Apple Watch Ultra, 2 of 3 566
63.235 Apple Watch Ultra, 3 of 3 567
63.236 Apple Watch Series 8, 45 mm 568
63.237 Apple Watch Series 8, 41 mm 569
63.238 Apple Watch Series 7, 45 mm 570

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

63.239 Apple Watch Series 7, 41 mm 571
63.240 Apple Watch Series 6, 44 mm 572
63.241 Apple Watch Series 6, 40 mm 573
63.242 Apple Watch SE, 44 mm 574
63.243 Apple Watch SE, 40 mm 575
63.244 Apple Watch Series 5, 44 mm 576
63.245 Apple Watch Series 5, 40 mm 577
63.246 Apple Watch Series 5 Ceramic, 44 mm 578
63.247 Apple Watch Series 5 Ceramic, 40 mm 579
63.248 Apple Watch Series 4, 44 mm 580
63.249 Apple Watch Series 4, 40 mm 581
63.250 Apple Watch Series 3 Ceramic, 42 mm 582
63.251 Apple Watch Series 3 Ceramic, 38 mm 583
63.252 Apple Watch Series 3 Metal, 42 mm 584
63.253 Apple Watch Series 3 Metal, 38 mm 585
63.254 Apple Watch Series 2 Ceramic, 42 mm 586
63.255 Apple Watch Series 2 Ceramic, 38 mm 587
63.256 Apple Watch Series 2 Metal, 42 mm 588
63.257 Apple Watch Series 2 Metal, 38 mm 589
63.258 Apple Watch Series 1 and Apple Watch (1st generation), 42 mm 590
63.259 Apple Watch Series 1 and Apple Watch (1st generation), 38 mm 591
63.260 Apple Vision Pro, 1 of 8 592
63.261 Apple Vision Pro, 2 of 8 593
63.262 Apple Vision Pro, 3 of 8 594
63.263 Apple Vision Pro, 4 of 8 595
63.264 Apple Vision Pro, 5 of 8 596
63.265 Apple Vision Pro, 6 of 8 597
63.266 Apple Vision Pro, 7 of 8 598
63.267 Apple Vision Pro, 8 of 8 599
63.268 Apple Vision Pro Battery 600
63.269 Apple Vision Pro Audio Strap 601
63.270 ZEISS Optical Inserts, 1 of 4 602
63.271 ZEISS Optical Inserts, 2 of 4 603
63.272 ZEISS Optical Inserts, 3 of 4 604
63.273 ZEISS Optical Inserts, 4 of 4 605
63.274 MagSafe Charging Case for AirPods Pro 3, 1 of 3 606
63.275 MagSafe Charging Case for AirPods Pro 3, 2 of 3 607
63.276 MagSafe Charging Case for AirPods Pro 3, 3 of 3 608
63.277 AirPods Pro 3 609

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

63.278 Wireless Charging Case (USB-C) for AirPods 4, 1 of 3 610
63.279 Wireless Charging Case (USB-C) for AirPods 4, 2 of 3 611
63.280 Wireless Charging Case (USB-C) for AirPods 4, 3 of 3 612
63.281 AirPods 4 613
63.282 MagSafe Charging Case (USB-C) for AirPods Pro (2nd generation), 1 of 3 614
63.283 MagSafe Charging Case (USB-C) for AirPods Pro (2nd generation), 2 of 3 615
63.284 MagSafe Charging Case (USB-C) for AirPods Pro (2nd generation), 3 of 3 616
63.285 MagSafe Charging Case for AirPods Pro (2nd generation), 1 of 3 617
63.286 MagSafe Charging Case for AirPods Pro (2nd generation), 2 of 3 618
63.287 MagSafe Charging Case for AirPods Pro (2nd generation), 3 of 3 619
63.288 AirPods Pro (2nd generation) 620
63.289 MagSafe Charging Case for AirPods (3rd generation) 621
63.290 AirPods (3rd generation) 622
63.291 AirPods Max, 1 of 6 623
63.292 AirPods Max, 2 of 6 624
63.293 AirPods Max, 3 of 6 625
63.294 AirPods Max, 4 of 6 626
63.295 AirPods Max, 5 of 6 627
63.296 AirPods Max, 6 of 6 628
63.297 Wireless Charging Case for AirPods Pro (1st generation) 629
63.298 AirPods Pro (1st generation) 630
63.299 Wireless Charging Case for AirPods 631
63.300 AirPods (2nd generation) and AirPods (1st generation) 632
63.301 Apple MagSafe Charger (1 m) and Apple MagSafe Charger (2 m) 633
63.302 Apple MagSafe Charger 634
63.303 AirTag 635
63.304 Apple TV 4K (3rd generation) 636
63.305 Siri Remote (3rd generation) 637

Revision History 638
Added Content 638
Updated Content 638

Copyright © 2025 Apple Inc. All Rights Reserved.

Overview

1. Introduction

Note:
These Accessory Design Guidelines for Apple Devices ('Guidelines') are subject to the terms and conditions set forth on the final page of this document. By downloading, accessing, or otherwise utilizing these Guidelines, you agree to be bound by, and only utilize the Guidelines in accordance with, such terms and conditions.

These guidelines address:

- Physical compatibility with iPhone, iPad, Apple Watch, AirPods, Apple TV, and Apple Vision Pro.
- Using USB-C to connect to iPhone, iPad, and AirPods.
- Using Bluetooth to connect to iPhone, iPad, Apple Watch, Apple TV, Apple Vision Pro, and Mac computers.
- AC power adapters and battery packs compatible with iPhone, iPad, and AirPods.
- Qi wireless transmitters compatible with iPhone and AirPods.

Some aspects of accessory interaction are not addressed in this document and may require access to the Apple MFi Program (page 27) and the Accessory Interface Specification (page 27).

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

2. Requirements

The use of the words *shall*, *shall not*, *required*, *prohibited*, *should*, *should not*, *recommended*, *not recommended*, *may*, *optional*, and *deprecated* in a statement have the following meanings:

- *shall*, or *required* means the statement is an absolute requirement.
- *shall not* or *prohibited* means the statement is an absolute prohibition.
- *should* or *recommended* means the full implications shall be understood before choosing a different course.
- *should not* or *not recommended* means the full implications shall be understood before choosing this course.
- *may* or *optional* means the statement is truly optional, and its presence or absence cannot be assumed.
- *deprecated* means the statement is provided for historical purposes only and is equivalent to 'shall not'.

2.1 Developer Preview

Content labeled as *developer preview* has been reviewed for accuracy, but it is not final. Apple is supplying this content to help accessory developers plan for the adoption of the accessory interface features described herein. This information is subject to change, and accessories implemented according to this content shall be tested with final operating system software and final documentation.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

3. Terminology

3.1 Device

Device refers to an iPhone, iPad, or iPod.

iOS device refers to an iPhone or iPod running iOS.

iPadOS device refers to an iPad running iPadOS.

watchOS device refers to an Apple Watch running watchOS.

tvOS device refers to an Apple TV running tvOS.

Where appropriate, specific Apple product and operating system references will also be used.

3.2 Accessory

Accessory or *peer device* refers to any product connecting to a *device* using the interfaces described in this specification.

3.3 Component

A *component* is a functional unit or a constituent part of an accessory. Components interconnect and function as a part of a greater system. Examples include:

- Integrated circuits, microprocessors, flash memory, microphones, and speakers.
- Data transport interface, such as a Lightning connector, USB connector, or Bluetooth radio.
- Power sources, such as a battery or power supply.
- Human Interface Device (HID) Control Surface (page 26), such as a play/pause button.

A *component* may also refer to a group or collection, such as the keyboard portion of a keyboard/trackpad accessory.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

3.4 Control Surface

A *control surface* is a human interface device (HID) component enabling user interaction with an accessory. Examples include:

- Connectors
- Buttons
- Switches
- Rotary knobs
- Joysticks
- Touchscreens or touch-sensitive surfaces
- Microphones
- Motion/presence sensors

References to specific types of control surfaces such as buttons or switches are only applicable to those control surface types. If a requirement calls for a physical button to be implemented, a physical button shall be present.

3.5 Direct User Action

A *direct user action* is defined as user interaction with an accessory using a Control Surface (page 26). Examples include:

- Physical gestures, such as:
  - Attaching an accessory to a device.
  - Pressing a button.
  - Actuating a switch.
  - Turning a knob.
  - Interacting with a touchscreen.
  - Waving a hand.
  - Moving in/out of range (for wireless accessories).
- Voice input.

Accessories shall not autonomously perform user inputs unless explicitly authorized by the user.

3.6 Built-In Cable

A *built-in cable* is a cable with one end permanently attached to the accessory enclosure.

Copyright © 2025 Apple Inc. All Rights Reserved.

3.7 Apple MFi Program

The Apple MFi Program provides access to specifications, components, connectors, and other resources to create accessories capable of communicating with devices.

See https://mfi.apple.com for more information.

3.8 Accessory Interface Specification

The *Accessory Interface Specification* is available through the Apple MFi Program (page 27).

Use of some features requires accessory developers to be a member of the program and to integrate specific MFi hardware into the accessory.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Accessories

4. All Accessories

4.1 Scratches and Damage

Accessories shall not scratch or damage any device.

Accessories with abrasive surfaces and sharp edges (such as hard plastic, metal, or glass) shall not contact the active area of the device display.

4.2 Compliance Testing

Accessories shall not assume evidence of functionality when attached to a device means the accessory is specification compliant. Such an approach does not account for future devices or software releases, and runs a high risk of dependence on undocumented device behavior which is subject to change at any time.

If available, accessories should validate their design and implementation using the recommended test procedures for all supported features.

4.3 USB-B Receptacles

Accessories integrating USB-B receptacles shall comply with *USB Battery Charging Specification –Release 1.2*.

4.4 User Supplied Cables and AC Power Adapters

Accessories intended for use with user-supplied cables and/or AC power adapters shall be designed to work with any cables, AC Power Adapters (page 93), or Battery Packs (page 96) compliant with this specification, including Apple branded cables and AC power adapters. Such accessories shall not declare compatibility with only Apple branded USB cables or AC power adapters.

This compatibility requirement applies to all aspects of user-supplied cables and power adapters. For example:

Copyright © 2025 Apple Inc. All Rights Reserved.

- Connector receptacles on accessories shall accommodate all specification-compliant connector overmolds, and any accessory opening surrounding the device receptacle shall provide sufficient clearance for specification-compliant connector overmolds.
- Accessories shall work with all specification-compliant cables in regards to electrical DCR and SI.

Such accessories shall be tested with a wide variety of specification-compliant cables (including various lengths of the same cable if applicable) and AC power adapters during accessory development, in addition to Apple branded cables and AC power adapters.

4.5 TDMA Noise

GSM phones emit radiated and conducted RF noise, which can produce time division multiple access (TDMA) sounds from audio outputs. Accessories shall minimize coupling of audible interference from the device (commonly known as *TDMA noise* or *chopper noise*) into an accessory's electronics.

4.6 Attachments

Accessories shall remain compliant with the specification when connected to any attachments designed for the accessory.

Examples of accessory attachments include, but are not limited to:

- Car or desk mounts for a case.
- Wireless charging mats for a dongle or case.
- Detachable barcode scanners/credit card readers for a dock.

4.7 Magnetic Interference

Unless otherwise specified, Apple recommends avoiding the use of magnets and metal components in accessories.

Accessories claiming compatibility with a device with a digital compass (magnetometer) shall minimize interference with the digital compass and shall not repeatedly trigger compass recalibration.

Accessories claiming compatibility with a device with autofocus (AF) and/or optical image stabilization (OIS) shall not affect the operation of those features.

Devices featuring optical image stabilization:

- iPhone 17 Pro Max
- iPhone 17 Pro

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- iPhone 17
- iPhone Air
- iPhone 16e
- iPhone 16 Pro Max
- iPhone 16 Pro
- iPhone 16 Plus
- iPhone 16
- iPhone 15 Pro Max
- iPhone 15 Pro
- iPhone 15 Plus
- iPhone 15
- iPhone 14 Pro Max
- iPhone 14 Pro
- iPhone 14 Plus
- iPhone 14
- iPhone SE (3rd generation)
- iPhone 13 Pro Max
- iPhone 13 Pro
- iPhone 13
- iPhone 13 mini
- iPhone 12 Pro Max
- iPhone 12 Pro
- iPhone 12
- iPhone 12 mini
- iPhone SE (2nd generation)
- iPhone 11 Pro Max
- iPhone 11 Pro
- iPhone 11
- iPhone XS Max
- iPhone XS
- iPhone XR
- iPhone X
- iPhone 8 Plus
- iPhone 8
- iPhone 7 Plus
- iPhone 7
- iPhone 6s Plus
- iPhone 6 Plus
- iPad Pro 12.9-inch (2nd generation)
- iPad Pro 10.5-inch

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

4.8 Radio Frequency (RF) Performance

4.8.1 Materials and Coatings

Accessories should avoid use of:

- Metals
- Conductive materials or coatings
- Materials with high dielectric (permittivity >5 F/m)

Such materials absorb radio frequency energy and may impair or degrade the performance of antennas for cellular communication, GPS, Wi-Fi, Bluetooth, and NFC.

Examples include, but are not limited to:

- Steel, aluminum, magnesium, titanium, etc.
- Plastics with any carbon content, glass content, or metallic plating
- Metallic paints
- Black paints with high carbon loading
- White paints with high titanium dioxide loading
- Metallic Physical Vapor Deposition (PVD) coatings

4.8.2 Antenna Keep-Out

Antenna keep-out regions can be found in Device Dimensional Drawings (page 328).

Accessory Materials and Coatings (page 32) which absorb radio frequency energy located in the antenna keep-out region have a higher risk of degrading device's wireless performance.

4.8.3 Over The Air (OTA) Transmission/Reception

Accessories shall not excessively degrade a device's RF transmission efficiency. This can be quantified by measuring Total Radiated Power (TRP) across all of the device's operating bands.

Accessories shall not excessively degrade a device's RF reception sensitivity. This can be quantified by measuring Effective Isotropic Sensitivity (EIS) across all of the device's operating bands.

Accessories may have a higher risk of excessively degrading device's RF performance if they:

- Contain magnets.
- Intrude on device Antenna Keep-Out (page 32) zones.
- Contain active electronic circuitry, such as:
  - Bluetooth radios.
  - Switched-mode power supplies.
  - High speed data interfaces.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Accessory configurations shall be taken into account when designing for maximum RF compatibility. Examples include, but are not limited to:

- Accessory on/off.
- Accessory open/closed.
- Attachments (page 30) present/not present.

Good design practices shall be followed to minimize emissions and maximize RF compatibility. These include, but are not limited to:

- Shielding digital circuitry and clock signals.
- Minimizing radiation from digital interfaces.
- Decoupling high frequency signals and power supplies.
- Filtering off-board signals.
- Maintaining ground plane circuit board integrity.
- Minimizing current loop areas.
- Ensuring proper cable shielding terminations.

4.8.4 Specific Absorption Rate (SAR)

A list of labs performing SAR testing with devices is available through the Apple MFi Program (page 27).

4.8.5 Near Field Communication (NFC)

Accessories shall not degrade a device's NFC transaction performance.

Accessories may have a higher risk of degrading device's NFC transaction performance if they intrude on device Antenna Keep-Out (page 32) zones.

Devices featuring NFC:

- iPhone 17 Pro Max
- iPhone 17 Pro
- iPhone 17
- iPhone Air
- iPhone 16e
- iPhone 16 Pro Max
- iPhone 16 Pro
- iPhone 16 Plus
- iPhone 16
- iPhone 15 Pro Max
- iPhone 15 Pro
- iPhone 15 Plus
- iPhone 15

Copyright © 2025 Apple Inc. All Rights Reserved.

- iPhone 14 Pro Max
- iPhone 14 Pro
- iPhone 14 Plus
- iPhone 14
- iPhone SE (3rd generation)
- iPhone 13 Pro Max
- iPhone 13 Pro
- iPhone 13
- iPhone 13 mini
- iPhone 12 Pro Max
- iPhone 12 Pro
- iPhone 12
- iPhone 12 mini
- iPhone SE (2nd generation)
- iPhone 11 Pro Max
- iPhone 11 Pro
- iPhone 11
- iPhone XS Max
- iPhone XS
- iPhone XR
- iPhone X
- iPhone 8 Plus
- iPhone 8
- iPhone 7 Plus
- iPhone 7
- iPhone SE
- iPhone 6s Plus
- iPhone 6s
- iPhone 6 Plus
- iPhone 6

4.9 Thermal Management

The accessory's supported temperature range shall be greater than or equal to the published temperature ranges of every device the accessory claims compatibility with.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

4.10 Tripod Connections

Tripod connections shall comply with *ISO 1222:2010, Photography — Tripod connections*, see https://www.iso.org/standard/55918.html.

4.11 Anthropometric Considerations

Children and people with smaller hands (5th percentile), as well as people with larger hands (95th percentile) should all be considered during the accessory design process.

Apple recommends using design resources such as:

- AnthroKids (https://math.nist.gov/~SRessler/anthrokids/).
- U.S. Army Anthropometry Survey (http://mreed.umtri.umich.edu/mreed/downloads.html#ansur2).
- Civilian American and European Surface Anthropometry Resource (CAESAR).

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

5. Cases

Cases are accessories substantially enclosing devices.

The requirements shall be applied to each component separately for cases with multiple user-detachable components substantially enclosing the device.

5.1 Product Design

A well-designed case will securely house a device without interfering with the device's operation. Significant factors in mechanical design include access to the device's sensors, controls, and connectors. See Device Dimensional Drawings (page 328).

5.1.1 Device Protection

Cases shall protect the device from a 1 m drop onto a hard paved surface in any orientation.

Exposed glass on the device shall not come within 0.85 mm of a flat surface, such as a table or floor, in any orientation when the case is attached. Ideally the glass should not come within 1.00 mm. Device protection should be achieved by creating features around the exposed glass to keep it away from the flat surface.

Care should be given to the design of the bottom of the case to achieve both device protection and provide access to device speakers, microphones, and connectors. For example, the bottom of iPhone X cases should:

- Not have an opening wider than 50 mm, see dimension 'A' in Figure 5-1 (page 37).
- Be made of polycarbonate (PC) at least 1.15 mm thick, see dimension 'B' in Figure 5-1 (page 37).

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 5-1 Device protection



5.1.2 Access to Inputs and Interconnects

Cases shall readily permit user access to inputs and interconnects.

5.1.2.1 Access to Controls

Cases shall readily permit user access and operation of the device's mechanical controls, such as:

- Volume buttons.
- Camera Control.
- Side/Top button.
- Action button.
- Ring/Silent switch.
- Home button.
- Touch ID sensor.

5.1.2.2 Access to the Camera Control

Cases for devices with Camera Control shall accommodate the following gestures across the entire surface of the Camera Control:

- Click.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- Light press.
- Slide.
- Swipe.

The case shall either:

- Have an opening meeting the keep-out defined in the Device Dimensional Drawings (page 328).
- Integrate the Camera Control Case Interface (page 38).

The opening shall be large with smooth edges and a wide angle designed to accommodate:

- Various grip styles, including:
  - Portrait orientation, when held with either the right or left hand.
  - Landscape orientation, with the Camera Control at the top, when held with either one or two hands.
- Diverse hand and finger sizes, see Anthropometric Considerations (page 35).
- Diverse finger nail lengths, including nails extending beyond the tip of the finger.

The opening should not have sharp or hard edges causing the user to experience finger discomfort when engaging with the Camera Control.

5.1.2.2.1 Camera Control Case Interface

Cases may integrate their own Camera Control case interface.

A Camera Control case interface shall have a(n):

- Bottom layer consisting of 6 to 24 copper pads connecting to the Camera Control, see Figure 5-2 (page 39) for a 6-pad example.
- Top layer consisting of 6 to 24 copper pads, see Figure 5-2 (page 39) for a 6-pad example.
- PCB-like material to connect the bottom and top layers and to achieve proper thickness for the case design.
- Even number of copper pads.
- Spacing between the copper pads (pad gap) of at least 0.15 mm.

The outer dimensions of the user-facing side of the button may be sized differently depending on the case design.

Figure 5-2 Example 6-button Camera Control case interface top and bottom layers



Table 5-1 Example Camera Control Top Button Dimensions

Device	Button Length	Button Width	Pads 1,6 Length	Pads 2-5 Length	Pad Width	Pad Gap
All devices except iPhone Air	16.83 mm	2.77 mm	2.68 mm	2.34 mm	2.15 mm	0.30 mm
iPhone Air	16.83 mm	2.27 mm	2.68 mm	2.34 mm	1.55 mm	0.30 mm

Table 5-2 Example Camera Control Bottom Button Dimensions

Device	Button Length	Button Width	Pad Length	Pad Width	Pad Gap
All devices except iPhone Air	16.53 mm	2.47 mm	2.35 mm	1.55 mm	0.30 mm
iPhone Air	16.53 mm	1.97 mm	2.35 mm	1.05 mm	0.30 mm

Camera Control case interface shall:

- Have a top cap, such as a sapphire crystal. Plastic top caps will cause Camera Control to fail due to capacitive signal loss.
- Have a flatness of less than 25 µm where it makes contact with the Camera Control.
- Have a tilt of less than 160 µm in all directions.
- Have a static (no user contact) misalignment center to center along:
  - The width of the Camera Control of less than 160 µm.
  - The length of the Camera Control of less than 190 µm.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- Have a dynamic (user contact) misalignment center to center in all directions of less than 130 µm.
- Have a maximum stiffness of 180 gf/mm.
  - Target stiffness should be 90 gf/mm throughout its range of travel.
- Be designed to maintain contact with the Camera Control across all copper pads and shall:
  - Have a case applied force (preload) of 45 gf or less at maximum button offset.
  - Not trigger a light press when the area around the Camera Control is squeezed up to 1050 gf.
  - Not have an air gap greater than 50 µm to the Camera Control. Apple recommends no air gap.
- Have a capacitance greater than 0.362 pF for pads P1 and P6.
- Have a capacitance greater than 0.432 pF for pads P2, P3, P4, and P5.
- Have a sheet resistance for inks and coatings greater than 50 G-Ω/sq.

5.1.2.2.2 User Study

A study evaluating the usability and comfort of the Camera Control by end users shall be completed. Users should be able to perform all gestures without discomfort from pressing into the case material surrounding the Camera Control.

The study population shall include:

- Various hand sizes as defined in Anthropometric Considerations (page 35).
- Various finger shapes, taking into account:
  - Taper.
  - Flatness.
- Various finger nail lengths:
  - Shorter than the fingertip.
  - At the fingertip.
  - Slightly longer than the fingertip.
  - Much longer than the fingertip.

The user study shall be performed using the Gestures (page 74) portion of the Camera Control (page 74) test.

5.1.2.3 Access to the USB-C Connector

Cases shall provide easy access to a device's USB-C connector, if present.

The USB-C receptacle keep-out:

- Shall be at least 12.35 mm by 6.50 mm.
- Should be at least 12.45 mm by 6.60 mm with full radii rounded edges for the greatest compatibility with the widest variety of cables and docks, see USB-C receptacle accessory keep-out (page 315).

USB-C connector openings shall be designed with enough margin to compensate for shifting or dimensional changes of the case material.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

5.1.2.4 Access to the Lightning Connector

Cases shall provide easy access to a device's Lightning connector, if present.

The Lightning receptacle keep-out:

- Shall be at least 12.05 mm by 6.30 mm with full radii rounded edges.
- Should be at least 13.65 mm by 6.85 mm for the greatest compatibility with the widest variety of cables and docks, see Figure 5-3 (page 41).

Figure 5-3 Lightning Receptacle (C37) keep-out



Lightning connector openings shall be designed with enough margin to compensate for shifting or dimensional changes of the case material.

5.1.2.5 Access to the Headset Jack

Cases shall provide easy access to a device's headset jack, if present.

The headset jack keep-out:

- Shall be at least 6.0 mm in diameter and at most 14.0 mm deep.
- Should be at least 6.5 mm in diameter and at most 10.0 mm deep for the best compatibility with a range of headsets.

Headset jack openings shall be designed with enough margin to compensate for shifting or dimensional changes of the case material.

5.1.2.6 Touchscreen

Cases should not have edges trapping water on the touchscreen when the device is held at a 30° angle relative to the horizon.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Cases shall allow a 120° opening, see Figure 5-4 (page 42), along the edges of a touchscreen's active area to ensure compatibility with touchscreen features. See Device Dimensional Drawings (page 328) for active areas.

Figure 5-4 Touchscreen keep-out angle



5.1.2.7 Edge Swipe Gestures

Users shall be able to easily use edge swipe gestures.

Examples of such gestures include, but are not limited to:

- Swipe in from the top edge for Control Center or Notification Center.
- Swipe in from the bottom edge for Home, App Switcher, or Reachability.
- Swipe in from the left edge in Messages or Mail to go back from a conversation.

5.1.2.8 Cover Glass Contact

Cases should not contact the cover glass of:

- iPhone SE (3rd generation)
- iPhone SE (2nd generation)
- iPhone 11 Pro Max
- iPhone 11 Pro
- iPhone 11
- iPhone XS Max
- iPhone XS

Copyright © 2025 Apple Inc. All Rights Reserved.

- iPhone XR
- iPhone X
- iPhone 8 Plus
- iPhone 8
- iPhone 7 Plus
- iPhone 7
- iPhone 6s Plus
- iPhone 6s
- iPhone 6 Plus
- iPhone 6

5.1.3 Dock Compatibility

The distance from bottom of the device to the outside of a case should not exceed 1.8 mm for compatibility with docks.

5.1.4 Wireless Power

Cases claiming compatibility with MagSafe or Qi wireless power 2.0 or later, see Device Power (Inductive) (page 182), shall:

- Integrate a MagSafe Case Magnet Array (page 194).
- Not have rear pockets or holders for credit cards, RFID cards, or other similar items. Cards may be damaged and/or impact wireless charging performance.

5.2 Acoustics

Cases shall not impair or degrade the acoustic performance of a device.

5.2.1 Call Quality

Cases shall not impair or degrade the user experience making and receiving audio calls over a cellular network or audio/video calls using FaceTime in both handset and speakerphone modes. Cases should not change the frequency response of the speakers or microphones. In addition, the user should not hear distortion or echo resulting from using the case.

Cases shall not obstruct microphones during a phone call. Occluding microphones can result in call quality degradation.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

5.2.2 Speaker to Microphone Coupling

Cases shall not facilitate the conduction of sound from speakers to microphones. Such sound conduction may cause echoing in phone calls.

5.2.3 Speaker/Microphone Openings

Device speaker/microphone port locations vary from model to model, see Device Dimensional Drawings (page 328).

5.2.3.1 Thin Cases (≤2.25 mm)

Microphone/speaker openings in thin cases should:

- Be offset at least 2.0 mm from the edge of any device speaker/microphone port.
- Be at most 1.5 mm thick along their inner diameter.
- Have a maximum 45° incoming angle to their inner diameter.
- Maintain a proper seal against the device between speaker/microphone ports.

Figure 5-5 Microphone/speaker opening recommendations for thin cases



5.2.3.2 Thick Cases (>2.25 mm)

Speaker and microphone openings should be channeled independently and without interruption to/from the outside surface of a thick case.

Figure 5-6 Thick case acoustic channels



Thick cases should maximize exit separation between speaker and microphone channels.

Figure 5-7 Thick case microphone and speaker exit separation



Thick case channels may act as a resonance chamber and detune microphone/speaker frequency response. The resulting frequency response may vary according to channel size/shape.

If a thick case does not maintain a proper seal against the device between microphone/speaker channels, the case itself may become an acoustic chamber.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 5-8 Improper thick case seal



5.3 Ambient Light Sensor and Proximity Sensor

Ambient light sensor and proximity sensor locations for various devices are illustrated in the Device Dimensional Drawings (page 328). Some drawings indicate sensor keep-out areas.

5.4 Haptics

Cases should not cause a substantial change in the feel of the device's haptic feedback.

5.5 Magnetic Interference

Cases shall not interfere with the device's:

- Magnetic compass.
- Rear camera autofocus (AF).
- Rear camera optical image stabilization (OIS), if present.
- Front camera autofocus, if present.

See Magnetic Interference (page 30) for additional details.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

5.6 Touch ID

Cases shall not inhibit use of the device's Touch ID sensor. Touch ID sensor keep-outs are indicated in the Device Dimensional Drawings (page 328).

Cases overlaying the sensor may cause users to have difficulty using Touch ID.

5.7 Camera

The camera field of view (FOV) and the illumination provided by the flash are designed for each devices' camera. It is exceptionally important manufacturers consult Device Dimensional Drawings (page 328) for each device, and shall not assume any parameters are shared between devices.

Images from the camera may be affected by the geometry, color, and surface finish of the case, particularly when using a flash. Camera opening trim should be designed to avoid reflecting light into the camera.

5.7.1 Geometry

The camera lens FOV shall not be blocked. Making opening dimensions too small around the camera and flash may block the lens FOV and the illumination from the flash. Blocking the FOV may cause vignetting in the image, where one or more corners of the image are darker than the center. Blocking marginal rays just outside the lens FOV may also reduce the sharpness and contrast of the image. Blocking flash illumination may cause haze in the image, resulting in reduced contrast. See Device Dimensional Drawings (page 328) for camera keep-outs.

Case openings shall not be designed in a manner directing stray light into the camera lens. If the opening is too narrow or too steep, it may reflect light into the camera lens, washing out the image or adding unwanted color casting. Adding a chamfer to the opening trim near the camera may help direct stray light away from the camera lens. When the device includes a flash, a narrow or steep opening may reflect light from the camera and flash opening back into the camera lens. This may cause images to appear washed out or cause unwanted artifacts. Designers should also ensure mechanical keep-outs as outlined in the Device Dimensional Drawings (page 328) are maintained with worst-case X-Y placement tolerances to minimize the risk of image haze.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

5.7.2 Color

Light reflected from a case may carry the color of the case. Black material or black coatings may help avoid color bleeding into the camera lens from an external light source or the flash. The darker the color the less likely light from a flash or external source may be reflected off the case and into the camera lens. Apple recommends a semi-gloss black material or coating around the camera and flash openings.

5.7.3 Surface Finish

Matte or diffuse materials scatter light in all directions increasing the likelihood light from the flash or other strong light sources may be reflected into camera lenses. Semi-gloss materials may direct light away from the camera lens.

5.7.4 Image Degradation Examples

Figure 5-9 Sample image degradation by image blocking in an ambient condition



Reference Degraded

Figure 5-10 Sample image degradation by color shift through accessory with strong color



Reference Degraded

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 5-11 Sample image degradation by flash interference



5.8 Reliability

Cases shall be tested to verify they will withstand long-term use under typical use conditions, and will not impair, functionally degrade a device, cause Scratches and Damage (page 29) to the device or its immediate surroundings, or adversely affect the user.

5.8.1 Device Insertion and Removal

Cases shall hold the device securely while permitting easy insertion and removal. A case shall not cause Scratches and Damage (page 29) to the device by the repeated insertion and removal of the device from the case under conditions representative of long-term use in a variety of environments.

5.8.2 Colorfastness

Dyes, inks, or coatings in or on the case shall not transfer or bleed color onto either the device or user, particularly while the case is in contact with common substances such as water, hand sanitizer, sunscreen or lotions.

5.9 Environmental

Cases shall comply with applicable environmental regulations for the regions in which such accessories are to be sold, as well as applicable substance or material restrictions including:

- Organic tin compounds, PFOS, PFOA, phthalates, azo dyes, polybrominated biphenyls (PBBs) and PAHs, per requirements of the EU REACh regulation EC 1907/2006.
- Nickel leach rate on surfaces in prolonged skin contact, per requirements of the EU REACh regulation EC 1907/2006.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- Cadmium, lead, hexavalent chromium, and nickel, per requirements of EU Directive 2009/48/EC.
- Natural rubber latex, per requirements of EU Directive EC 93/42/EEC.
- Dimethylfumarate (DMFu), per requirements of EU Regulation 412/2012.
- pH and Formaldehyde, per requirements of China GB 18401 for textiles and China GB 20400 for leather.
- Endangered species of flora and fauna in products or packaging (US Lacey Act).
- Polybrominated diphenyl ethers (PBDE).
- Compliance with California proposition 65, as applicable.

5.10 Verification

5.10.1 Device Models

Case testing procedures vary depending on the device they enclose.

5.10.1.1 iPhone 17 Pro Max

Table 5-3 iPhone 17 Pro Max case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 17 Pro Max	
Camera Control (page 74)	iPhone 17 Pro Max	
Haptics (page 75)	iPhone 17 Pro Max	
Image Quality (page 76)	iPhone 17 Pro Max	Silver model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 17 Pro Max	
Near-Field Communication (NFC) (page 80)	iPhone 17 Pro Max	
Acoustics (page 82)	iPhone 17 Pro Max	
MagSafe Case Magnet Array (page 208)	iPhone 17 Pro Max	Cases supporting MagSafe only.

5.10.1.2 iPhone 17 Pro

Table 5-4 iPhone 17 Pro case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 17 Pro	
Camera Control (page 74)	iPhone 17 Pro	
Haptics (page 75)	iPhone 17 Pro	
Image Quality (page 76)	iPhone 17 Pro	Silver model only.

Copyright © 2025 Apple Inc. All Rights Reserved.

Test	Using	Notes
Autofocus & Optical Image Stabilization (page 80)	iPhone 17 Pro	
Near-Field Communication (NFC) (page 80)	iPhone 17 Pro	
Acoustics (page 82)	iPhone 17 Pro	
MagSafe Case Magnet Array (page 208)	iPhone 17 Pro	Cases supporting MagSafe only.

5.10.1.3 iPhone 17

Table 5-5 iPhone 17 case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 17	
Camera Control (page 74)	iPhone 17	
Haptics (page 75)	iPhone 17	
Image Quality (page 76)	iPhone 17	White model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 17	
Near-Field Communication (NFC) (page 80)	iPhone 17	
Acoustics (page 82)	iPhone 17	
MagSafe Case Magnet Array (page 208)	iPhone 17	Cases supporting MagSafe only.

5.10.1.4 iPhone Air

Table 5-6 iPhone Air case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone Air	
Camera Control (page 74)	iPhone Air	
Haptics (page 75)	iPhone Air	
Image Quality (page 76)	iPhone Air	Cloud White model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone Air	
Near-Field Communication (NFC) (page 80)	iPhone Air	
Acoustics (page 82)	iPhone Air	
MagSafe Case Magnet Array (page 208)	iPhone Air	Cases supporting MagSafe only.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

5.10.1.5 iPhone 16e

Table 5-7 iPhone 16e case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 16e	
Haptics (page 75)	iPhone 16e	
Image Quality (page 76)	iPhone 16e	White model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 16e	
Near-Field Communication (NFC) (page 80)	iPhone 16e	
Acoustics (page 82)	iPhone 16e	

5.10.1.6 iPhone 16 Pro Max

Table 5-8 iPhone 16 Pro Max case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 16 Pro Max	
Camera Control (page 74)	iPhone 16 Pro Max	
Haptics (page 75)	iPhone 16 Pro Max	
Image Quality (page 76)	iPhone 16 Pro Max	White Titanium model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 16 Pro Max	
Near-Field Communication (NFC) (page 80)	iPhone 16 Pro Max	
Acoustics (page 82)	iPhone 16 Pro Max	
MagSafe Case Magnet Array (page 208)	iPhone 16 Pro Max	Cases supporting MagSafe only.

5.10.1.7 iPhone 16 Pro

Table 5-9 iPhone 16 Pro case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 16 Pro	
Camera Control (page 74)	iPhone 16 Pro	
Haptics (page 75)	iPhone 16 Pro	
Image Quality (page 76)	iPhone 16 Pro	White Titanium model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 16 Pro	
Near-Field Communication (NFC) (page 80)	iPhone 16 Pro	
Acoustics (page 82)	iPhone 16 Pro	
MagSafe Case Magnet Array (page 208)	iPhone 16 Pro	Cases supporting MagSafe only.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

5.10.1.8 iPhone 16 Plus

Table 5-10 iPhone 16 Plus case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 16 Plus	
Camera Control (page 74)	iPhone 16 Plus	
Haptics (page 75)	iPhone 16 Plus	
Image Quality (page 76)	iPhone 16 Plus	White model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 16 Plus	
Near-Field Communication (NFC) (page 80)	iPhone 16 Plus	
Acoustics (page 82)	iPhone 16 Plus	
MagSafe Case Magnet Array (page 208)	iPhone 16 Plus	Cases supporting MagSafe only.

5.10.1.9 iPhone 16

Table 5-11 iPhone 16 case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 16	
Camera Control (page 74)	iPhone 16	
Haptics (page 75)	iPhone 16	
Image Quality (page 76)	iPhone 16	White model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 16	
Near-Field Communication (NFC) (page 80)	iPhone 16	
Acoustics (page 82)	iPhone 16	
MagSafe Case Magnet Array (page 208)	iPhone 16	Cases supporting MagSafe only.

5.10.1.10 iPhone 15 Pro Max

Table 5-12 iPhone 15 Pro Max case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 15 Pro Max	
Haptics (page 75)	iPhone 15 Pro Max	
Image Quality (page 76)	iPhone 15 Pro Max	White Titanium model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 15 Pro Max	

Copyright © 2025 Apple Inc. All Rights Reserved.

Test	Using	Notes
Near-Field Communication (NFC) (page 80)	iPhone 15 Pro Max	
Acoustics (page 82)	iPhone 15 Pro Max	
MagSafe Case Magnet Array (page 208)	iPhone 15 Pro Max	Cases supporting MagSafe only.

5.10.1.11 iPhone 15 Pro

Table 5-13 iPhone 15 Pro case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 15 Pro	
Haptics (page 75)	iPhone 15 Pro	
Image Quality (page 76)	iPhone 15 Pro	White Titanium model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 15 Pro	
Near-Field Communication (NFC) (page 80)	iPhone 15 Pro	
Acoustics (page 82)	iPhone 15 Pro	
MagSafe Case Magnet Array (page 208)	iPhone 15 Pro	Cases supporting MagSafe only.

5.10.1.12 iPhone 15 Plus

Table 5-14 iPhone 15 Plus case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 15 Plus	
Haptics (page 75)	iPhone 15 Plus	
Image Quality (page 76)	iPhone 15 Plus	Blue model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 15 Plus	
Near-Field Communication (NFC) (page 80)	iPhone 15 Plus	
Acoustics (page 82)	iPhone 15 Plus	
MagSafe Case Magnet Array (page 208)	iPhone 15 Plus	Cases supporting MagSafe only.

5.10.1.13 iPhone 15

Table 5-15 iPhone 15 case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 15	

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Test	Using	Notes
Haptics (page 75)	iPhone 15	
Image Quality (page 76)	iPhone 15	Blue model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 15	
Near-Field Communication (NFC) (page 80)	iPhone 15	
Acoustics (page 82)	iPhone 15	
MagSafe Case Magnet Array (page 208)	iPhone 15	Cases supporting MagSafe only.

5.10.1.14 iPhone 14 Pro Max

Table 5-16 iPhone 14 Pro Max case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 14 Pro Max	
Haptics (page 75)	iPhone 14 Pro Max	
Image Quality (page 76)	iPhone 14 Pro Max	Silver model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 14 Pro Max	
Near-Field Communication (NFC) (page 80)	iPhone 14 Pro Max	
Acoustics (page 82)	iPhone 14 Pro Max	
MagSafe Case Magnet Array (page 208)	iPhone 14 Pro Max	Cases supporting MagSafe only.

5.10.1.15 iPhone 14 Pro

Table 5-17 iPhone 14 Pro case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 14 Pro	
Haptics (page 75)	iPhone 14 Pro	
Image Quality (page 76)	iPhone 14 Pro	Silver model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 14 Pro	
Near-Field Communication (NFC) (page 80)	iPhone 14 Pro	
Acoustics (page 82)	iPhone 14 Pro	
MagSafe Case Magnet Array (page 208)	iPhone 14 Pro	Cases supporting MagSafe only.

Copyright © 2025 Apple Inc. All Rights Reserved.

5.10.1.16 iPhone 14 Plus

Table 5-18 iPhone 14 Plus case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 14 Plus	
Haptics (page 75)	iPhone 14 Plus	
Image Quality (page 76)	iPhone 14 Plus	Starlight model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 14 Plus	
Near-Field Communication (NFC) (page 80)	iPhone 14 Plus	
Acoustics (page 82)	iPhone 14 Plus	
MagSafe Case Magnet Array (page 208)	iPhone 14 Plus	Cases supporting MagSafe only.

5.10.1.17 iPhone 14

Table 5-19 iPhone 14 case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 14	
Haptics (page 75)	iPhone 14	
Image Quality (page 76)	iPhone 14	Starlight model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 14	
Near-Field Communication (NFC) (page 80)	iPhone 14	
Acoustics (page 82)	iPhone 14	
MagSafe Case Magnet Array (page 208)	iPhone 14	Cases supporting MagSafe only.

5.10.1.18 iPhone 13 Pro Max

Table 5-20 iPhone 13 Pro Max case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 13 Pro Max	
Haptics (page 75)	iPhone 13 Pro Max	
Image Quality (page 76)	iPhone 13 Pro Max	Silver model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 13 Pro Max	
Near-Field Communication (NFC) (page 80)	iPhone 13 Pro Max	
Acoustics (page 82)	iPhone 13 Pro Max	

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Test	Using	Notes
MagSafe Case Magnet Array (page 208)	iPhone 13 Pro Max	Cases supporting MagSafe only.

5.10.1.19 iPhone 13 Pro

Table 5-21 iPhone 13 Pro case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 13 Pro	
Haptics (page 75)	iPhone 13 Pro	
Image Quality (page 76)	iPhone 13 Pro	Silver model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 13 Pro	
Near-Field Communication (NFC) (page 80)	iPhone 13 Pro	
Acoustics (page 82)	iPhone 13 Pro	
MagSafe Case Magnet Array (page 208)	iPhone 13 Pro	Cases supporting MagSafe only.

5.10.1.20 iPhone 13

Table 5-22 iPhone 13 case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 13	
Haptics (page 75)	iPhone 13	
Image Quality (page 76)	iPhone 13	Starlight model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 13	
Near-Field Communication (NFC) (page 80)	iPhone 13	
Acoustics (page 82)	iPhone 13	
MagSafe Case Magnet Array (page 208)	iPhone 13	Cases supporting MagSafe only.

5.10.1.21 iPhone 13 mini

Table 5-23 iPhone 13 mini case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 13 mini	
Haptics (page 75)	iPhone 13 mini	
Image Quality (page 76)	iPhone 13 mini	Starlight model only.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Test	Using	Notes
Autofocus & Optical Image Stabilization (page 80)	iPhone 13 mini	
Near-Field Communication (NFC) (page 80)	iPhone 13 mini	
Acoustics (page 82)	iPhone 13 mini	
MagSafe Case Magnet Array (page 208)	iPhone 13 mini	Cases supporting MagSafe only.

5.10.1.22 iPhone 12 Pro Max

Table 5-24 iPhone 12 Pro Max case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 12 Pro Max	
Haptics (page 75)	iPhone 12 Pro Max	
Image Quality (page 76)	iPhone 12 Pro Max	Silver model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 12 Pro Max	
Near-Field Communication (NFC) (page 80)	iPhone 12 Pro Max	
Acoustics (page 82)	iPhone 12 Pro Max	
MagSafe Case Magnet Array (page 208)	iPhone 12 Pro Max	Cases supporting MagSafe only.

5.10.1.23 iPhone 12 Pro

Table 5-25 iPhone 12 Pro case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 12 Pro	
Haptics (page 75)	iPhone 12 Pro	
Image Quality (page 76)	iPhone 12 Pro	Silver model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 12 Pro	
Near-Field Communication (NFC) (page 80)	iPhone 12 Pro	
Acoustics (page 82)	iPhone 12 Pro	
MagSafe Case Magnet Array (page 208)	iPhone 12 Pro	Cases supporting MagSafe only.

Copyright © 2025 Apple Inc. All Rights Reserved.

5.10.1.24 iPhone 12

Table 5-26 iPhone 12 case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 12	
Haptics (page 75)	iPhone 12	
Image Quality (page 76)	iPhone 12	Silver model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 12	
Near-Field Communication (NFC) (page 80)	iPhone 12	
Acoustics (page 82)	iPhone 12	
MagSafe Case Magnet Array (page 208)	iPhone 12	Cases supporting MagSafe only.

5.10.1.25 iPhone 12 mini

Table 5-27 iPhone 12 mini case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 12 mini	
Haptics (page 75)	iPhone 12 mini	
Image Quality (page 76)	iPhone 12 mini	Silver model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 12 mini	
Near-Field Communication (NFC) (page 80)	iPhone 12 mini	
Acoustics (page 82)	iPhone 12 mini	
MagSafe Case Magnet Array (page 208)	iPhone 12 mini	Cases supporting MagSafe only.

5.10.1.26 iPhone 11 Pro Max

Table 5-28 iPhone 11 Pro Max case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 11 Pro Max	
Haptics (page 75)	iPhone 11 Pro Max	
Image Quality (page 76)	iPhone 11 Pro Max	Silver model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 11 Pro Max	
Near-Field Communication (NFC) (page 80)	iPhone 11 Pro Max	
Acoustics (page 82)	iPhone 11 Pro Max	

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

5.10.1.27 iPhone 11 Pro

Table 5-29 iPhone 11 Pro case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 11 Pro	
Haptics (page 75)	iPhone 11 Pro	
Image Quality (page 76)	iPhone 11 Pro	Silver model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 11 Pro	
Near-Field Communication (NFC) (page 80)	iPhone 11 Pro	
Acoustics (page 82)	iPhone 11 Pro	

5.10.1.28 iPhone 11

Table 5-30 iPhone 11 case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 11	
Haptics (page 75)	iPhone 11	
Image Quality (page 76)	iPhone 11	Silver model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 11	
Near-Field Communication (NFC) (page 80)	iPhone 11	
Acoustics (page 82)	iPhone 11	

5.10.1.29 iPhone XS Max

Table 5-31 iPhone XS Max case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone XS Max	
Haptics (page 75)	iPhone XS Max	
Image Quality (page 76)	iPhone XS Max	Silver model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone XS Max	
Near-Field Communication (NFC) (page 80)	iPhone XS Max	
Acoustics (page 82)	iPhone XS Max	

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

5.10.1.30 iPhone XS

Table 5-32 iPhone XS case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone XS	
Haptics (page 75)	iPhone XS	
Image Quality (page 76)	iPhone XS	Silver model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone XS	
Near-Field Communication (NFC) (page 80)	iPhone XS	
Acoustics (page 82)	iPhone XS	

5.10.1.31 iPhone XR

Table 5-33 iPhone XR case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone XR	
Haptics (page 75)	iPhone XR	
Image Quality (page 76)	iPhone XR	White model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone XR	
Near-Field Communication (NFC) (page 80)	iPhone XR	
Acoustics (page 82)	iPhone XR	

5.10.1.32 iPhone X

Table 5-34 iPhone X case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone X	
Haptics (page 75)	iPhone X	
Image Quality (page 76)	iPhone X	Silver model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone X	
Near-Field Communication (NFC) (page 80)	iPhone X	
Acoustics (page 82)	iPhone X	

Copyright © 2025 Apple Inc. All Rights Reserved.

5.10.1.33 iPhone 8 Plus/iPhone 7 Plus

Table 5-35 iPhone 8 Plus/iPhone 7 Plus case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 8 Plus and iPhone 7 Plus	
Haptics (page 75)	iPhone 8 Plus and iPhone 7 Plus	
Touch ID Sensor Overlays (page 76)	iPhone 8 Plus and iPhone 7 Plus	
Image Quality (page 76)	iPhone 8 Plus and iPhone 7 Plus	Silver model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 8 Plus	
Near-Field Communication (NFC) (page 80)	iPhone 8 Plus and iPhone 7 Plus	
Acoustics (page 82)	iPhone 8 Plus and iPhone 7 Plus	

It is not possible for a case to claim compatibility with only iPhone 8 Plus, or only iPhone 7 Plus.

5.10.1.34 iPhone SE (3rd generation)/iPhone SE (2nd generation)/iPhone 8/iPhone 7

Table 5-36 iPhone SE (3rd generation)/iPhone SE (2nd generation)/iPhone 8/iPhone 7 case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone SE (3rd generation), iPhone SE (2nd generation), iPhone 8, and iPhone 7	
Haptics (page 75)	iPhone SE (3rd generation), iPhone SE (2nd generation), iPhone 8, and iPhone 7	
Touch ID Sensor Overlays (page 76)	iPhone SE (3rd generation), iPhone SE (2nd generation), iPhone 8, and iPhone 7	
Image Quality (page 76)	iPhone SE (3rd generation), iPhone SE (2nd generation), iPhone 8 and iPhone 7	Silver model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone SE (3rd generation) and iPhone SE (2nd generation)	
Near-Field Communication (NFC) (page 80)	iPhone SE (3rd generation) and iPhone SE (2nd generation)	
Acoustics (page 82)	iPhone SE (3rd generation), iPhone SE (2nd generation), iPhone 8, and iPhone 7	

It is not possible for a case to claim compatibility with only iPhone SE (3rd generation), or only iPhone SE (2nd generation), or only iPhone 8, or only iPhone 7.

Copyright © 2025 Apple Inc. All Rights Reserved.

5.10.1.35 iPhone 6s Plus/iPhone 6 Plus

Table 5-37 iPhone 6s Plus/iPhone 6 Plus case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 6s Plus and iPhone 6 Plus	
Image Quality (page 76)	iPhone 6s Plus and iPhone 6 Plus	Silver model only.
Autofocus & Optical Image Stabilization (page 80)	iPhone 6s Plus	
Near-Field Communication (NFC) (page 80)	iPhone 6s Plus and iPhone 6 Plus	
Haptics (page 75)	iPhone 6s Plus	

It is not possible for a case to claim compatibility with only iPhone 6s Plus, or only iPhone 6 Plus.

5.10.1.36 iPhone 6s/iPhone 6

Table 5-38 iPhone 6s/iPhone 6 case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 6s and iPhone 6	
Image Quality (page 76)	iPhone 6s and iPhone 6	Silver model only.
Near-Field Communication (NFC) (page 80)	iPhone 6s and iPhone 6	
Haptics (page 75)	iPhone 6s	

It is not possible for a case to claim compatibility with only iPhone 6s, or only iPhone 6.

5.10.1.37 iPhone 5/iPhone 5s/iPhone SE

Table 5-39 iPhone 5/iPhone 5s/iPhone SE case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone SE	
Image Quality (page 76)	iPhone SE	Silver or gold model only.

It is not possible for a case to claim compatibility with only iPhone 5, or only iPhone 5s, or only iPhone SE.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

5.10.1.38 iPhone 5c

Table 5-40 iPhone 5c case testing matrix

Test	Using	Notes
Product Design (page 72)	iPhone 5c	
Image Quality (page 76)	iPhone 5c	White model only.
Compass (page 81)	iPhone 5c	

5.10.1.39 iPad Pro 13-inch (M5) and iPad Pro 13-inch (M4)

Table 5-41 iPad Pro 13-inch (M5) and iPad Pro 13-inch (M4) case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad Pro 13-inch (M5)	
Image Quality (page 76)	iPad Pro 13-inch (M5)	Silver model only.
Compass (page 81)	iPad Pro 13-inch (M5)	

It is not possible for a case to claim compatibility with only iPad Pro 13-inch (M5), or only iPad Pro 13-inch (M4).

5.10.1.40 iPad Pro 11-inch (M5) and iPad Pro 11-inch (M4)

Table 5-42 iPad Pro 11-inch (M5) and iPad Pro 11-inch (M4) case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad Pro 11-inch (M5)	
Image Quality (page 76)	iPad Pro 11-inch (M5)	Silver model only.
Compass (page 81)	iPad Pro 11-inch (M5)	

It is not possible for a case to claim compatibility with only iPad Pro 11-inch (M5), or only iPad Pro 11-inch (M4).

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

5.10.1.41 iPad Air 13-inch (M3) and iPad Air 13-inch (M2)

Table 5-43 iPad Air 13-inch (M3) and iPad Air 13-inch (M2) case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad Air 13-inch (M3)	
Image Quality (page 76)	iPad Air 13-inch (M3)	Silver model only.
Compass (page 81)	iPad Air 13-inch (M3)	

It is not possible for a case to claim compatibility with only iPad Air 13-inch (M3), or only iPad Air 13-inch (M2).

5.10.1.42 iPad Air 11-inch (M3) and iPad Air 11-inch (M2)

Table 5-44 iPad Air 11-inch (M3) and iPad Air 11-inch (M2) case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad Air 11-inch (M3)	
Image Quality (page 76)	iPad Air 11-inch (M3)	Silver model only.
Compass (page 81)	iPad Air 11-inch (M3)	

It is not possible for a case to claim compatibility with only iPad Air 11-inch (M3), or only iPad Air 11-inch (M2).

5.10.1.43 iPad (A16) and iPad (10th generation)

Table 5-45 iPad (A16) case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad (A16)	
Image Quality (page 76)	iPad (A16)	Silver model only.
Compass (page 81)	iPad (A16)	

It is not possible for a case to claim compatibility with only iPad (A16), or only iPad (10th generation).

Copyright © 2025 Apple Inc. All Rights Reserved.

5.10.1.44 iPad Pro 12.9-inch (6th generation) and iPad Pro 12.9-inch (5th generation)

Table 5-46 iPad Pro 12.9-inch (6th generation) and iPad Pro 12.9-inch (5th generation) case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad Pro 12.9-inch (6th generation)	
Image Quality (page 76)	iPad Pro 12.9-inch (6th generation)	Silver model only.
Compass (page 81)	iPad Pro 12.9-inch (6th generation)	

It is not possible for a case to claim compatibility with only iPad Pro 12.9-inch (6th generation), or only iPad Pro 12.9-inch (5th generation).

5.10.1.45 iPad Pro 11-inch (4th generation) and iPad Pro 11-inch (3rd generation)

Table 5-47 iPad Pro 11-inch (4th generation) and iPad Pro 11-inch (3rd generation) case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad Pro 11-inch (4th generation)	
Image Quality (page 76)	iPad Pro 11-inch (4th generation)	Silver model only.
Compass (page 81)	iPad Pro 11-inch (4th generation)	

It is not possible for a case to claim compatibility with only iPad Pro 11-inch (4th generation), or only iPad Pro 11-inch (3rd generation).

5.10.1.46 iPad mini (A17 Pro) and iPad mini (6th generation)

Table 5-48 iPad mini (A17 Pro) and iPad mini (6th generation) case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad mini (A17 Pro)	
Image Quality (page 76)	iPad mini (A17 Pro)	Starlight model only.
Compass (page 81)	iPad mini (A17 Pro)	

It is not possible for a case to claim compatibility with only iPad mini (A17 Pro), or only iPad mini (6th generation).

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

5.10.1.47 iPad (7th generation)/iPad (8th generation)/iPad (9th generation)

Table 5-49 iPad (7th generation)/iPad (8th generation)/iPad (9th generation) case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad (7th generation), iPad (8th generation), and iPad (9th generation)	
Image Quality (page 76)	iPad (7th generation), iPad (8th generation), and iPad (9th generation)	Silver model only.
Compass (page 81)	iPad (7th generation), iPad (8th generation), and iPad (9th generation)	

It is not possible for a case to claim compatibility with only iPad (7th generation), or only iPad (8th generation), or only iPad (9th generation).

5.10.1.48 iPad Air (5th generation)/iPad Air (4th generation)

Table 5-50 iPad Air (5th generation)/iPad Air (4th generation) case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad Air (5th generation)	
Image Quality (page 76)	iPad Air (5th generation)	Silver model only.
Compass (page 81)	iPad Air (5th generation)	

5.10.1.49 iPad Pro 12.9-inch (4th generation)

Table 5-51 iPad Pro 12.9-inch (4th generation) case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad Pro 12.9-inch (4th generation)	
Image Quality (page 76)	iPad Pro 12.9-inch (4th generation)	Silver model only.
Compass (page 81)	iPad Pro 12.9-inch (4th generation)	

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

5.10.1.50 iPad Pro 11-inch (2nd generation)

Table 5-52 iPad Pro 11-inch (2nd generation) case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad Pro 11-inch (2nd generation)	
Image Quality (page 76)	iPad Pro 11-inch (2nd generation)	Silver model only.
Compass (page 81)	iPad Pro 11-inch (2nd generation)	

5.10.1.51 iPad Air (3rd generation)

Table 5-53 iPad Air (3rd generation) case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad Air (3rd generation)	
Image Quality (page 76)	iPad Air (3rd generation)	Silver model only.
Autofocus & Optical Image Stabilization (page 80)	iPad Air (3rd generation)	
Compass (page 81)	iPad Air (3rd generation)	

5.10.1.52 iPad mini (5th generation)

Table 5-54 iPad mini (5th generation) case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad mini (5th generation)	
Image Quality (page 76)	iPad mini (5th generation)	Silver model only.
Compass (page 81)	iPad mini (5th generation)	

5.10.1.53 iPad Pro 12.9-inch (3rd generation)

Table 5-55 iPad Pro 12.9-inch (3rd generation) case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad Pro 12.9-inch (3rd generation)	
Image Quality (page 76)	iPad Pro 12.9-inch (3rd generation)	Silver model only.
Compass (page 81)	iPad Pro 12.9-inch (3rd generation)	

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

5.10.1.54 iPad Pro 11-inch (1st generation)

Table 5-56 iPad Pro 11-inch (1st generation) case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad Pro 11-inch (1st generation)	
Image Quality (page 76)	iPad Pro 11-inch (1st generation)	Silver model only.
Compass (page 81)	iPad Pro 11-inch (1st generation)	

5.10.1.55 iPad Pro 10.5-inch

Table 5-57 iPad Pro 10.5-inch case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad Pro 10.5-inch	
Image Quality (page 76)	iPad Pro 10.5-inch	Silver model only.
Autofocus & Optical Image Stabilization (page 80)	iPad Pro 10.5-inch	
Compass (page 81)	iPad Pro 10.5-inch	

5.10.1.56 iPad Pro 12.9-inch (2nd generation)

Table 5-58 iPad Pro 12.9-inch (2nd generation) case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad Pro 12.9-inch (2nd generation)	
Image Quality (page 76)	iPad Pro 12.9-inch (2nd generation)	Silver model only.
Autofocus & Optical Image Stabilization (page 80)	iPad Pro 12.9-inch (2nd generation)	
Compass (page 81)	iPad Pro 12.9-inch (2nd generation)	

5.10.1.57 iPad (5th and 6th generation)

Table 5-59 iPad (5th and 6th generation) case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad (5th generation) or iPad (6th generation)	
Image Quality (page 76)	iPad (5th generation) or iPad (6th generation)	Silver model only.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Test	Using	Notes
Compass (page 81)	iPad (5th generation) or iPad (6th generation)	

5.10.1.58 iPad Pro 9.7-inch

Table 5-60 iPad Pro 9.7-inch case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad Pro 9.7-inch	
Image Quality (page 76)	iPad Pro 9.7-inch	Silver model only.
Compass (page 81)	iPad Pro 9.7-inch	

5.10.1.59 iPad Pro 12.9-inch (1st generation)

Table 5-61 iPad Pro 12.9-inch (1st generation) case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad Pro 12.9-inch (1st generation)	
Image Quality (page 76)	iPad Pro 12.9-inch (1st generation)	Silver model only.
Compass (page 81)	iPad Pro 12.9-inch (1st generation)	

5.10.1.60 iPad mini 4

Table 5-62 iPad mini 4 case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad mini 4	
Image Quality (page 76)	iPad mini 4	Silver model only.
Compass (page 81)	iPad mini 4	

5.10.1.61 iPad mini/iPad mini 2/iPad mini 3

Table 5-63 iPad mini/iPad mini 2/iPad mini 3 case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad mini 3	

Copyright © 2025 Apple Inc. All Rights Reserved.

Test	Using	Notes
Image Quality (page 76)	iPad mini 3	Silver model only.
Compass (page 81)	iPad mini 2 and iPad mini 3	

It is not possible for a case to claim compatibility with only iPad mini, or only iPad mini 2, or only iPad mini 3.

5.10.1.62 iPad Air 2

Table 5-64 iPad Air 2 case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad Air 2	
Image Quality (page 76)	iPad Air 2	Silver model only.
Compass (page 81)	iPad Air 2	

5.10.1.63 iPad Air

Table 5-65 iPad Air case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad Air	
Image Quality (page 76)	iPad Air	Silver model only.
Compass (page 81)	iPad Air	

5.10.1.64 iPad (4th generation)

Table 5-66 iPad (4th generation) case testing matrix

Test	Using	Notes
Product Design (page 72)	iPad (4th generation)	
Image Quality (page 76)	iPad (4th generation)	Silver model only.
Compass (page 81)	iPad (4th generation)	

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

5.10.1.65 iPod touch (5th generation)/iPod touch (6th generation)/iPod touch (7th generation)

Table 5-67 iPod touch (5th generation)/iPod touch (6th generation)/iPod touch (7th generation) Case Testing Matrix

Test	Using	Notes
Product Design (page 72)	iPod touch (7th generation)	
Image Quality (page 76)	iPod touch (5th generation) and iPod touch (6th generation) and iPod touch (7th generation)	Silver model only.

It is not possible for a case to claim compatibility with only iPod touch (5th generation), or only iPod touch (6th generation), or only iPod touch (7th generation).

5.10.2 Product Design

5.10.2.1 Equipment

The following equipment is necessary:

- Device.
- Apple Lightning Digital AV Adapter for devices with a Lightning receptacle.
- Apple USB-C Digital AV Multiport Adapter for devices with a USB-C receptacle.
- EarPods with 3.5 mm Headphone Plug for devices with a 3.5 mm headset jack.
- Vernier calipers.
- 0.85 mm plastic feeler gauge.

5.10.2.2 Procedure

1. Insert the device into the case.
2. Verify the device completely fits inside the case.
3. Verify the device is not loose.
4. Verify all buttons are accessible.
5. Inspect for button feel. Verify all buttons are not too hard to press or take a lot of effort to press.
6. Verify speaker/microphone ports are not occluded.
7. If the device has an Apple Lightning receptacle:
   a. Insert the Apple Lightning Digital AV Adapter into the receptacle and verify it fits.
   b. Using vernier calipers, measure the Lightning connector opening on the case. Verify the opening is measured to be at least 12.05 mm by 6.30 mm.
8. If the device has a USB-C receptacle:
   a. Insert the Apple USB-C Digital AV Multiport Adapter into the receptacle and verify it fits.

Copyright © 2025 Apple Inc. All Rights Reserved.

b. Using vernier calipers, measure the USB-C connector opening on the case. Verify the opening is measured to be at least 12.35 mm by 6.50 mm.

9. If the device has a 3.5 mm headset jack:
   a. Insert EarPods with 3.5 mm Headphone Plug into the headset jack and verify it fits.
   b. Using vernier calipers, measure the headset jack opening on the case. Verify the opening measures least 6 mm in diameter and no more than 14 mm deep.
10. If the device has a Touch ID sensor integrated with the Home button, use vernier calipers to verify the case is at least 2 mm away from the Touch ID sensor.
11. If the device has a Touch ID sensor integrated with the Top button, use vernier calipers to verify the case meets the keep-out defined for each device the accessory claims compatibility with. See Device Dimensional Drawings (page 328).
12. Verify the case is always proud of the feeler gauge when the gauge is placed at each corner of the device. See Figure 5-12 (page 73).

Figure 5-12 Device proudness test



13. Set the device flat on its face (screen facing down).
14. Roll the device towards any side not enclosed by the case until the gap between the device's exposed glass and flat surface is smallest.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

15. Verify the feeler gauge fits into the gap between the device's exposed glass and flat surface.

Figure 5-13 Device gap test



16. If the case has an overlay, verify there are no air gaps introduced between it and the touchscreen.

5.10.3 Camera Control

This test applies to devices with Camera Control.

5.10.3.1 Equipment

The following equipment is necessary:

- Device running iOS 26.1 or later.
- Accessory Developer Assistant (ADA) (page 325) installed on the device.

5.10.3.2 Setup

1. Attach the case to the device.
2. Launch the Accessory Developer Assistant app and sign in.
3. Select Case, Camera Control.

5.10.3.3 Preload

1. Select Preload, and follow the on-screen instructions.
2. Verify the test passes.
3. Perform the Preload test again, firmly squeezing the device just above or below the Camera Control.
4. Verify the test passes.

5.10.3.4 Gestures

1. Perform the 'Light press', 'Click', and 'Slide' tests under Landscape, following the on-screen instructions for each.
2. Verify the tests pass.

Copyright © 2025 Apple Inc. All Rights Reserved.

3. Using only the left hand, perform the 'Light press', 'Click', and 'Slide' tests under Portrait, following the on-screen instructions for each.
4. Verify the tests pass.
5. Using only the right hand, perform the 'Light press', 'Click', and 'Slide' tests under Portrait, following the on-screen instructions for each.
6. Verify the tests pass.

5.10.4 Haptics

5.10.4.1 Equipment

The following equipment is necessary:

- Two devices of the same model.

5.10.4.2 Setup

Repeat the following for each device:

1. Open Settings > Sound & Haptics > Haptics, select Always Play.

5.10.4.3 Procedure

1. Attach the case to one device.
2. Verify the case does not cause substantial changes in the feel of the device's haptic feedback by comparing the haptic feedback between the devices for each of the following tasks:
   a. Toggle the Ring/Silent switch or use the Action button.
   b. Connect a charger, wait a few seconds, then disconnect the charger.
   c. Open Settings > Notifications > Phone > Sounds, select Reflection (Default).
   d. Open Settings > Notifications > Messages > Sounds, select Note (Default).
   e. Go to the Home Screen.
   f. Long press the Settings app to show the Quick Actions menu, then slide a finger across the menu and release to select Wi-Fi.
   g. Go to the Home Screen.
   h. Long press the Home app to show the Quick Actions menu. Release, then tap away from the menu to return to the Home Screen.
   i. Open the Clock app, select Timers, then scroll through the hours, minutes, and seconds.
   j. If the device has a Home button:
      a. Open Settings > General > Home Button, select option 2.
      b. Press the Home button.
      c. Place the device on a flat surface, like a table.
      d. Press the Home button.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

5.10.5 Touch ID Sensor Overlays

This test procedure applies to accessories overlaying the Touch ID sensor.

5.10.5.1 Equipment

The following equipment is necessary:

- Nitrile gloves (for example, Ansell TNT Blue).
- Ethyl alcohol hand sanitizer (for example, Purell).
- Scissors.

5.10.5.2 Procedure

1. Cut off a square of material from the nitrile glove's wrist portion.
2. Install the accessory onto the device.
3. Press the Side/Top button to place the device into a sleep state (display off).
4. Place the square of nitrile glove material over the Touch ID sensor with the glove's outer side facing away from the device.
5. Apply a small amount of hand sanitizer (approximately 2 cm in diameter) to the glove over the Touch ID sensor.
6. Repeat the following steps 10 times:
   a. Press the Touch ID sensor with a thumb.
   b. Verify the device wakes (display on).
   c. Place the device into a sleep state (display off).
7. Repeat the following steps 10 times:
   a. Press the Touch ID sensor with an index finger.
   b. Verify the device wakes (display on).
   c. Place the device into a sleep state (display off).

5.10.5.3 Pass/Fail Criteria

Verify the device wakes every time the Touch ID sensor is pressed.

5.10.6 Camera

5.10.6.1 Image Quality

This test applies to devices with a rear-facing camera.

5.10.6.1.1 Equipment

The following equipment is necessary:

Copyright © 2025 Apple Inc. All Rights Reserved.

- Dust-free rectangular room, see Figure 5-15 (page 78):
  - ≥400 cm width, ≥500 cm depth.
  - Symmetrical flat wall painted with a low reflectance (matte) black paint.
  - Average reflection factor <10%.
- 3D test charts, see https://developer.apple.com/download/files/camera-charts.zip:
  - Painted flat grey (10%) with micro beads (Mold-Tech MT11050 texture), see Figure 5-14 (page 77).
  - Small: 1270 mm (W) x 900 mm (H) x 47 mm (D) for wide and telephoto cameras.
  - Large: 1592 mm (W) x 1129 mm (H) x 13 mm (D) for ultra wide camera.
- Device running iOS 26.1 or later or iPadOS 26.1 or later.
- Tripod or fixture to hold the device.
- Accessory Developer Assistant (ADA) (page 325) installed on the device.

The following equipment is necessary for devices without a rear flash:

- Uniform light source:
  - Two dimmable fixtures capable of producing at least 400 lux of illuminance.
  - Correlated color temperature (CCT) of 5500 K ±200 K.
- Konica Minolta CL-200A chroma light meter or equivalent.

Figure 5-14 Camera image quality test chart



5.10.6.1.2 Setup

Figure 5-15 Image quality test setup



1. Center the test chart against the wall.
2. Take precautions to avoid stray light entering the camera lens or on the test chart.
3. Clean the camera lens and flash diffuser using a lens cleaning cloth or suitable alternative. Ensure no dust or fingerprints are visible on the camera lens.

If the device does not have a rear flash:

1. Place two light fixtures at an angle of 45° relative to the chart center. Verify shadows do not appear on the chart. A light diffuser may be used to reduce reflected glare.
2. Using the light meter, measure the light level at the 9 specified points in Figure 5-16 (page 79). Verify the illuminance at each point is 400 lux ±5% and all points are within 15 lux of each other.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 5-16 Illuminance measurement points



5.10.6.1.3 Procedure

1. Open Accessory Developer Assistant (ADA) (page 325) on the device.
2. Select Camera Image Quality Test.
3. Mount the appropriate test chart on the wall:
   - Small test chart for wide angle and telephoto.
   - Large test chart for ultra wide.
4. Mount the device on the tripod or fixture in landscape orientation so the rear camera(s) are at the top edge facing the test chart.
5. Align the camera lens with the center of the test chart at a distance of approximately 200 cm.
6. Verify the camera and the test chart are parallel.
7. Follow the instructions in the app, keep the following in mind:

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- Move the device forwards or backwards until the test chart lines up with the test chart overlay on the app.
- Low lux: Power off all of the lights in the room. The image capture needs to be carried out in complete darkness.
- High lux: Set the illuminance at the test chart as specified in Setup (page 78).

5.10.6.2 Autofocus & Optical Image Stabilization

This test applies to devices with Autofocus (AF) and/or Optical Image Stabilization (OIS).

5.10.6.2.1 Equipment

The following equipment is necessary:

- Device running iOS 26.1 or later or iPadOS 26.1 or later, see Device Models (page 50).
- Flat level non-ferrous test surface away from magnetic fields.
- Accessory Developer Assistant (ADA) (page 325) installed on the device.
- Autofocus & Optical Image Stabilization Test Profile (page 326) installed on the device.

5.10.6.2.2 Procedure

1. Launch the Accessory Developer Assistant (ADA) (page 325) app and sign in.
2. Select Case, Autofocus and Optical Image Stabilization.
3. Allow ADA to access the device camera, if prompted.
4. Set the device on the test surface.
5. Follow the on-screen instructions.
6. Select Measure Baseline and wait for the measurement to complete.
7. Attach the case being tested on the device.
8. Set the device back on the test surface.
9. Select Measure Attached and wait for the measurement to complete.
10. Verify all tests pass and note the results.

5.10.7 Near-Field Communication (NFC)

This test applies to devices with NFC.

5.10.7.1 Equipment

The following equipment is necessary:

- Device running iOS 26.1 or later.
- Accessory Developer Assistant (ADA) (page 325) installed on the device.
- NFC tag.
- NFC transmitter.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

    - Separate device with the ADA app may be used as an NFC transmitter.
- Flat level non-ferrous test surface away from magnetic fields.
- Straight edge non-metallic ruler.

5.10.7.2 Setup

1. Place the NFC tag or transmitter on the flat level non-ferrous test surface.
2. Position the ruler to measure the vertical distance from the NFC tag or transmitter to the device.

5.10.7.3 Procedure

This procedure establishes a detection baseline without a case attached and then tests are rerun with the case attached. The procedure is repeated for both NFC tag & transmitter modes.

1. Launch the Accessory Developer Assistant app and sign in.
2. Select Near Field Communication.
3. Select 'Test with NFC tag', and follow the on-screen instructions.
    a. Measure baseline average distance with no case attached.
    b. Attach case.
    c. Repeat measurements with case attached.
    d. Verify test passes.
4. Select 'Test with an NFC transmitter', and follow the on-screen instructions.
    a. If using a second device as an NFC transmitter:
        a. Open ADA app on the second device.
        b. Select Apple Pay Detector.
        c. Select Start Detector.
    b. Measure baseline average distance with no case attached.
    c. Attach case.
    d. Repeat measurements with case attached.
    e. Verify test passes.
5. Perform multi-angle detection.
6. Verify multi-angle detection test passes.

5.10.8 Compass

5.10.8.1 Equipment

The following equipment is necessary:

- Device running iPadOS 26.1 or later.
- Accessory Developer Assistant (ADA) (page 325) installed on the device.
- Flat level non-ferrous test surface away from magnetic fields.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- Magnetometer, such as the Meda FVM400.

5.10.8.2 Setup

1. Place a mark on the test surface with a 90° angle to use for repeated device alignment. For example, use two pieces of tape perpendicular to each other.
2. Use the magnetometer to verify the test surface has a consistent magnetic field, not affected by nearby electronics or magnets.

5.10.8.3 Procedure

1. Launch the Accessory Developer Assistant app and sign in.
2. Select Compass and the case type, such as: Folio, Keyboard Folio, or Shell.
3. Scroll down and select all supported case configurations, see Figure 5-17 (page 82).

Figure 5-17 Case configurations



4. Scroll down and select all included case materials.
5. Select Start Test.
6. If a closed case configuration is selected, connect an external display and mouse when prompted.
7. Place the device with no case attached on the test surface, aligned to the mark.
8. Select Measure Baseline to collect an initial measurement.
9. Once the measurement is complete, follow the on-screen instructions to attach the case and collect a measurement for each supported case configuration.
10. Verify all tests pass and note the results.

5.10.9 Acoustics

Procedures apply to devices with a built in speaker and/or microphone.

Copyright © 2025 Apple Inc. All Rights Reserved.

5.10.9.1 Speakerphone Call

This procedure evaluates the impact of a case on the speakerphone performance of a device.

5.10.9.1.1 Setup

This procedure needs two operators in separate quiet rooms.

Room A:

- Operator A.
- The device used to evaluate the case with cellular service and at least two out of five bars of cellular reception within the room.

Room B:

- Operator B.
- Landline speakerphone.
- Digital audio recorder (for example, a device with the Voice Memo app).

5.10.9.1.2 Pass/Fail Criteria

There are two categories of failure for this procedure:

- Echo: If Operator B hears their own voice from the landline.
- Double talk: If Operator B hears Operator A inconsistently.

Establish the pass/fail threshold for these two categories by performing the test procedure using the device (without the case) as a reference. If there is no perceivable difference between the reference and the same procedure conducted with the case on the device, the test passes.

5.10.9.1.3 Procedure

1. Operator A: Use the device (without a case) in Room A to call the landline phone in Room B.
2. Operator A: Place the device in speakerphone mode.
3. Operator B: Answer the call with the landline phone in Room B.
4. Operator B: Place the landline phone in speakerphone mode.
5. Operator A and B: Simultaneously recite the following phrases to evaluate the call quality:
   a. The birch canoe slid on the smooth planks.
   b. Glue the sheet to the dark blue background.
   c. It's easy to tell the depth of a well.
   d. These days a chicken leg is a rare dish.
   e. Rice is often served in round bowls.
   f. The juice of lemons makes fine punch.
   g. The box was thrown beside the parked truck.
   h. The hogs were fed chopped corn and garbage.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

i. Four hours of steady work faced us.
j. Large size in stockings is hard to sell.

6. Operator B: Evaluate the call. Ensure the call is audible and clear when there is no case on the device.
7. Operator A: Place the case on the device.
8. Operator B: Start audio recording using a digital audio recorder.
9. Operator A: State the test date and identify the manufacturer name, product name, and a unique identifier (UID) for case (production run name, design version, etc.).
10. Operator A and B: Simultaneously recite the same phrases as above.
11. Operator B: Stop audio recording.
12. Operator B: Evaluate the recording against the Pass/Fail Criteria (page 83).

The phrases used for this test procedure are from "IEEE Recommended Practice for Speech Quality Measurements," in *IEEE Transactions on Audio and Electroacoustics*, vol. 17, no. 3, pp. 225-246, September 1969.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

6. Covers

Covers are accessories providing protection by covering device displays.

6.1 Device Protection

Covers shall not damage coatings on the display in any operating condition (for example, when closed, carrying in a backpack, or storing).

6.2 Magnetic Interference

Accessory covers shall not interfere with the device's:

- Magnetic compass.
- Rear camera autofocus (AF).
- Rear camera optical image stabilization (OIS), if present.
- Front camera autofocus, if present.

See Magnetic Interference (page 30) for additional details.

6.3 Smart Covers

Dimensional drawings indicating magnet and Hall effect sensor locations:

- iPad Pro 13-inch (M5) and iPad Pro 13-inch (M4), 3 of 5 (page 428)
- iPad Pro 11-inch (M5) and iPad Pro 11-inch (M4), 3 of 5 (page 433)
- iPad Air 13-inch (M3) and iPad Air 13-inch (M2), 3 of 5 (page 438)
- iPad Air 11-inch (M3) and iPad Air 11-inch (M2), 3 of 5 (page 443)
- iPad (A16) and iPad (10th generation), 3 of 7 (page 448)
- iPad (A16) and iPad (10th generation), 4 of 7 (page 449)
- iPad (A16) and iPad (10th generation), 5 of 7 (page 450)
- iPad mini (A17 Pro), 3 of 6 (page 455)
- iPad mini (A17 Pro), 4 of 6 (page 456)
- iPad Pro 12.9-inch (6th generation), 3 of 5 (page 461)
- iPad Pro 11-inch (4th generation), 3 of 5 (page 466)

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- iPad Air (5th generation) and iPad Air (4th generation), 3 of 5 (page 471)
- iPad mini (6th generation), 3 of 6 (page 476)
- iPad mini (6th generation), 4 of 6 (page 477)
- iPad (9th generation), iPad (8th generation) and iPad (7th generation), 2 of 4 (page 481)
- iPad Pro 12.9-inch (5th generation), 3 of 5 (page 486)
- iPad Pro 11-inch (3rd generation), 3 of 5 (page 491)
- iPad Pro 12.9-inch (4th generation), 3 of 5 (page 496)
- iPad Pro 11-inch (2nd generation), 3 of 5 (page 501)
- iPad Air (3rd generation), 2 of 3 (page 505)
- iPad Air (3rd generation) with Cellular, 2 of 3 (page 508)
- iPad mini (5th generation), 2 of 3 (page 511)
- iPad mini (5th generation) with Cellular, 2 of 3 (page 514)
- iPad Pro 12.9-inch (3rd generation), 2 of 3 (page 517)
- iPad Pro 11-inch (1st generation), 2 of 3 (page 520)
- iPad Pro 12.9-inch (2nd generation) Magnet/Hall Effect Sensors, 1 of 2 (page 524)
- iPad Pro 12.9-inch (2nd generation) Magnet/Hall Effect Sensors, 2 of 2 (page 525)
- iPad Pro 10.5-inch Magnet/Hall Effect Sensors, 1 of 2 (page 528)
- iPad Pro 10.5-inch Magnet/Hall Effect Sensors, 2 of 2 (page 529)
- iPad (5th and 6th generation) Magnet/Hall Effect Sensors, 1 of 2 (page 531)
- iPad (5th and 6th generation) Magnet/Hall Effect Sensors, 2 of 2 (page 532)
- iPad Pro 9.7-inch Magnet/Hall Effect Sensors, 1 of 2 (page 535)
- iPad Pro 9.7-inch Magnet/Hall Effect Sensors, 2 of 2 (page 536)
- iPad Pro 12.9-inch (1st generation) Magnet/Hall Effect Sensors, 1 of 2 (page 539)
- iPad Pro 12.9-inch (1st generation) Magnet/Hall Effect Sensors, 2 of 2 (page 540)
- iPad mini 4 Magnet/Hall Effect Sensors (page 543)

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

7. Screen Overlays

The displays on Apple products have been carefully engineered and tested to deliver exacting visual performance. Many products also feature Multi-Touch technology to support user interactions. Any material overlaying the screen or between the surface and users' fingers (or writing instruments on iPad) may impact the visual, touch, or sensor performance.

7.1 Product Design

A screen overlay shall not:

- Degrade the performance of Multi-Touch, Apple Pencil, or sensors.
- Introduce air gaps between the touchscreen and overlay.
- Be electrically conductive.
- Cause any color tinge to cool white light sources.

A screen overlay should have a relative permittivity (dielectric) of 3.1 to 3.2.

A screen overlay should not:

- Exceed 0.3 mm in thickness.
- Exceed 0.095 mm in thickness to support Apple Pencil.
- Have a water contact angle <110°.

> **Note:**
> Non-glossy surfaces may accelerate Apple Pencil tip wear.

7.1.1 Optical Transmission

Optical transmission of screen overlays should:

- Be greater than 90% relative to clear glass for any viewing angle across the active display area, see Device Dimensional Drawings (page 328).
- Remain flat as defined in Figure 7-1 (page 88). Upon normalizing the transmission spectrum to the value at 550 nm, the normalized spectrum should fall in the range of [0.99, 1.01] from 500-800 nm and [0.95, 1.01] from 400-500 nm.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 7-1 Transmission spectrum



7.1.2 Infrared Transmission

Infrared transmission variance shall not exceed 1.5%. The infrared transmission in the 1200 nm - 1500 nm range relative to light source should be greater than:

- 90% for an angle of incidence between 0° and 45°.
- 84% for an angle of incidence between 45° and 60°.

7.1.3 Transmission Haze

Transmission haze is the percentage of visible and infrared light scattered at more than 2.5° from the normal transmission. Screen overlay transmission haze should:

- Not exceed 0.3% for:
  - iPhone 16 Pro Max
  - iPhone 16 Pro
  - iPhone 16 Plus
  - iPhone 16
  - iPhone 15 Pro Max
  - iPhone 15 Pro
  - iPhone 15 Plus
  - iPhone 15
  - iPhone 14 Pro Max
  - iPhone 14 Pro
- Not exceed 13% for all other devices.
- Be measured with a haze meter, per *ASTM D1003*.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

7.1.4 Dynamic Island

Screen overlays shall not have a punch-out for the Dynamic Island.

7.2 Edge Swipe Gestures

See Edge Swipe Gestures (page 42).

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

8. Camera Attachments

Camera attachments are accessories intentionally altering images captured by device cameras.

8.1 Magnetic Interference

Camera attachments shall not interfere with the device's:

- Magnetic compass.
- Rear camera autofocus (AF).
- Rear camera optical image stabilization (OIS), if present.
- Front camera autofocus, if present.

See Magnetic Interference (page 30) for additional details.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

9. Adapters

An adapter accessory is a dongle or a Built-In Cable (page 26) enabling connections between physically incompatible devices and accessories.

Unless otherwise specified, accessories may integrate one or more adapter components as well as other accessory features to create more advanced multi-port adapters. For example, a Lightning or USB-C adapter may support audio, power, external storage, media controls, app communication, and more.

See the Accessory Interface Specification (page 27) for more information.

9.1 Headset Adapters (Lightning to 3.5 mm)

Lightning to 3.5 mm headset adapters are accessories enabling 3.5 mm audio connections.

See the Accessory Interface Specification (page 27) for more information.

9.2 USB-A/USB-C to Lightning Headset Adapters

USB-A to Lightning or USB-C to Lightning headset adapters are accessories integrating a Lightning Receptacle (C37) to support Lightning headsets, speakers, and microphones.

See the Accessory Interface Specification (page 27) for more information.

9.3 Lightning to USB Micro-B Adapters

Figure9-1 Lightning to USB Micro-B adapter



2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Lightning to USB Micro-B adapters are Lightning dongle accessories functioning exactly like the Apple Lightning to USB Micro-B Adapter and shall consist of:

- Lightning connector.
- USB Micro-B receptacle.

See the Accessory Interface Specification (page 27) for more information.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

10. AC Power Adapters

AC power adapters convert AC "mains" power to DC to provide power to a device and may provide power using:

- Device Power (Inductive) (page 182).
- Device Power (USB-C) (page 175).
- Device Power (Lightning) (page 177).

10.1 Converter Switching Frequencies

Device touchscreen or audio functionality may be degraded by converter switching frequencies. Converter switching frequencies shall:

- Be above 22 kHz under loads greater than 5 mA.
- Be above 60 kHz and should be above 450 kHz under loads greater than 20 mA.

10.2 YCAP AC Capacitor

AC power adapters should include a YCAP AC capacitor (up to 1000 pF) between the primary and secondary sections of the adapter's transformer to reduce common-mode noise at switching frequencies. These frequencies or their harmonics can interfere with device touchscreen sensors.

10.3 Impedance Stability

AC power adapter series impedance should not change abruptly. Sudden changes in impedance may cause touchscreen sensor output oscillations.

Bridge diodes used in full-wave bridge rectifiers can be a major source of abrupt changes in the series impedance. If the bridge diodes have large inherent reverse capacitance (greater than 100 pF), then the net impedance change due to diode switching may be acceptably small. However, diode reverse capacitance may decrease in more compact IC designs due to decreased chip area.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Impedance of bridge diodes with unacceptably low reverse capacitance can be stabilized using the example circuit shown in Figure 10-1 (page 94) and Table 10-1 (page 94). In this example, capacitors C1, C2, C3, and C4 have been placed in parallel with diodes D1, D2, D3, and D4 to stabilize the bridge impedance. Their values are larger than the inherent reverse capacitances of the diodes.

Resistors R1, R2, R3, and R4 are optional; if included, they can block noise at very high frequencies, which can help with EMI compatibility. The recommended values of R1, R2, R3, and R4 in Table 10-1 (page 94) were chosen to have trivial levels of impedance relative to the impedances of C1, C2, C3, and C4 at power line frequencies.

Figure 10-1 Typical AC power adapter diode bridge circuit



Table 10-1 Typical component values for an AC power adapter diode bridge circuit

Component	Value
C1, C2, C3, C4	47 pF
R1, R2, R3, R4	2 kΩ

10.4 Fuse Protection

A fuse should be present at the input of the AC power adapter to protect it under any fault condition.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

10.5 Short Circuit Response

The output of the AC power adapter should drop or fold back without any resulting damage if its output is shorted to the secondary common (less than 10 mΩ).

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

11. Battery Packs

A battery pack is an accessory designed to provide power to the device.

The battery pack may provide power using:

- Device Power (Inductive) (page 182).
- Device Power (USB-C) (page 175).
- Device Power (Lightning) (page 177).

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

12. Headsets

Headsets provide users with personal audio experiences. Devices treat headsets differently from accessories with speakers.

Headsets shall comply with:
- TDMA Noise (page 30) requirements.
- Applicable volume limit regulations in the regions in which they are sold.

Wired headsets should support Apple Music Lossless or Hi-Res Lossless, see https://support.apple.com/en-us/118295.

12.1 Product Design

Headsets shall have:
- Drivers positioned at user's ears.
- Microphone(s) positioned to record user's voice.

12.2 Audio Interface

Headsets shall establish audio connections to devices using one of the following interfaces:
- USB-C Plug (page 310), including the Apple USB-C Analog Headset Module (page 278).
- Bluetooth (page 258):
  - Hands-Free Profile (HFP) (page 262)
  - Advanced Audio Distribution Profile (A2DP) (page 267)
- Headset Plug (3.5 mm) (page 318).

If connected using the USB-C Plug (page 310), headsets shall integrate one of the following:
- Apple USB-C Analog Headset Module (page 278) (recommended for standard headsets).
- USB Audio Device Class 2.0 or 4.0 compliant codec.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

12.3 Remote Controls

Headsets connecting to a device using the headset jack or USB-C connector (including Apple USB-C Analog Headset Module (page 278)) shall implement three physical controls mimicking the labeling and behavior of an Apple wired headset.

Controls shall be implemented using one of the following:

- Direct electrical connections to the Headset Remote and Microphone Transmitter (page 287) when integrating an Apple USB-C Analog Headset Module (page 278), or Headset Plug (3.5 mm) (page 318).
- HID Headset Remote (page 188) when using one of the following:
  - USB-C Plug (page 310) with a USB Audio Device Class 2.0 or 4.0 compliant codec.
  - Bluetooth (page 258).
- Bluetooth Audio/Video Remote Control Profile (AVRCP) (page 265).

Bluetooth headsets should implement controls identical to an Apple wired headset.

12.4 USB-C Headset Identification

USB-C headsets shall:

- Set the idVendor, idProduct, iManufacturer, iProduct, and iSerialNumber in the Standard Device Descriptor to reflect the accessory markings and packaging.
- Set the Output Terminal Type to `0x0302` (Headphones) if the headset does not integrate a microphone.
- Set the Output Terminal Type and Input Terminal Type to `0x0402` (Headset) if the headset integrates a microphone.
- Set the Audio Function Category to `0x04` (Headset).

USB-C headsets should:

- Set the iInterface Playback and iInterface Record strings to reflect the accessory markings and packaging.
- Set a unique iSerialNumber in the Standard Device Descriptor.

> **Note:**
> C125 has its Output Terminal Type and Input Terminal Type set to `0x0402` (Headset) and Audio Function Category set to `0x04` (Headset). These configurations cannot be overwritten.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

13. Strobes

Strobe accessories replace a device's integrated flash when capturing a still image from either the front or rear-facing cameras. Photographers can use such accessories to control scene lighting for creative purposes.

Strobes are:

- Compatible with all iOS camera applications.
- Synchronized with iPhone camera using the Lightning connector.

Figure 13-1 Example of integrated flash (top) vs. external strobe (bottom)



2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Devices supporting strobe accessories:

- iPhone 14 Pro Max
- iPhone 14 Pro
- iPhone 14 Plus
- iPhone 14
- iPhone SE (3rd generation)
- iPhone 13 Pro Max
- iPhone 13 Pro
- iPhone 13
- iPhone 13 mini
- iPhone 12 Pro Max
- iPhone 12 Pro
- iPhone 12
- iPhone 12 mini
- iPhone SE (2nd generation)
- iPhone 11 Pro Max
- iPhone 11 Pro
- iPhone 11

This feature is supported on iOS 14.0 or later.

See the Accessory Interface Specification (page 27) for more information.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

14. Keyboards

Devices may accept user input from accessory keyboards in place of the onscreen keyboard.

14.1 Requirements

Accessory keyboards shall:

- Support the Human Interface Device (HID) (page 247) protocol.
- Not identify themselves as Apple-branded accessories, for example, using the Apple Vendor ID and/or Product IDs.

Keyboard keys exhibiting any of the following behaviors are explicitly prohibited:

- Send anything other than 'key pressed' or 'key released' for key(s) physically pressed/released.
- Emulate combinations or sequences of keys (for example, a Copy button sending ⌘-C or macros generating a timed sequence of events).
- Emulate timed user actions, such as 'press-and-hold'.
- Send different HID usages depending on the state of another control surface.

HID reports sent from the keyboard shall only occur in response to a Direct User Action (page 26).

Keyboards may integrate LEDs to indicate the:

- Caps Lock status of the device.
- Connection status, such as Bluetooth state.
- Battery status of the accessory, if applicable.

Keyboards shall not incorporate any other status LEDs not supported by devices.

Keyboards should be integrated with Trackpads (page 107) when possible to provide an enhanced user experience.

Mechanical key layout shall be based on the *ISO/IEC 9995-2*, *ANSI-INCITS 154-1988*, or *JIS X 6002-1980* standards. Keyboard HID descriptors shall set the Keyboard Physical Layout usage to the appropriate layout code as defined in Table 14-5 (page 105).

Keyboard HID descriptors shall set the bCountryCode field to the appropriate country code as defined in *Device Class Definition for Human Interface Devices (HID) – Version 1.11, Section 6.2.1 HID Descriptor*.

Keyboard HID descriptors shall declare support for the HID Keyboard/Keypad Page. HID report descriptors may declare a input usage minimum of 0 and maximum of 255 as shown in Example HID Report Descriptor (page 106) for efficiency. Otherwise, the descriptor shall individually enumerate each HID Keyboard/Keypad page usage the keyboard is capable of sending.

Keyboards shall implement individual keys emitting the following HID Keyboard/Keypad page usages:

Table 14-1 Required HID Keyboard/Keypad Page (`0x07`) controls for use by keyboards

Usage ID	Usage Name	Apple Function
`0x0004`	a and A	a and A
`0x0005`	b and B	b and B
`0x0006`	c and C	c and C
`0x0007`	d and D	d and D
`0x0008`	e and E	e and E
`0x0009`	f and F	f and F
`0x000A`	g and G	g and G
`0x000B`	h and H	h and H
`0x000C`	i and I	i and I
`0x000D`	j and J	j and J
`0x000E`	k and K	k and K
`0x000F`	l and L	l and L
`0x0010`	m and M	m and M
`0x0011`	n and N	n and N
`0x0012`	o and O	o and O
`0x0013`	p and P	p and P
`0x0014`	q and Q	q and Q
`0x0015`	r and R	r and R
`0x0016`	s and S	s and S
`0x0017`	t and T	t and T
`0x0018`	u and U	u and U
`0x0019`	v and V	v and V
`0x001A`	w and W	w and W
`0x001B`	x and X	x and X
`0x001C`	y and Y	y and Y
`0x001D`	z and Z	z and Z
`0x001E`	1 and !	1 and !
`0x001F`	2 and @	2 and @
`0x0020`	3 and #	3 and #

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Usage ID	Usage Name	Apple Function
0x0021	4 and $	4 and $
0x0022	5 and %	5 and %
0x0023	6 and ^	6 and ^
0x0024	7 and &	7 and &
0x0025	8 and *	8 and *
0x0026	9 and (	9 and (
0x0027	0 and)	0 and)
0x0028	Return/Enter	Return
0x002A	Delete/Backspace	Delete
0x002B	Tab	Tab
0x002C	Spacebar	Spacebar
0x002D	- and _	- and _
0x002E	= and +	= and +
0x002F	[and {	[and {
0x0030	] and }	] and }
0x0031	\ and |	\ and |
0x0033	; and :	; and :
0x0034	' and "	' and "
0x0035	Grave Accent and Tilde	` and ~
0x0036	, and <	, and <
0x0037	. and >	. and >
0x0038	/ and ?	/ and ?
0x0039	CapsLock	Caps Lock
0x004F	RightArrow	Right Arrow
0x0050	LeftArrow	Left Arrow
0x0051	DownArrow	Down Arrow
0x0052	UpArrow	Up Arrow
0x00E1	LeftShift	Left Shift
0x00E2	LeftAlt	Left Option / Alt
0x00E3	LeftGUI	Left Command / ⌘
0x00E5	RightShift	Right Shift
0x00E6	RightAlt	Right Option / Alt
0x00E7	RightGUI	Right Command / ⌘

Keyboards may implement individual keys emitting the following HID Keyboard/Keypad page usages:

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Table 14-2 Optional HID Keyboard/Keypad Page (0x07) controls for use by keyboards

Usage ID	Usage Name	Apple Function
0x0029	Escape	Escape
0x00E0	LeftControl	Left Control
0x00E4	RightControl	Right Control
0x004A	Home	Home
0x004D	End	End
0x0054	Keypad /	Keypad /
0x0055	Keypad *	Keypad *
0x0056	Keypad -	Keypad -
0x0057	Keypad +	Keypad +
0x0058	Keypad Enter	Keypad Enter
0x0059	Keypad 1 and End	Keypad 1
0x005A	Keypad 2 and Down Arrow	Keypad 2
0x005B	Keypad 3 and PageDn	Keypad 3
0x005C	Keypad 4 and Left Arrow	Keypad 4
0x005D	Keypad 5	Keypad 5
0x005E	Keypad 6 and Right Arrow	Keypad 6
0x005F	Keypad 7 and Home	Keypad 7
0x0060	Keypad 8 and Up Arrow	Keypad 8
0x0061	Keypad 9 and PageUp	Keypad 9
0x0062	Keypad 0 and Insert	Keypad 0
0x0063	Keypad . and Delete	Keypad .
0x0067	Keypad =	Keypad =

Keyboards may implement individual keys emitting the following HID Consumer page usages:

Table 14-3 HID Consumer Page (0x0C) controls for use by keyboards

Usage ID	Usage Name	Apple Function
0x0030	Power	Lock
0x0040	Menu	Home Button
0x006F	Display Brightness Increment	Brighter
0x0070	Display Brightness Decrement	Dimmer
0x00B5	Scan Next Track	Transport Right
0x00B6	Scan Previous Track	Transport Left
0x00CD	Play/Pause	Play/Pause

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Usage ID	Usage Name	Apple Function
0x00E2	Mute	Mute
0x00E9	Volume Increment	Louder
0x00EA	Volume Decrement	Softer
0x01AE	AL Keyboard Layout	Toggle Onscreen Keyboard
0x029D	AC Keyboard Layout Select	Globe Key
0x0221	AC Search	Spotlight
0x025B	Promote	Play More Like This
0x025C	Demote	Play Less Like This
0x0262	Add to Cart	Add to Wish List
0x02C3	Keyboard Physical Layout	Keyboard Physical Layout, see Table 14-5 (page 105).

Keyboards may implement individual keys emitting the following HID Generic Desktop page usages:

Table 14-4 HID Generic Desktop Page (0x01) controls for use by keyboards

Usage ID	Usage Name	Apple Function
0x009B	System Do Not Disturb	Toggle Focus Mode

Table 14-5 Keyboard Physical Layout codes

Value	Description
1	101 (for example, US) - ANSI
3	102 (for example, German) - ISO
5	106 (DOS/V Japan) - JIS

JIS keyboards shall also implement additional keys found on the Japanese Apple Magic Keyboard. Non-JIS keyboards shall not implement the Japanese keys.

Table 14-6 Required HID Keyboard/Keypad Page (0x07) controls for use by JIS keyboards

Usage ID	Usage Name	Apple Function
0x0087	Keyboard International1	_
0x0089	Keyboard International3	¥
0x0090	LANG1	Switch to Previous Language
0x0091	LANG2	Switch to Next Language

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

14.2 Examples

14.2.1 Example HID Report Descriptor

```
USAGE PAGE (Generic Desktop)              05 01
USAGE (Keyboard)                          09 06
COLLECTION (Application)                  A1 01
  USAGE PAGE (LEDs)                       05 08
  LOGICAL MINIMUM (0)                     15 00
  LOGICAL MAXIMUM (1)                     25 01
  USAGE (Caps Lock)                       09 02
  REPORT SIZE (1)                         75 01
  REPORT COUNT (1)                        95 01
  OUTPUT (Data,Var,Abs)                   91 02
  REPORT SIZE (7)                         75 07
  REPORT COUNT (1)                        95 01
  OUTPUT (Cnst,Var,Abs)                   91 03
  USAGE PAGE (Keyboard)                   05 07
  USAGE MINIMUM (Keyboard Left Control)   19 E0
  USAGE MAXIMUM (Keyboard Right GUI)      29 E7
  REPORT SIZE (1)                         75 01
  REPORT COUNT (8)                        95 08
  INPUT (Data,Var,Abs)                    81 02
  LOGICAL MINIMUM (0)                     15 00
  LOGICAL MAXIMUM (255)                   26 FF 00
  USAGE MINIMUM (0)                       19 00
  USAGE MAXIMUM (255)                     2A FF 00
  REPORT SIZE (8)                         75 08
  REPORT COUNT (5)                        95 05
  INPUT (Data,Ary,Abs)                    81 00
  USAGE PAGE (Consumer Devices)           05 0C
  LOGICAL MINIMUM (0)                     15 00
  LOGICAL MAXIMUM (1)                     25 01
  USAGE (Menu)                            09 40
  USAGE (AC Search)                       0A 21 02
  USAGE (AL Keyboard Layout)              0A AE 01
  USAGE (Scan Previous Track)             09 B6
  USAGE (Play/Pause)                      09 CD
  USAGE (Scan Next Track)                 09 B5
  USAGE (Mute)                            09 E2
  USAGE (Volume Down)                     09 EA
  USAGE (Volume Up)                       09 E9
  USAGE (Power)                           09 30
  REPORT SIZE (1)                         75 01
  REPORT COUNT (10)                       95 0A
  INPUT (Data,Var,Abs)                    81 02
  REPORT SIZE (6)                         75 06
  REPORT COUNT (1)                        95 01
  INPUT (Cnst,Var,Abs)                    81 03
END COLLECTION                            C0
```

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

15. Trackpads

Devices may accept user input from accessory trackpads.

This feature is supported on iPadOS 14.5 or later.

15.1 Requirements

Accessory trackpads shall:

- Support the Human Interface Device (HID) (page 247) protocol.
- Not identify themselves as Apple-branded accessories, for example, using the Apple Vendor ID (VID).

Accessory trackpads exhibiting any of the following behaviors are explicitly prohibited:

- Emulating combinations of touch gestures.
- Emulating timed user actions, such as 'click and hold', drag, and zoom gestures.
- Sending different HID usages depending on the state of another control surface.

HID reports sent from the accessory trackpad shall only occur in response to a Direct User Action (page 26).

Trackpads shall support 2-5 simultaneous contacts on the digitizer surface.

15.1.1 Integration with Keyboards

Accessory trackpads shall be integrated with Keyboards (page 101) and simultaneously support both input methods. The following are examples of interactions involving both keyboard and trackpad input:

- Rapidly transitioning between cursor movement and keyboard entry.
- Pressing and holding modifier keys while performing a drag.
- Pressing ⌘-Tab to see the app switcher, then using the cursor to switch apps.
- Dragging an item using the trackpad, followed by pressing ⌘-Tab to switch apps.

15.1.2 HID Report Descriptor

HID report descriptors for an accessory trackpad shall declare support for the HID Digitizer Page.

Accessory trackpads shall implement the following HID Digitizer page usages:

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Table 15-1 Required HID Digitizer Page (0x0D) controls for use by accessory trackpads

Usage ID	Usage Name	Apple Function
0x01	Button 1	Primary button state
0x05	Report ID	Feature Report ID
0x22	Finger	Number of contact collection points
0x30	X	X coordinate of contact position
0x31	Y	Y coordinate of contact position
0x38 or 0x51	Transducer Index or Contact ID	Index (from 0-4) uniquely identifying the finger/contact
0x42	Tip Switch	Contact is on the surface of the digitizer
0x47	Confidence	Touch is an intended, valid contact
0x57	Surface Switch	Digitizer surface on/off

Accessory trackpads may implement the following HID Digitizer page usages. These HID usages are recommended:

Table 15-2 Recommended HID Digitizer Page (0x0D) controls for use by accessory trackpads

Usage ID	Usage Name	Apple Function
0x02	Button 2	Secondary button state
0x56	Scan Time	Relative scan time
0xA1	Report Rate	Report rate (Hz)

15.1.3 Coexistence

Accessory trackpads shall:

- Not degrade the performance of Multi-Touch or Apple Pencil.
- Not support a drive voltage greater than 6 V_{pp}.
- Not support drive frequencies less than 500 kHz.
- Support 3 or more drive frequencies, separated by at least 50 kHz each.
- Dynamically switch between drive frequencies whenever effective resolution drops below 120 DPI. For example, effective resolution may drop in the presence of 50 mV RMS noise from external power sources.

Accessory trackpads should support a sine wave narrow band drive frequency.

15.1.4 Performance

Accessory trackpads shall:

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- Behave uniformly across the digitizer surface.
- Uniquely detect contact points as close as 8 mm center to center.
- Detect contact sizes of at least 5 mm.
- Differentiate between multi-finger taps and single-finger drags.
- Maintain an effective input resolution less than 20 µm and immediately report positional updates greater than or equal to the effective input resolution.
- Maintain an effective resolution more than 600 DPI.
- Maintain the highest possible report rate to the device. Apple recommends 60 Hz or higher.
- Maintain a panning latency less than or equal to 23 ms.
- Maintain a touch down latency less than or equal to 35 ms.
- Maintain a positional accuracy less than or equal to 500 µm.
- Maintain a stationary contact jitter less than or equal to 210 µm.
- Not deviate more than 250 µm from an ideal line.

15.1.5 Input Confidence

Accessory trackpads shall:

- Set the Confidence usage when an input transitions from valid to invalid. Contact transitions should be quick, accurate, and stable to achieve the best user experience. Incorrect or fluctuating classification of contacts may result in recognition of unintended gestures, interruption, or cancelation of intended gestures.
- Detect and reject unintended/invalid inputs, such as palms, while continuing to report valid inputs to the device, such as multiple contacts.
- Distinguish between a valid large thumb and an invalid lightly resting palm.
- Reject inputs ≥1 mm from the tracking surface.

15.1.6 Click to Wake

Devices use Report ID usage to indicate to the trackpad whether surface contacts shall be reported or not. Devices will use the Surface Switch usage to tell the accessory to go into Click to Wake mode where only button clicks are accepted. Trackpads may use this opportunity to go into a low power mode where the digitizer surface does not have to be constantly scanned.

This feature report also doubles as an informational report. Devices may query the accessory trackpad at any time after enumeration to obtain the current state of the Surface Switch, and also to get the accessory's Report Rate.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

15.2 Examples

15.2.1 Example HID Report Descriptor

The following descriptor is for a 92.10 mm x 50.60 mm trackpad with two buttons supporting up to five simultaneous contacts.

Additional modifications may be necessary in order to implement this HID report descriptor in the accessory trackpad firmware, specifically:

- Modify physical maximum values for X (`0x30`) and Y (`0x31`) positions of each finger to match the physical size of the accessory trackpad. Units are in tenths of a mm (0.1 mm). In the example, X goes from `0x0` to `0x0399` (92.10 mm) and Y goes from `0x0` to `0x01FA` (50.60 mm).
- Modify logical maximum values for the X (`0x30`) and Y (`0x31`) of each finger positions to match the resolution of the accessory trackpad. In the example, X (`0x30`) goes from 0 to `0x0451` (for a resolution of 92.10/1105 = ~0.083 mm) and Y (`0x31`) goes from 0 to `0x025F` (for the same resolution of 50.60/607 = ~0.083 mm).

```
USAGE PAGE (Digitizer Device Page)                  05 0D
USAGE (Touch Pad)                                   09 05
COLLECTION (Application)                            A1 01
  REPORT_ID (3)                                     85 03
  LOGICAL MAXIMUM (65535)                           27 FF FF 00 00
  USAGE (Relative Scan Time (DV=Dynamic Value))     09 56
  REPORT SIZE (16)                                  75 10
  REPORT COUNT (1)                                  95 01
  INPUT (Data,Var,Abs)                              81 02
  LOGICAL MAXIMUM (1)                               25 01
  REPORT SIZE (1)                                   75 01
  USAGE (Surface Switch)                            09 57
  FEATURE (Data,Var,Abs)                            B1 02
  LOGICAL MAXIMUM (32767)                           26 FF 7F
  REPORT SIZE (15)                                  75 0F
  USAGE (Report Rate)                               09 A1
  FEATURE (Data,Var,Abs)                            B1 02
  USAGE PAGE (Button Page)                          05 09
  LOGICAL MAXIMUM (1)                               25 01
  USAGE MINIMUM (Button 1)                          19 01
  USAGE MAXIMUM (Button 2)                          29 02
  REPORT COUNT (2)                                  95 02
  REPORT SIZE (1)                                   75 01
  INPUT (Data,Var,Abs)                              81 02
  REPORT COUNT (6)                                  95 06
  INPUT (Cost, Ary, Abs)                            81 01
  USAGE PAGE (Digitizer Device Page)                05 0D
  USAGE (Finger)                                    09 22
  COLLECTION (Physical)                             A1 00
  USAGE (Tip Switch)                                09 42
  USAGE (Confidence)                                09 47
```

Copyright © 2025 Apple Inc. All Rights Reserved.

```
REPORT COUNT (2)                                95 02
INPUT (Data,Var,Abs)                            81 02
LOGICAL MAXIMUM (5)                             25 05
USAGE (Transducer Index)                        09 38
REPORT SIZE (6)                                 75 06
REPORT COUNT (1)                                95 01
INPUT (Data,Var,Abs)                            81 02
USAGE PAGE (Generic Desktop Page)               05 01
PHYSICAL MAXIMUM (921)                          46 99 03
PHYSICAL MINIMUM (0)                            35 00
LOGICAL MAXIMUM (1105)                          26 51 04
REPORT SIZE (12)                                75 0C
UNIT EXPONENT (Unit Value x .01)                55 0E
GLOBAL UNIT (Distance in centimeters)           65 11
USAGE (X)                                       09 30
INPUT (Data,Var,Abs)                            81 02
PHYSICAL MAXIMUM (506)                          46 FA 01
LOGICAL MAXIMUM (607)                           26 5F 02
USAGE (Y)                                       09 31
INPUT (Data,Var,Abs)                            81 02
END COLLECTION (Physical)                       C0
USAGE PAGE (Digitizer Device Page)              05 0D
USAGE (Finger)                                  09 22
COLLECTION (PHYSICAL)                           A1 00
LOGICAL MAXIMUM (1)                             25 01
USAGE (Tip Switch)                              09 42
USAGE (Confidence)                              09 47
REPORT SIZE (1)                                 75 01
REPORT COUNT (2)                                95 02
INPUT (Data,Var,Abs)                            81 02
USAGE (Transducer Index)                        09 38
LOGICAL MAXIMUM (5)                             25 05
REPORT SIZE (6)                                 75 06
REPORT COUNT (1)                                95 01
INPUT (Data,Var,Abs)                            81 02
USAGE PAGE (Generic Desktop Page)               05 01
PHYSICAL MAXIMUM (921)                          46 99 03
LOGICAL MAXIMUM (1105)                          26 51 04
REPORT SIZE (12)                                75 0C
USAGE (X)                                       09 30
INPUT (Data,Var,Abs)                            81 02
PHYSICAL MAXIMUM (506)                          46 FA 01
LOGICAL MAXIMUM (607)                           26 5F 02
USAGE (Y)                                       09 31
INPUT (Data,Var,Abs)                            81 02
END COLLECTION (Physical)                       C0
USAGE PAGE (Digitizer Device Page)              05 0D
USAGE (Finger)                                  09 22
COLLECTION (Physical)                           A1 00
LOGICAL MAXIMUM (1)                             25 01
USAGE (Tip Switch)                              09 42
USAGE (Confidence)                              09 47
REPORT SIZE (1)                                 75 01
```

Copyright © 2025 Apple Inc. All Rights Reserved.

```
REPORT COUNT (2)                        95 02
INPUT (Data,Var,Abs)                    81 02
USAGE (Transducer Index)                09 38
LOGICAL MAXIMUM (5)                     25 05
REPORT SIZE (6)                         75 06
REPORT COUNT (1)                        95 01
INPUT (Data,Var,Abs)                    81 02
USAGE PAGE (Generic Desktop Page)       05 01
PHYSICAL MAXIMUM (921)                  46 99 03
LOGICAL MAXIMUM (1105)                  26 51 04
REPORT SIZE (12)                        75 0C
USAGE (X)                               09 30
INPUT (Data,Var,Abs)                    81 02
PHYSICAL MAXIMUM (506)                  46 FA 01
LOGICAL MAXIMUM (607)                   26 5F 02
USAGE (Y)                               09 31
INPUT (Data,Var,Abs)                    81 02
END COLLECTION (PHYSICAL)               C0
USAGE PAGE (Digitizer Device Page)      05 0D
USAGE (Finger)                          09 22
COLLECTION (PHYSICAL)                   A1 00
LOGICAL MAXIMUM (1)                     25 01
USAGE (Tip Switch)                      09 42
USAGE (Confidence)                      09 47
REPORT SIZE (1)                         75 01
REPORT COUNT (2)                        95 02
INPUT (Data,Var,Abs)                    81 02
USAGE (Transducer Index)                09 38
LOGICAL MAXIMUM (5)                     25 05
REPORT SIZE (6)                         75 06
REPORT COUNT (1)                        95 01
INPUT (Data,Var,Abs)                    81 02
USAGE PAGE (Generic Desktop Page)       05 01
PHYSICAL MAXIMUM (921)                  46 99 03
LOGICAL MAXIMUM (1105)                  26 51 04
REPORT SIZE (12)                        75 0C
USAGE (X)                               09 30
INPUT (Data,Var,Abs)                    81 02
PHYSICAL MAXIMUM (506)                  46 FA 01
LOGICAL MAXIMUM (607)                   26 5F 02
USAGE (Y)                               09 31
INPUT (Data,Var,Abs)                    81 02
END COLLECTION (Physical)               C0
USAGE PAGE (Digitizer Device Page)      05 0D
USAGE (Finger)                          09 22
COLLECTION (PHYSICAL)                   A1 00
LOGICAL MAXIMUM (1)                     25 01
USAGE (Tip Switch)                      09 42
USAGE (Confidence)                      09 47
REPORT SIZE (1)                         75 01
REPORT COUNT (2)                        95 02
INPUT (Data,Var,Abs)                    81 02
USAGE (Transducer Index)                09 38
```

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

```
  LOGICAL MAXIMUM (5)                          25 05
  REPORT SIZE (6)                              75 06
  REPORT COUNT (1)                             95 01
  INPUT (Data,Var,Abs)                         81 02
  USAGE PAGE (Generic Desktop Page)            05 01
  PHYSICAL MAXIMUM (921)                       46 99 03
  LOGICAL MAXIMUM (1105)                       26 51 04
  REPORT SIZE (12)                             75 0C
  USAGE (X)                                    09 30
  INPUT (Data,Var,Abs)                         81 02
  PHYSICAL MAXIMUM (506)                       46 FA 01
  LOGICAL MAXIMUM (607)                        26 5F 02
  USAGE (Y)                                    09 31
  INPUT (Data,Var,Abs)                         81 02
  END COLLECTION (Physical)                    C0
END COLLECTION (Application)                   C0
```

15.2.2 Example Trackpad

The following HID reports are for a 60 Hz accessory trackpad using the Example HID Report Descriptor (page 110):

1. Two contacts are made on the surface of the accessory trackpad.
   `03000000 0300100F 0700C016 00000000 00000000 00000000`



2. Two contacts move simultaneously along the X axis.
   `03A70000 0314110F 0714C116 00000000 00000000 00000000`



3. Two contacts continue moving until they reach the center of the digitizer surface.
   `034E0100 0328120F 0728C216 00000000 00000000 00000000`



4. One contact is removed. Confidence for removed contact is still 1 and its coordinates are unchanged.
   `03F50100 0328120F 0628C216 00000000 00000000 00000000`



5. Remaining contact moves to the exact center of the digitizer surface. Confidence and coordinates of the removed contact are now 0.
   `039C0200 0328F212 00000000 00000000 00000000 00000000`

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.



6. Button 1 is clicked.
   `03430301 0328F212 00000000 00000000 000000000 0000000`



7. Button 1 is un-clicked and contact is removed. Confidence for removed contact is still 1 and its coordinates are unchanged.
   `03EA0300 0228F212 00000000 00000000 00000000 00000000`



16. Braille Displays and Keyboards

A braille display is an accessory enabling a user who is blind or has low vision to read text using raised pins. These accessories may include a braille keyboard to enter text, controls used to navigate a device, and controls to interface with a screen reader.

Figure 16-1 Braille display with keyboard



This feature is supported on iOS 12.0 or later, tvOS 12.0 or later, and macOS 10.14 Mojave or later.

16.1 Requirements

Braille display accessories shall:

- Support the Human Interface Device (HID) (page 247) protocol.
- Not identify themselves as Apple-branded accessories, for example, using the Apple Vendor ID.

Braille display keys exhibiting any of the following behaviors are explicitly prohibited:

- Sending anything other than a 'key pressed' or 'key released' for a physically pressed key.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- Emulating combinations of other keys (for example, macros like Command-C for Copy).
- Emulating timed user actions, such as 'press-and-hold'.

HID reports sent from braille displays shall only occur in response to Direct User Action (page 26).

HID report descriptors for braille displays shall declare support for the Braille Display Page (`0x41`). HID report descriptors shall individually enumerate each usage the accessory is capable of receiving or sending.

Braille display accessories shall declare a braille display collection containing one or more braille rows with 8 dot and/or 6 dot braille cells with the following usages:

Table 16-1 Required Braille Display Page (`0x41`) usages for use by display

Usage ID	Usage Name	Apple Function
`0x0001`	Braille Display	Braille Display
`0x0002`	Braille Row	Braille Row
`0x0003`	8 Dot Braille Cell	8 Dot Braille Cell
`0x0004`	6 Dot Braille Cell	6 Dot Braille Cell

Braille display accessories may support the following usages:

Table 16-2 Optional Braille Display Page (`0x41`) usages for use by display

Usage ID	Usage Name	Apple Function
`0x0005`	Number of Braille Cells	Number of Braille Cells
`0x00FA`	Router Set 1	Primary Button
`0x00FB`	Router Set 2	Secondary Button
`0x00FC`	Router Set 3	Tertiary Button
`0x0100`	Router Key	Router Key for a Braille Cell
`0x0101`	Row Router Key	Router Key for a Braille Row
`0x020C`	Braille Face Controls	Braille Face Controls
`0x020D`	Braille Left Controls	Braille Left Controls
`0x020E`	Braille Right Controls	Braille Right Controls
`0x020F`	Braille Top Controls	Braille Top Controls
`0x0210`	Braille Joystick Center	Braille Joystick Center
`0x0211`	Braille Joystick Up	Braille Joystick Up
`0x0212`	Braille Joystick Down	Braille Joystick Down
`0x0213`	Braille Joystick Left	Braille Joystick Left
`0x0214`	Braille Joystick Right	Braille Joystick Right

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Usage ID	Usage Name	Apple Function
0x0215	Braille D-Pad Center	Braille D-Pad Center
0x0216	Braille D-Pad Up	Braille D-Pad Up
0x0217	Braille D-Pad Down	Braille D-Pad Down
0x0218	Braille D-Pad Left	Braille D-Pad Left
0x0219	Braille D-Pad Right	Braille D-Pad Right
0x021A	Braille Pan Left	Braille Pan Left
0x021B	Braille Pan Right	Braille Pan Right
0x021C	Braille Rocker Up	Braille Rocker Up
0x021D	Braille Rocker Down	Braille Rocker Down
0x021E	Braille Rocker Press	Braille Rocker Press

16.1.1 Braille Keyboards

Braille displays may include a braille keyboard to enter text.

Braille display accessories with braille keyboards shall implement individual keys emitting the following usages:

Table 16-3 Required Braille Display Page (0x41) controls for use by display with keyboard

Usage ID	Usage Name	Apple Function
0x0200	Braille Buttons	Braille Buttons
0x0201	Braille Keyboard Dot 1	Braille Keyboard Dot 1
0x0202	Braille Keyboard Dot 2	Braille Keyboard Dot 2
0x0203	Braille Keyboard Dot 3	Braille Keyboard Dot 3
0x0204	Braille Keyboard Dot 4	Braille Keyboard Dot 4
0x0205	Braille Keyboard Dot 5	Braille Keyboard Dot 5
0x0206	Braille Keyboard Dot 6	Braille Keyboard Dot 6
0x0209	Braille Keyboard Space	Braille Keyboard Space

Braille display accessories with braille keyboards may implement individual keys emitting the following usages:

Table 16-4 Optional Braille Display Page (0x41) controls for use by display with keyboard

Usage ID	Usage Name	Apple Function
0x0207	Braille Keyboard Dot 7	Braille Keyboard Dot 7
0x0208	Braille Keyboard Dot 8	Braille Keyboard Dot 8

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Usage ID	Usage Name	Apple Function
0x020A	Braille Keyboard Left Space	Braille Keyboard Left Space
0x020B	Braille Keyboard Right Space	Braille Keyboard Right Space

Braille display accessories with braille keyboards shall support the ability to send all Braille Keyboard Dot and Space usages simultaneously.

16.1.2 Screen Reader Controls

Braille displays may include a controls to interface with a screen reader.

Braille display accessories supporting screen reader controls shall support the following usages:

Table 16-5 Required Braille Display Page (0x41) usages for use by display with screen reader controls

Usage ID	Usage Name	Apple Function
0x0006	Screen Reader Control	Screen Reader Controls (See Table 16-7 (page 120).)
0x0007	Screen Reader Identifier	Screen Reader Identifier (See Table 16-6 (page 119).)

The screen reader identifier is a 128 bit UUID from the device identifying the active screen reader. Table 16-6 (page 119) lists Apple screen reader identifiers.

VoiceOver (https://www.apple.com/accessibility/features/?vision) is the screen reader feature built into Apple's operating systems. Users who are blind or have low vision can interact with and control devices and Mac computers simply by moving their finger over the touchscreen or touch-sensitive trackpad. When VoiceOver is paired with a Braille display, users are able to use VoiceOver even if they are unable to touch the device display.

Table 16-6 Apple screen reader identifiers

Screen Reader	Screen Reader Identifier
iOS/iPadOS/tvOS VoiceOver	D211EC73–AE43–4B2B–A691–5F6620B4DBF6
macOS VoiceOver	BC4B74EA–B787–4A6D–B572–4E2D746A9AFD

The screen reader control array is populated with Button Page (0x09) usages. The behavior of each usage depends on the active screen reader. Table 16-7 (page 120) lists Apple screen reader functions for each usage.

Braille display accessories may support the following screen reader control usages:

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Table 16-7 Optional Button Page (0x09) usages for use by display with screen reader controls

Usage ID	Usage Name	Apple Function
0x01	Button 1	Next Braille Input Mode
0x02	Button 2	Next Braille Output Mode
0x03	Button 3	Pan Braille Left
0x04	Button 4	Pan Braille Right
0x05	Button 5	Delete Braille
0x06	Button 6	Forward Delete Braille
0x07	Button 7	Activates Return Key
0x08	Button 8	Escape Current Context
0x09	Button 9	Toggle Contracted Braille
0x0A	Button 10	Toggle Eight-Dot Braille
0x11	Button 17	Go to Status Bar
0x12	Button 18	Go to First Item
0x13	Button 19	Go to Last item
0x14	Button 20	Move to Previous Item
0x15	Button 21	Move to Next Item
0x16	Button 22	Read Page
0x17	Button 23	Read Page Starting at Focused Item
0x18	Button 24	Scroll Left One Page
0x19	Button 25	Scroll Right One Page
0x1A	Button 26	Scroll Up One Page
0x1B	Button 27	Scroll Down One Page
0x21	Button 33	Next Virtual Menu Item
0x22	Button 34	Previous Virtual Menu Item
0x23	Button 35	Select Previous Virtual Menu Item Setting
0x24	Button 36	Select Next Virtual Menu Item Setting
0x25	Button 37	Perform Tap
0x26	Button 38	Pause/Continue Speech
0x27	Button 39	Perform Contextual Action
0x31	Button 49	Move to Desktop
0x32	Button 50	Move to Taskbar
0x33	Button 51	Move to Menu Bar
0x34	Button 52	Start Interaction with Item
0x35	Button 53	Stop Interaction with Item
0x41	Button 65	Navigate Up
0x42	Button 66	Navigate Down

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Usage ID	Usage Name	Apple Function
0x43	Button 67	Navigate Left
0x44	Button 68	Navigate Right
0x45	Button 69	Navigate Up with Wrapping
0x46	Button 70	Navigate Down with Wrapping
0x47	Button 71	Navigate Left with Wrapping
0x48	Button 72	Navigate Right with Wrapping
0x49	Button 73	Next Heading
0x4A	Button 74	Previous Heading
0x4B	Button 75	Next Graphic
0x4C	Button 76	Previous Graphic
0x4D	Button 77	Next Table
0x4E	Button 78	Previous Table
0x4F	Button 79	Next List
0x50	Button 80	Previous List
0x51	Button 81	Next Control
0x52	Button 82	Previous Control
0x53	Button 83	Next Blockquote
0x54	Button 84	Previous Blockquote
0x55	Button 85	Next Same Blockquote
0x56	Button 86	Previous Same Blockquote
0x57	Button 87	Next Link
0x58	Button 88	Previous Link
0x59	Button 89	Next Visited Link
0x5A	Button 90	Previous Visited Link
0x5B	Button 91	Next Same Heading
0x5C	Button 92	Previous Same Heading
0x5D	Button 93	Next Bold Text
0x5E	Button 94	Previous BoldT ext
0x5F	Button 95	Next Italic Text
0x60	Button 96	Previous Italic Text
0x61	Button 97	Next Underline Text
0x62	Button 98	Previous Underline Text
0x63	Button 99	Next Misspelled Word
0x64	Button 100	Previous Misspelled Word
0x65	Button 101	Next Plain Text
0x66	Button 102	Previous Plain Text
0x67	Button 103	Next Color Change
0x68	Button 104	Previous Color Change

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Usage ID	Usage Name	Apple Function
0x69	Button 105	Next Font Change
0x6A	Button 106	Previous Font Change
0x6B	Button 107	Next Style Change
0x6C	Button 108	Previous Style Change
0x6D	Button 109	Next Same Element
0x6E	Button 110	Previous Same Element
0x6F	Button 111	Next Different Element
0x70	Button 112	Previous Different Element

16.2 Examples

16.2.1 Example HID Report Descriptor

The following descriptor is for a 20 cell braille display with integrated keyboard and screen reader controls.

```
0x05, 0x41,        // Usage Page (Braille)
0x09, 0x01,        // USAGE (Braille Display)
0xA1, 0x01,        // Collection (Application)
0x1A, 0x01, 0x02,  //   Usage Minimum (Braille Keyboard Dot 1)
0x2A, 0x08, 0x02,  //   Usage Maximum (Braille Keyboard Dot 8)
0x75, 0x01,        //   Report Size (1)
0x95, 0x08,        //   Report Count (8)
0x15, 0x00,        //   Logical Minimum (0)
0x25, 0x01,        //   Logical Maximum (1)
0x81, 0x02,        //   Input (Data,Var,Abs,No Wrap,Linear,Preferred State,No Null Position)
0x05, 0x41,        //   Usage Page (Braille)
0x0A, 0x09, 0x02,  //   Usage (Braille Keyboard Space)
0x0A, 0x0A, 0x02,  //   Usage (Braille Keyboard Left Space)
0x0A, 0x0B, 0x02,  //   Usage (Braille Keyboard Right Space)
0x75, 0x01,        //   Report Size (1)
0x95, 0x03,        //   Report Count (3)
0x15, 0x00,        //   Logical Minimum (0)
0x25, 0x01,        //   Logical Maximum (1)
0x81, 0x02,        //   Input (Data,Var,Abs,No Wrap,Linear,Preferred State,No Null Position)
0x75, 0x01,        //   Report Size (1)
0x95, 0x05,        //   Report Count (5)
0x15, 0x00,        //   Logical Minimum (0)
0x25, 0x01,        //   Logical Maximum (1)
0x81, 0x02,        //   Input (Data,Var,Abs,No Wrap,Linear,Preferred State,No Null Position)
0x05, 0x41,        //   Usage Page (Braille)
0xA1, 0x02,        //   Collection (Logical)
0x05, 0x0A,        //     Usage Page (Ordinal)
0x09, 0x01,        //     Usage (Instance 1)
```

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

```
0xA1, 0x02,        //     Collection (Logical)
0x05, 0x41,        //       Usage Page (Braille)
0x0A, 0x10, 0x02,  //       Usage (Braille Joystick Center)
0x0A, 0x11, 0x02,  //       Usage (Braille Joystick Up)
0x0A, 0x12, 0x02,  //       Usage (Braille Joystick Down)
0x0A, 0x13, 0x02,  //       Usage (Braille Joystick Left)
0x0A, 0x14, 0x02,  //       Usage (Braille Joystick Right)
0x75, 0x01,        //       Report Size (1)
0x95, 0x05,        //       Report Count (8)
0x15, 0x00,        //       Logical Minimum (0)
0x25, 0x01,        //       Logical Maximum (1)
0x81, 0x02,        //       Input (Data,Var,Abs,No Wrap,Linear,Preferred State,No Null Position)
0xC0,              //     End Collection
0x05, 0x0A,        //     Usage Page (Ordinal)
0x09, 0x02,        //     Usage (Instance 2)
0xA1, 0x02,        //     Collection (Logical)
0x05, 0x41,        //       Usage Page (Braille)
0x0A, 0x10, 0x02,  //       Usage (Braille Joystick Center)
0x0A, 0x11, 0x02,  //       Usage (Braille Joystick Up)
0x0A, 0x12, 0x02,  //       Usage (Braille Joystick Down)
0x0A, 0x13, 0x02,  //       Usage (Braille Joystick Left)
0x0A, 0x14, 0x02,  //       Usage (Braille Joystick Right)
0x75, 0x01,        //       Report Size (1)
0x95, 0x05,        //       Report Count (8)
0x15, 0x00,        //       Logical Minimum (0)
0x25, 0x01,        //       Logical Maximum (1)
0x81, 0x02,        //       Input (Data,Var,Abs,No Wrap,Linear,Preferred State,No Null Position)
0xC0,              //     End Collection
0x75, 0x01,        //     Report Size (1)
0x95, 0x06,        //     Report Count (6)
0x15, 0x00,        //     Logical Minimum (0)
0x25, 0x01,        //     Logical Maximum (1)
0x81, 0x02,        //     Input (Data,Var,Abs,No Wrap,Linear,Preferred State,No Null Position)
0xC0,              //   End Collection
0x0A, 0x0D, 0x02,  //   Usage (Braille Left Controls)
0xA1, 0x02,        //   Collection (Logical)
0x05, 0x09,        //     Usage Page (Button)
0x19, 0x01,        //     Usage Minimum (Button 1)
0x29, 0x03,        //     Usage Maximum (Button 3)
0x75, 0x01,        //     Report Size (1)
0x95, 0x03,        //     Report Count (3)
0x15, 0x00,        //     Logical Minimum (0)
0x25, 0x01,        //     Logical Maximum (1)
0x81, 0x02,        //     Input (Data,Var,Abs,No Wrap,Linear,Preferred State,No Null Position)
0x05, 0x41,        //     Usage Page (Braille)
0x0A, 0x1A, 0x02,  //     Usage (Pan Left)
0x75, 0x01,        //     Report Size (1)
0x95, 0x01,        //     Report Count (1)
0x15, 0x00,        //     Logical Minimum (0)
0x25, 0x01,        //     Logical Maximum (1)
0x81, 0x02,        //     Input (Data,Var,Abs,No Wrap,Linear,Preferred State,No Null Position)
0xC0,              //   End Collection
0x05, 0x41,        //   Usage Page (Braille)
```

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

```
0x0A, 0x0E, 0x02,  //   Usage (Braille Right Controls)
0xA1, 0x02,        //   Collection (Logical)
0x05, 0x09,        //     Usage Page (Button)
0x19, 0x01,        //     Usage Minimum (Button 1)
0x29, 0x03,        //     Usage Maximum (Button 3)
0x75, 0x01,        //     Report Size (1)
0x95, 0x03,        //     Report Count (3)
0x15, 0x00,        //     Logical Minimum (0)
0x25, 0x01,        //     Logical Maximum (1)
0x81, 0x02,        //     Input (Data,Var,Abs,No Wrap,Linear,Preferred State,No Null Position)
0x05, 0x41,        //     Usage Page (Braille)
0x0A, 0x1B, 0x02,  //     Usage (Pan Right)
0x75, 0x01,        //     Report Size (1)
0x95, 0x01,        //     Report Count (1)
0x15, 0x00,        //     Logical Minimum (0)
0x25, 0x01,        //     Logical Maximum (1)
0x81, 0x02,        //     Input (Data,Var,Abs,No Wrap,Linear,Preferred State,No Null Position)
0xC0,              //   End Collection
0x05, 0x41,        //   Usage Page (Braille)
0x0A, 0x0F, 0x02,  //   Usage (Braille Top Controls)
0xA1, 0x02,        //   Collection (Logical)
0x05, 0x09,        //     Usage Page (Button)
0x19, 0x01,        //     Usage Minimum (Button 1)
0x29, 0x03,        //     Usage Maximum (Button 3)
0x75, 0x01,        //     Report Size (1)
0x95, 0x03,        //     Report Count (3)
0x15, 0x00,        //     Logical Minimum (0)
0x25, 0x01,        //     Logical Maximum (1)
0x81, 0x02,        //     Input (Data,Var,Abs,No Wrap,Linear,Preferred State,No Null Position)
0x05, 0x41,        //     Usage Page (Braille)
0x0A, 0x15, 0x02,  //     Usage (Braille D-Pad Center)
0x0A, 0x16, 0x02,  //     Usage (Braille D-Pad Up)
0x0A, 0x17, 0x02,  //     Usage (Braille D-Pad Down)
0x0A, 0x18, 0x02,  //     Usage (Braille D-Pad Left)
0x0A, 0x19, 0x02,  //     Usage (Braille D-Pad Right)
0x75, 0x01,        //     Report Size (1)
0x95, 0x05,        //     Report Count (5)
0x15, 0x00,        //     Logical Minimum (0)
0x25, 0x01,        //     Logical Maximum (1)
0x81, 0x02,        //     Input (Data,Var,Abs,No Wrap,Linear,Preferred State,No Null Position)
0xC0,              //   End Collection
0x05, 0x41,        //   Usage Page (Braille)
0x0A, 0x0C, 0x02,  //   Usage (Braille Face Controls)
0xA1, 0x02,        //   Collection (Logical)
0x05, 0x09,        //     Usage Page (Button)
0x19, 0x01,        //     Usage Minimum (Button 1)
0x29, 0x04,        //     Usage Maximum (Button 4)
0x75, 0x01,        //     Report Size (1)
0x95, 0x04,        //     Report Count (4)
0x15, 0x00,        //     Logical Minimum (0)
0x25, 0x01,        //     Logical Maximum (1)
0x81, 0x02,        //     Input (Data,Var,Abs,No Wrap,Linear,Preferred State,No Null Position)
0x05, 0x41,        //     Usage Page (Braille)
```

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

```
0x0A, 0x1C, 0x02,  //     Usage (Braille Rocker Up)
0x0A, 0x1D, 0x02,  //     Usage (Braille Rocker Down)
0x0A, 0x1E, 0x02,  //     Usage (Braille Rocker Press)
0x75, 0x01,        //     Report Size (1)
0x95, 0x03,        //     Report Count (3)
0x15, 0x00,        //     Logical Minimum (0)
0x25, 0x01,        //     Logical Maximum (1)
0x81, 0x03,        //     Input (Const,Var,Abs,No Wrap,Linear,Preferred State,No Null Position)
0x75, 0x01,        //     Report Size (1)
0x95, 0x01,        //     Report Count (1)
0x15, 0x00,        //     Logical Minimum (0)
0x25, 0x01,        //     Logical Maximum (1)
0x81, 0x03,        //     Input (Const,Var,Abs,No Wrap,Linear,Preferred State,No Null Position)
0xC0,              //   End Collection
0x05, 0x41,        //   Usage Page (Braille)
0x09, 0x06,        //   USAGE (Screen Reader Controls)
0xA1, 0x02,        //     Collection (Logical)
0x05, 0x09,        //     Usage Page (Button)
0x19, 0x01,        //     Usage Minimum (Button 1)
0x29, 0x08,        //     Usage Maximum (Button 8)
0x75, 0x01,        //     Report Size (1)
0x95, 0x08,        //     Report Count (8)
0x15, 0x00,        //     Logical Minimum (0)
0x25, 0x01,        //     Logical Maximum (1)
0x81, 0x02,        //     Input (Data,Var,Abs,No Wrap,Linear,Preferred State,No Null Position)
0xC0,              //   End Collection
0x05, 0x41,        //   Usage Page (Braille)
0x09, 0x02,        //   USAGE (Braille Row)
0xA1, 0x02,        //   Collection (Logical)
0x09, 0x04,        //     Usage (8 Dot Braille Cell)
0x15, 0x00,        //     Logical Minimum (0)
0x26, 0xFF, 0x00,  //     Logical Maximum (255)
0x75, 0x08,        //     Report Size (8)
0x95, 0xA,         //     Report Count (20)
0x91, 0x03,        //     Output (Const,Var,Abs,No Wrap,Linear,Preferred State,No Null
Position,Non-volatile)
0x09, 0xFA,        //     USAGE (Router Set 1)
0xA1, 0x02,        //     Collection (Logical)
0x0A, 0x00, 0x01,  //       Usage (Router Key)
0x0A, 0x00, 0x01,  //       Usage (Router Key)
0x0A, 0x00, 0x01,  //       Usage (Router Key)
0x0A, 0x00, 0x01,  //       Usage (Router Key)
0x0A, 0x00, 0x01,  //       Usage (Router Key)
0x0A, 0x00, 0x01,  //       Usage (Router Key)
0x0A, 0x00, 0x01,  //       Usage (Router Key)
0x0A, 0x00, 0x01,  //       Usage (Router Key)
0x0A, 0x00, 0x01,  //       Usage (Router Key)
0x0A, 0x00, 0x01,  //       Usage (Router Key)
0x0A, 0x00, 0x01,  //       Usage (Router Key)
0x0A, 0x00, 0x01,  //       Usage (Router Key)
0x0A, 0x00, 0x01,  //       Usage (Router Key)
0x0A, 0x00, 0x01,  //       Usage (Router Key)
0x0A, 0x00, 0x01,  //       Usage (Router Key)
0x0A, 0x00, 0x01,  //       Usage (Router Key)
0x0A, 0x00, 0x01,  //       Usage (Router Key)
```

```
0x0A, 0x00, 0x01,  //       Usage (Router Key)
0x0A, 0x00, 0x01,  //       Usage (Router Key)
0x0A, 0x00, 0x01,  //       Usage (Router Key)
0x0A, 0x00, 0x01,  //       Usage (Router Key)
0x0A, 0x00, 0x01,  //       Usage (Router Key)
0x15, 0x00,        //       Logical Minimum (0)
0x25, 0x01,        //       Logical Maximum (1)
0x75, 0x01,        //       Report Size (1)
0x95, 0x14,        //       Report Count (20)
0x81, 0x02,        //       Input (Data,Var,Abs,No Wrap,Linear,Preferred State,No Null Position)
// 4-bit padding
0x75, 0x04,        //       Report Size (4)
0x95, 0x01,        //       Report Count (1)
0x81, 0x02,        //       Input (Data,Var,Abs,No Wrap,Linear,Preferred State,No Null Position)
0xC0,              //     End Collection
0xC0,              //   End Collection
0x05, 0x41,        //   Usage Page (Braille)
0x09, 0x07,        //   USAGE (Screen Reader Identifier)
0x95, 0x01,        //   Report Count (1)
0x75, 0x80,        //   Report Size (128)
0xB1, 0x02,        //   FEATURE (Data,Var,Abs)
0xC0,              // End Collection
```

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

17. External Storage

Devices support external storage, such as USB drives and SD card readers, to:

- Store and access files.
- Import and export photos.
- Record video.

17.1 Overview

Accessories may support moving data to or from a device using:

- *USB Mass Storage Class Specification Overview–Version 1.4*, see https://www.usb.org/document-library/mass-storage-class-specification-overview-14.
- External Accessory Protocol (page 187).

17.2 Apple ProRes 4K

To support Apple ProRes capture at 4K, external storage shall:

- Be ExFAT formatted.
- Sustain a write speed of incompressible data, sampled every second, across the entire storage capacity, of at least:
  - 440 MB/s for 4K at 120 fps.
  - 220 MB/s for 4K at 60 fps.
  - 510 MB/s for ProRes RAW (4K at 120 fps).
- Not exceed 900 mA of current draw at any point in time. See Accessory Power (USB-C) (page 162).

For more information on Apple ProRes, including specific device support, see https://support.apple.com/en-us/109041.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

17.3 Verification

17.3.1 Apple ProRes 4K

17.3.1.1 Equipment

The following equipment is necessary:

- Device supporting external Apple ProRes 4K capture running iOS 18.0 or later, see https://support.apple.com/en-us/109041.

17.3.1.2 Setup

1. Fully charge the device.
2. Attach the external storage.
3. Erase and format the external storage as ExFAT:
   a. Open Files and browse to the top level.
   b. Long press the external storage entry and select Erase.
   c. Verify the external storage is empty.
4. Open Settings > Camera > Formats and enable Apple ProRes under Video Capture.
5. Verify ProRes encoding is set to HDR.

17.3.1.3 Procedure

1. Attach the external storage to the device.
2. Open Camera, select Video and enable ProRes HDR from the Camera header.
3. Select the resolution indicator until it displays 4K.
4. Select the fps indicator until it displays:
   - 120 for devices and accessories supporting 4K at 120 fps.
   - 60 for devices and accessories supporting 4K at 60 fps.
5. Verify the Max Time indicator is displayed.
6. Verify the 'USB-C' indicator is displayed near the USB-C port.
7. Record video including motion (camera pan/tilt, people, vehicles) for at least 10 minutes.
8. Stop recording and wait for all data to be written to external storage.
9. Verify no error messages are displayed.
10. Attach the external storage to a Mac and play the video.
11. Verify the video playback is smooth, with no choppiness or missing frames.
12. Repeat the procedure, recording video until the drive is full, and verify all video is smooth, with no choppiness or missing frames.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

18. AirPods Accessories

Accessories shall not interfere with AirPods operation. Keep-out regions may be found in the device dimensional drawings, see:

- AirPods Pro 3 (page 609).
- AirPods 4 (page 613).
- AirPods Pro (2nd generation) (page 620).
- AirPods (3rd generation) (page 622).
- AirPods Max, 1 of 6 (page 623).
- AirPods Pro (1st generation) (page 630).
- AirPods (2nd generation) and AirPods (1st generation) (page 632).

18.1 Charging Case Covers

Charging case covers shall:

- Not interfere with AirPods charging case operation.
- Have a uniform thickness across the metal keep-out region.
- Not exceed 2.5 mm in thickness. Apple recommends 1.0 mm for maximum compatibility with inductive transmitters.

Keep-out regions may be found in the device dimensional drawings, see:

- MagSafe Charging Case for AirPods Pro 3, 1 of 3 (page 606).
- Wireless Charging Case (USB-C) for AirPods 4, 1 of 3 (page 610).
- MagSafe Charging Case (USB-C) for AirPods Pro (2nd generation), 1 of 3 (page 614).
- MagSafe Charging Case for AirPods Pro (2nd generation), 1 of 3 (page 617).
- MagSafe Charging Case for AirPods (3rd generation) (page 621).
- Wireless Charging Case for AirPods Pro (1st generation) (page 629).
- Wireless Charging Case for AirPods (page 631).

Case covers claiming compatibility with Apple Watch chargers shall not obstruct the Apple Watch charger keep-out region, see:

- MagSafe Charging Case for AirPods Pro 3, 2 of 3 (page 607).
- Wireless Charging Case (USB-C) for AirPods 4, 2 of 3 (page 611).
- MagSafe Charging Case (USB-C) for AirPods Pro (2nd generation), 2 of 3 (page 615).
- MagSafe Charging Case for AirPods Pro (2nd generation), 2 of 3 (page 618).

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

18.2 Chargers

Wired charging accessories shall:

- Provide 5 W (1.0 A at 5 V) at all times using:
  - *USB Battery Charging Specification –Release 1.2*.
  - USB enumeration.
  - USB Power Delivery (PD) (page 240).
  - USB Type-C Current (page 241).

Wireless charging accessories shall meet the requirements in Device Power (Inductive) (page 182).

18.3 AirPods Max Accessories

Accessories shall not stretch the headband or canopy. Accessories should use soft, compliant materials such as microfiber or silicone.

If the accessory is a case for AirPods Max (USB-C), the keep-out for the USB-C connector:

- Shall be at least 12.35 mm by 6.50 mm.
- Should be at least 12.45 mm by 6.60 mm with full radii rounded edges for the greatest compatibility with the widest variety of cables and docks, see USB-C receptacle accessory keep-out (page 315).

18.3.1 Sleep Mode

Accessories may enable sleep mode to help maintain the battery charge. Sleep mode is activated when AirPods Max:

- Is not charging.
- Magnetic flux at the:
  - Right earcup is 125 to 167 gauss.
  - Left earcup is -111 to -161 gauss.

See Magnetic Flux Probe (page 131) for the precise measuring point, and AirPods Max, 2 of 6 (page 624) for datums.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

18.4 Magnetic Flux Probe



Copyright © 2025 Apple Inc. All Rights Reserved.

18.5 Verification

Test procedures for AirPods accessories.

18.5.1 MagSafe Charging with Case Cover

Power test procedures for AirPods charging case covers.

18.5.1.1 Equipment

The following equipment is necessary:

- AirPods.
- AirPods charging case.
- Apple MagSafe Charger.
- Device running iOS 26.1 or later.

18.5.1.2 Setup

1. Insert AirPods into charging case.
2. Unlock the device and open the charging case lid.
3. Pair AirPods with the device, if necessary.
4. Using the device, verify the state of charge for:
   a. Charging case is less than 80%.
   b. AirPods is less than 50%.
5. Close the charging case lid.
6. Verify the MagSafe charger is plugged into a functional power source.
7. Place the charging case onto the MagSafe charger on a flat surface.
8. Verify the charging case LED turns on momentarily.
9. Monitor the charging case LED for 30 seconds and verify the LED turns off.
10. Tap the charging case and verify the LED turns on momentarily.

18.5.1.3 Procedure

1. Attach the cover to the AirPods charging case.
2. Place the charging case and attached cover onto a MagSafe charger on a flat surface.
3. Verify the charging case LED turns on momentarily.
4. Monitor the charging case LED for 30 seconds and verify the LED turns off.
5. Tap the charging case and verify the LED turns on momentarily.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

19. Apple Vision Pro Accessories

Accessories shall not interfere with Apple Vision Pro operation. Keep-out regions may be found in the device dimensional drawings, see:

- Apple Vision Pro, 1 of 8 (page 592)
- Apple Vision Pro, 2 of 8 (page 593)
- Apple Vision Pro, 3 of 8 (page 594)
- Apple Vision Pro, 4 of 8 (page 595)
- Apple Vision Pro, 5 of 8 (page 596)
- Apple Vision Pro, 6 of 8 (page 597)
- Apple Vision Pro, 7 of 8 (page 598)
- Apple Vision Pro, 8 of 8 (page 599)
- Apple Vision Pro Battery (page 600)
- Apple Vision Pro Audio Strap (page 601)
- ZEISS Optical Inserts, 1 of 4 (page 602)
- ZEISS Optical Inserts, 2 of 4 (page 603)
- ZEISS Optical Inserts, 3 of 4 (page 604)
- ZEISS Optical Inserts, 4 of 4 (page 605)

19.1 Apple Vision Pro Storage Cases

Storage cases shall:

- Not interfere with the click or rotation function of the top button, digital crown, and fit dial.
- Not apply force on the top button, digital crown, and fit dial.
- Minimize contact with all glass surfaces, including the display and optics. When necessary, use a soft non-abrasive material.
- Maintain a power cable bend radius of at least 13 mm at the Apple Vision Pro Battery.

19.2 Apple Vision Pro Battery Holders

Battery holders should maintain at least 25% surface exposure for heat dissipation, see Apple Vision Pro Battery (page 600).

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

19.3 Apple Vision Pro Bands

Bands attaching to the Apple Vision Pro Audio Strap connector shall:

- Be designed to prevent hair snag between the connector and mating parts, particularly in small spaces and between hard materials.
- Not detach with a peel force less than 100 N at 12 mm from the connector.
- Have a maximum insertion force of 18.3 N.
- Not have metal contact with the elastomer portion of Apple Vision Pro Audio Strap.
- Not have a material hardness exceeding 320 HV for portions contacting the Apple Vision Pro Audio Strap connector.
- Have a maximum normal pull force of 300 N on the Apple Vision Pro Audio Strap connector.

19.4 Verification

Test procedures for Apple Vision Pro accessories.

19.4.1 Equipment

The following equipment is necessary:

- Apple Vision Pro Audio Strap.
- Digital force gauge, such as the Chatillon DFX II.
- Hook attachment for digital force gauge.
- Clamps, or a vice, to securely hold the Apple Vision Pro Audio Strap on a flat level surface.

19.4.2 Peel Force

Peel force test procedure for Apple Vision Pro Bands.

1. Clamp the Apple Vision Pro Audio Strap as close to the connector as possible.
2. Apply ramping force to the band at 12 mm from the connector until 100 N of force is reached, see Figure 19-1 (page 135).
3. Verify the band is still attached to the Apple Vision Pro Audio Strap. Material failure on the band is allowed.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 19-1 Peel force test setup



20. Watch Bands

A well-designed watch band will securely attach to Apple Watch without interfering with Apple Watch operation. See Device Dimensional Drawings (page 328) for Apple Watch keep-out zones.

20.1 Requirements

Watch bands for Apple Watch shall integrate two lugs to mate with the watch band interface, see:

- Apple Watch Band Interface (49 mm) (page 140)
- Apple Watch Band Interface (42 mm & 46 mm) (page 141)
- Apple Watch Band Interface (41 mm & 45 mm) (page 142)
- Apple Watch Band Interface (40 mm & 44 mm) (page 143)

Apple Watch uses a high precision interface profile, see https://developer.apple.com/accessories/apple-watch-lug-profile.zip for a sample 2D lug profile. Lugs should lock into the watch band mating slot with a 'lug latch' feature to prevent accidental removal of the watch band.

Exposed edges of watch bands and lugs shall pass *UL 1439, Tests for Sharpness of Edges on Equipment* and *BS EN 71-1:2014, Safety of toys - Part 1: Mechanical and physical properties*.

The lug latch shall never become jammed in the extended position.

Watch bands shall not integrate magnetic chargers.

Watch bands and lugs should:

- Pass a 72 hour salt mist test as specified in *ASTM B117* with no visible corrosion.
- Resist a 5-20 kgf lateral slide-out force when installed in Apple Watch.
- Resist a 20 kgf or greater pull force as specified in *ISO-6245:1996, Specifications for Diver's Watches –Section 7.3*.
- Detach easily from Apple Watch when the watch band release buttons are pressed.
- Take into account the weight of Apple Watch.

Watch bands shall enable the user to maintain direct skin contact with Apple Watch heart sensors and the back of Apple Watch, and shall incorporate sufficient margin to compensate for shifting or dimensional changes of the watch band material. Failure to do so may interfere with Apple Watch wrist detect and Apple Pay features. Watch bands should:

- Have length sizing adjustment pitch of less than 7 mm (center to center).

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- Provide sufficient adjustability for the user to achieve a snug, yet comfortable fit preventing movement of Apple Watch relative to the wearer's skin.

Watch bands intended for use during exercise should maintain a snug fit through a full range of motion to maintain compatibility with Apple Watch heart sensors.

Apple recommends the following materials for lug bodies:
- 75 Shore A silicone.
- 50-55% glass-filled nylon.
- 240-270HV 316L / EN 1.4435 stainless steel.

Apple recommends the following materials for lug latches:
- 50-55% glass-filled nylon.
- 240-270HV 316L / EN 1.4435 stainless steel.

Watch bands for Apple Watch shall comply with applicable environmental regulations for the regions in which the watch bands are to be sold, and any applicable substance or material restrictions, including applicable restrictions on:
- Organic tin compounds, PFOS, PFOA, phthalates, azo dyes, polybrominated biphenyls (PBBs) and PAHs, per requirements of the EU REACh regulation EC 1907/2006.
- Nickel leach rate on surfaces in prolonged skin contact, per requirements of the EU REACh regulation EC 1907/2006.
- Cadmium, lead, hexavalent chromium, and nickel, per requirements of EU Directive 2009/48/EC.
- Natural rubber latex, per requirements of EU Directive EC 93/42/EEC.
- Dimethylfumarate (DMFu), per requirements of EU Regulation 412/2012.
- pH and Formaldehyde, per requirements of China GB 18401 for textiles and China GB 20400 for leather.
- Endangered species of flora and fauna in products or packaging (US Lacey Act).
- Polybrominated diphenyl ethers (PBDE).

20.2 Example Apple Watch Lug Assembly

Assembly instructions are based on an assembly fixture with a clamping mechanism and example watch bands:
- Example Apple Watch Lug (49 mm) (page 144)
- Example Apple Watch Lug (42 mm & 46 mm) (page 145)
- Example Apple Watch Lug (41 mm & 45 mm) (page 146)
- Example Apple Watch Lug (40 mm & 44 mm) (page 147)

Proper assembly of the lug is critical to ensure the watch band securely attaches to Apple Watch. Improper assembly may result in damage to Apple Watch and/or the watch band.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Screw threads should be secured with Loctite 435. Previously installed/used screws should not be reused.

The assembly fixture should hold the lug assembly in place and a clamping mechanism should compress the lug during screw insertion.

Assemble the watch band and lug as follows, see Figure 20-1 (page 139).

1. Lightly insert the long end of the female pin in the watch band until hard stop. Ensure there is no warping or damage in the watch band.
2. Lightly insert the long end of the male pin in the other side of the band until it interlocks with the female pin and both pins are seated together. Ensure there is no warping or damage in the watch band.
3. Align the holes on the bottom of the lug with the exposed ends of the female and male pins. Note lug latch top/bottom orientation relative to the watch band. Latch shall be on the side of the watch band against the wrist.
4. Apply Loctite 435 to screw threads.
5. Install both screws using the following specification:
   - Torque: 1.1 kgf-cm ±10%
   - RPM: 120 ±10%
6. Visually inspect at 1200-1400 lux for screw proudness and cross-threading.
7. Ensure screws are just sub-flush to the lowest part of the counterbore and appear parallel to the long axis of the lug.
8. Ensure screws are undamaged, flat, and concentric with the counterbore.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 20-1 Apple Watch lug assembly fixture



2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

20.3 Apple Watch Band Interface (49 mm)



20.4 Apple Watch Band Interface (42 mm & 46 mm)

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. EXPOSED EDGES MUST CONFORM TO UL 1439: TESTS FOR SHARPNESS OF EDGES ON EQUIPMENT AND BS EN71-1: SAFETY OF TOYS
2. EDGES MUST BE FREE FROM BURRS/FLASH





CURVE AT LUG MIDLINE, 46MM WATCH



CURVE AT LUG MIDLINE, 42MM WATCH



LATCH EXTENDED



LATCH RETRACTED





SECTION A - A



SECTION B - B

METRIC	Apple Inc.
DRAWTER / DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER / DATE	
DIMENSIONS ARE IN MILLIMETERS TOLERANCES	TITLE: APPLE WATCH BAND INTERFACE
DO NOT SCALE DRAWINGS	DRAWING NUMBER / REV.
THIRD ANGLE PROJECTION / SIZE D	SCALE NONE / SHT / OF

NX GENERATED

20.5 Apple Watch Band Interface (41 mm & 45 mm)

NOTES: (UNLESS OTHERWISE SPECIFIED)

[1] EXPOSED EDGES MUST CONFORM TO UL 1439: TESTS FOR SHARPNESS OF EDGES ON EQUIPMENT AND BS EN71-1: SAFETY OF TOYS

[2] EDGES MUST BE FREE FROM BURRS/FLASH





CURVE AT LUG MIDLINE, 45MM WATCH



CURVE AT LUG MIDLINE, 41MM WATCH



LATCH EXTENDED



LATCH RETRACTED





SECTION A - A



SECTION B - B

METRIC	Apple Inc.
DRAWTER / DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVERSE ENGINEER OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER / DATE	
DIMENSIONS ARE IN MILLIMETERS TOLERANCES	TITLE: APPLE WATCH BAND INTERFACE
DO NOT SCALE DRAWINGS	DRAWING NUMBER / REV.
THIRD ANGLE PROJECTION / SIZE D	SCALE NONE / SHT / OF

NX GENERATED

20.6 Apple Watch Band Interface (40 mm & 44 mm)

NOTES:

[1] EXPOSED EDGES MUST CONFORM TO UL 1439: TESTS FOR SHARPNESS OF EDGES ON EQUIPMENT AND BS EN71-1: SAFETY OF TOYS.

[2] EDGES MUST BE FREE FROM BURRS/FLASH



LATCH EXTENDED



SECTION A-A





LATCH RETRACTED



SECTION B-B



CURVE AT LUG MIDLINE, 44MM WATCH



CURVE AT LUG MIDLINE, 40MM WATCH



METRIC	Apple Inc.
DRAFTER / DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO COPY OR REPRODUCE IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER / DATE	
DIMENSIONS ARE IN MILLIMETERS TOLERANCES	TITLE: APPLE WATCH BAND INTERFACE
DO NOT SCALE DRAWINGS	DRAWING NUMBER / REV.
THIRD ANGLE PROJECTION / SIZE D	SCALE: NONE / SHT / OF

NX GENERATED

Copyright © 2025 Apple Inc. All Rights Reserved.

20.7 Example Apple Watch Lug (49 mm)

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. EXPOSED EDGES MUST CONFORM TO UL 1439: TESTS FOR SHARPNESS OF EDGES ON EQUIPMENT AND BS EN71-1: SAFETY OF TOYS







SECTION A - A

METRIC	Apple Inc.
DRAFTER / DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER / DATE	
DIMENSIONS ARE IN MILLIMETERS TOLERANCES	TITLE: APPLE WATCH LUG
DO NOT SCALE DRAWINGS	DRAWING NUMBER / REV.
THIRD ANGLE PROJECTION	SIZE D / SCALE NONE / SHT / OF

NX GENERATED

20.8 Example Apple Watch Lug (42 mm & 46 mm)

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. EXPOSED EDGES MUST CONFORM TO UL 1439: TESTS FOR SHARPNESS OF EDGES ON EQUIPMENT AND BS EN71-1: SAFETY OF TOYS







METRIC	Apple Inc.
DRAFTER / DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER / DATE	
DIMENSIONS ARE IN MILLIMETERS TOLERANCES	TITLE: APPLE WATCH LUG
DO NOT SCALE DRAWINGS	DRAWING NUMBER / REV.
THIRD ANGLE PROJECTION / SIZE D	SCALE: NONE / SHT / OF

NX GENERATED

20.9 Example Apple Watch Lug (41 mm & 45 mm)



20.10 Example Apple Watch Lug (40 mm & 44 mm)

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. EXPOSED EDGES MUST CONFORM TO UL 1439: TESTS FOR SHARPNESS OF EDGES ON EQUIPMENT AND BS EN71-1: SAFETY OF TOYS.







METRIC	Apple Inc.
DRAFTER / DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER / DATE	
DIMENSIONS ARE IN MILLIMETERS TOLERANCES	TITLE: APPLE WATCH LUG
DO NOT SCALE DRAWINGS	DRAWING NUMBER / REV.
THIRD ANGLE PROJECTION	SIZE D / SCALE NONE / SHT / OF

NX GENERATED

21. Apple MagSafe Charger Mounts

Apple MagSafe Charger mounts (stands, docks, and other holders) provide a means to hold and position the charger and may support StandBy, see StandBy Mounts (page 149).

21.1 Mechanical

Mounts shall be compatible with:

- Apple MagSafe Charger (1 m) and Apple MagSafe Charger (2 m) (page 633)
- Apple MagSafe Charger (page 634)

Mounts should keep the Apple MagSafe Charger secure when attaching, detaching, or rotating a device.

Mounts shall not interfere with or cause Scratches and Damage (page 29) to the device.

To avoid interference with devices, mounts shall:

- Not exceed 30 mm from the center of the Apple MagSafe Charger surface towards the top edge of the device for all supported device orientations. If the device can be attached in any orientation, the accessory shall not exceed 30 mm in radius around the center of the Apple MagSafe Charger surface.
- Maintain a clearance of 5 mm from the back of the device (mating surface) for any part of the accessory past the 30 mm keep-in constraint.
- Stay within the MagSafe Accessory Enclosure Geometry (page 207).

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

22. StandBy Mounts

StandBy provides iPhone users a full-screen experience with glanceable information designed to be viewed from a distance when iPhone is in landscape orientation, locked, and charging. StandBy can be personalized to display a range of widgets and supports Live Activities, Siri, incoming calls, and notifications. StandBy remembers user's preferred views when using a MagSafe Charger.

Figure 22-1 MagSafe example

This feature is supported on iOS 17.0 or later.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

22.1 Product Design

Figure 22-2 StandBy mount example



Mounts supporting StandBy shall:

- Support landscape orientation.
- Support inductive or wired device charging.
- Not obstruct or touch the device cover glass or any device sensors.
- Not cause Scratches and Damage (page 29).

Mounts may be Apple MagSafe Charger Mounts (page 148).

The mounts should:

- Prevent free rotation of the device.
- Enable an adjustable backward tilt of at least 30° for optimal visibility.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- Be stable to prevent unintentionally exiting StandBy.
- Not obstruct Access to Controls (page 37).
- Implement Qi Wireless Power (page 182), version 2.0 or later, or the MagSafe Accessory Magnet Array (page 198).

22.2 Verification

22.2.1 Equipment

The following equipment is necessary:

- Supported device running iOS 17.0 or later.
- Charger, if not integrated in accessory.

22.2.2 Enable StandBy

1. Attach locked device in landscape orientation to the accessory.
2. Attach a charger if the accessory does not integrate inductive or wired charging.
3. Verify device enters StandBy within a few seconds.

22.2.3 Product Design

Verify the StandBy Mount:

1. Supports landscape orientation.
2. Does not obstruct or touch the device cover glass or any device sensors.
3. Does not scratch or damage device.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

23. Continuity Camera Mounts

Continuity Camera enables device cameras to be used with Apple TV or Mac and supports Portrait, Studio Light, Center Stage, Reactions, and Desk View video effects. System requirements for Continuity Camera are available at https://support.apple.com/en-us/108046#camera.

Mounts supporting Continuity Camera securely hold a device at the optimal height and angle to use with FaceTime and other apps.

Figure 23-1 MacBook Desk View example



2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

23.1 Product Design

Mounts supporting Continuity Camera shall:

- Support devices in portrait and landscape orientations.
- Enable use of a USB-C cable or USB to Lightning charge cable.
- Not touch the device cover glass, block any device camera field of view, or obstruct any ambient light sensors, see Device Dimensional Drawings (page 328).
- Not cause Scratches and Damage (page 29).

The mounts should:

- Prevent free rotation of the device.
- Enable a device camera lens height of at least 228 mm to support Desk View.
- Not obstruct Access to Controls (page 37).
- Implement the MagSafe Accessory Magnet Array (page 198).
- Support Tripod Connections (page 35).

Additional requirements apply to mounts used in the following scenerios:

- Apple TV Mount (page 154)
- MacBook Mount (page 155)
- iMac or Display Mount (page 156)

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

23.2 Apple TV Mount

Figure 23-2 Apple TV mount example



A mount designed for Apple TV shall:

- Be stable when placed on top, or in front of a TV.
- Not touch the display glass (active and non-active areas).
- Not sandwich or squeeze the TV and device together.

The mount should enable upward and downward tilt.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

23.3 MacBook Mount

Figure 23-3 MacBook mount example



A mount designed for MacBook, MacBook Air, and MacBook Pro shall:

- Not scratch or damage the MacBook.
- Not touch the MacBook display glass (active and non-active areas).
- Not interfere with or prevent fully closing the MacBook.
- Not sandwich or squeeze the MacBook and device together.

The mount should:

- Not cover or touch any portion of the MacBook display glass, camera, or other sensors.
- Enable a downward tilt in portrait orientation from 0° to 12° to support Desk View.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- Minimize the mass to maintain stability of the display.

23.4 iMac or Display Mount

Figure 23-4 Display mount example



A mount designed for iMac or displays shall:

- Not scratch or damage the iMac or display.
- Not touch the display glass (active and non-active areas).
- Not sandwich or squeeze the iMac or display and device together.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

The mount should:

- Not cover or touch any portion of the display glass, camera, microphones, or other sensors.
- Enable a downward tilt from 0° to 30° to support Desk View.

23.5 Verification

23.5.1 Equipment

The following equipment is necessary:

- If the mount is designed for Apple TV:
  - Supported devices running iOS 17.0 or later.
  - Apple TV 4K (2nd generation) or later running tvOS 17.0 or later, connected to a TV.
- If the mount is designed for Mac:
  - Supported devices running iOS 16.0 or later.
  - Mac running macOS 13.0 Ventura or later.
  - MacBook, MacBook Air, and MacBook Pro if the mount is designed for MacBook.
  - iMac if the mount is designed for iMac.
  - Variety of displays if the mount is designed for external displays.
  - USB-C cable.
  - USB to Lightning charge cable.
- Apple Account with two-factor authentication enabled and used on devices, Apple TV, and all Mac computers.
- Tripod, if the mount is designed for tripod connections.

23.5.2 Setup

23.5.2.1 Enable Continuity Camera on Apple TV

Configure an Apple TV and a device to enable Continuity Camera:

1. Open FaceTime on the Apple TV.
2. Select the user matching the device Apple Account.
3. Using the device, select the Continuity Camera notification and select Accept.
4. Attach the device to mount and orient it as prompted.
5. Verify Continuity Camera view displays full screen in FaceTime.

23.5.2.2 Enable Continuity Camera on Mac

Configure a Mac and a device to enable Continuity Camera:

1. Connect the device to the Mac using a cable.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

2. If the Mac is not a trusted computer, select Trust on the Trust This Computer alert on the device.
3. To use Continuity Camera wirelessly, disconnect the cable.
4. Attach the device to mount.
5. Open FaceTime on the Mac.
6. If the 'Use your iPhone as a Camera for your Mac' alert appears, select Continue.
7. Select the Continuity Camera option from the Video menu.
8. Verify Continuity Camera view displays in FaceTime.

Reconnect after the Mac and/or device are in sleep mode:

1. Wake the device and the Mac.
2. Connect the device to the Mac using a cable for a wired connection or disconnect the cable for a wireless connection.
3. Attach the device to the mount.
4. Open FaceTime on the Mac and select Continuity Camera from the Video menu.
5. Verify Continuity Camera view displays in FaceTime.

23.5.3 Product Design

Verify the mount:

1. Supports portrait and landscape orientations.
2. Does not touch the device cover glass or block any device camera field of view.
3. Does not scratch or damage the device.
4. When designed for tripods, complies with ISO 1222:2010.

If the mount is designed for Apple TV, verify the mount:

1. Is stable when placed on top, or in front of a TV.
2. Does not touch the display glass.
3. Does not sandwich or squeeze the TV and device together.

If the mount is designed for MacBook, iMac, or displays, verify the mount:

1. Does not touch the display glass.
2. Does not block any MacBook, iMac, or display camera field of view.
3. Does not sandwich or squeeze the device, MacBook, iMac, or display together.
4. Does not scratch or damage the device, MacBook, iMac, or display.
5. Enables use of USB-C cables or USB to Lightning charge cables.

23.5.4 Center Stage

Center Stage is a video effect available on Apple TV and in the Mac Control Center. Enabling Center Stage on Apple TV, or selecting it in the Control Center Video Effects causes the video to follow people's faces as they move within the Continuity Camera field of view. The video will zoom (in and out) and pan (left to right, right to left, up and down), to keep people's faces in the video frame.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

23.5.4.1 Center Stage on Apple TV

Perform mount testing using the FaceTime app on Apple TV to ensure the mount is not visible in the field of view:

1. Observe the Continuity Camera video from different positions using Center Stage face tracking, from the most extreme visible positions (left, right, top, bottom, and all four corners).
2. Verify there are no visual anomalies caused by the mount in any position.

23.5.4.2 Center Stage on Mac

Perform mount testing using the Photo Booth app on the Mac, with and without Center Stage enabled, to ensure the mount is not visible in the field of view:

1. Open the Photo Booth app on the Mac:
   a. Use the Camera menu to select Continuity Camera.
   b. Use the still photo mode.
2. Use the Mac Control Center menu to select Video Effects, and enable Center Stage.
3. Capture photos from different positions using Center Stage face tracking, in portrait and landscape orientation from the most extreme visible positions (left, right, top, bottom, and all four corners), waiting 5 seconds between each photo.
4. Use the Mac Control Center menu to select Video Effects, and disable Center Stage.
5. Capture photos in portrait and landscape orientation, waiting 5 seconds between each photo.
6. Using the Photo Booth film strip feature, verify all photos taken during the test:
   a. Are saved to the computer.
   b. Are clearly displayed when viewed.
   c. Have no visual anomalies caused by the mount in either portrait and landscape orientation.

23.5.5 Desk View

Desk View is a video effect available in the Mac Control Center. Selecting Video Effects and enabling Desk View causes a confirmation dialog box to appear, then a separate Desk View window opens. The tilt angle of the mount and its position determines the Desk View field of view. Adjust the tilt angle as necessary to display the desktop subject matter. Remote viewers will see the subject matter from the presenters perspective. Closing the Desk View window disables Desk View.

1. Ensure the device is logged into the same Apple Account used on the Mac.
2. Place the device in the mount and on the MacBook, iMac, display, tripod or free-standing support.
3. Perform mount testing using the FaceTime app with the Desk View video effect enabled.
   a. Open the FaceTime app on the Mac, and use the Video menu to select the Continuity Camera.
   b. Use the Mac Control Center menu to select Video Effects, and enable Desk View.
   c. Verify the Desk View window is displayed.
4. In both landscape and portrait orientation:
   a. Adjust the tilt angle of the mount to display the desktop subject matter in the Desk View window.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

b. Verify the desktop subject matter is visible in the Desk View window, and clearly displayed.
c. Verify there are no visible anomalies caused by the mount in the Desk View window.
d. Verify the user's face is still visible in FaceTime while Desk View is showing the desktop subject matter.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Features

24. Accessory Power (USB-C)

Accessory power enables accessories to draw a limited amount of power from a device, thereby avoiding the need to integrate a battery or connect to an external power source. This eliminates the need for users to monitor and charge the accessory and enables the accessory to function as long as the device has power. Accessories designed to temporarily connect to the device are good candidates for using accessory power.

Accessories drawing power from the device shall comply with *USB Type-C Cable and Connector Specification –Release 2.3*. Accessories should also support USB Power Delivery (PD) (page 240).

Accessories benefitting from accessory power include:

- Headsets (page 97).
- Adapters (page 91).
- Keyboards (page 101).
- External Storage (page 127).

24.1 Available Current

The following table lists the current available to an accessory.

Table 24-1 Available current

Device	Default	USB Type-C Current (page 241)	USB Power Delivery (PD) (page 240)
iPhone 17 Pro Max	900 mA	900 mA	900 mA (4.5 W)
iPhone 17 Pro	900 mA	900 mA	900 mA (4.5 W)
iPhone 17	500 mA	500 mA	900 mA (4.5 W)
iPhone Air	500 mA	500 mA	900 mA (4.5 W)
iPhone 16e	500 mA	500 mA	900 mA (4.5 W)
iPhone 16 Pro Max	900 mA	900 mA	900 mA (4.5 W)
iPhone 16 Pro	900 mA	900 mA	900 mA (4.5 W)
iPhone 16 Plus	500 mA	500 mA	900 mA (4.5 W)
iPhone 16	500 mA	500 mA	900 mA (4.5 W)
iPhone 15 Pro Max	900 mA	900 mA	900 mA (4.5 W)

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Device	Default	USB Type-C Current (page 241)	USB Power Delivery (PD) (page 240)
iPhone 15 Pro	900 mA	900 mA	900 mA (4.5 W)
iPhone 15 Plus	500 mA	500 mA	900 mA (4.5 W)
iPhone 15	500 mA	500 mA	900 mA (4.5 W)
iPad Pro 13-inch (M5)	900 mA	3.0 A	3.0 A (15 W)
iPad Pro 11-inch (M5)	900 mA	3.0 A	3.0 A (15 W)
iPad Air 13-inch (M3)	900 mA	1.5 A	1.5 A (7.5 W)
iPad Air 11-inch (M3)	900 mA	1.5 A	1.5 A (7.5 W)
iPad (A16)	900 mA	1.5 A	1.5 A (7.5 W)
iPad mini (A17 Pro)	900 mA	1.5 A	1.5 A (7.5 W)
iPad Pro 13-inch (M4)	900 mA	3.0 A	3.0 A (15 W)
iPad Pro 11-inch (M4)	900 mA	3.0 A	3.0 A (15 W)
iPad Air 13-inch (M2)	900 mA	1.5 A	1.5 A (7.5 W)
iPad Air 11-inch (M2)	900 mA	1.5 A	1.5 A (7.5 W)
iPad Pro 12.9-inch (6th generation)	900 mA	3.0 A	3.0 A (15 W)
iPad Pro 12.9-inch (5th generation)	900 mA	3.0 A	3.0 A (15 W)
iPad Pro 12.9-inch (4th generation)	900 mA	1.5 A	1.5 A (7.5 W)
iPad Pro 12.9-inch (3rd generation)	900 mA	1.5 A	1.5 A (7.5 W)
iPad Pro 11-inch (4th generation)	900 mA	3.0 A	3.0 A (15 W)
iPad Pro 11-inch (3rd generation)	900 mA	3.0 A	3.0 A (15 W)
iPad Pro 11-inch (2nd generation)	900 mA	1.5 A	1.5 A (7.5 W)
iPad Pro 11-inch (1st generation)	900 mA	1.5 A	1.5 A (7.5 W)
iPad Air (5th generation)	900 mA	1.5 A	1.5 A (7.5 W)
iPad Air (4th generation)	900 mA	1.5 A	1.5 A (7.5 W)
iPad mini (6th generation)	900 mA	1.5 A	1.5 A (7.5 W)
iPad (10th generation)	500 mA	1.5 A	1.5 A (7.5 W)

24.2 VCONN

USB 2.0 accessories capable of being powered from VCONN alone shall also be capable of being powered from VBUS.

24.3 Fast Role Swap (FRS)

iPads with a USB-C connector support USB Power Delivery (PD) (page 240) Fast Role Swap (FRS).

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

24.4 Verification

24.4.1 Maximum Accessory Power

This test procedure applies to accessories drawing power from the device. The accessory needs to be exercised to its full capability.

The example accessory in this test procedure is an external USB 3 drive claiming to draw up to 900 mA from the USB 3 host. The accessory is exercised by reading and writing a large file. Adapt this procedure as needed for different accessory types.

24.4.1.1 Equipment

The following equipment is necessary:

- External USB drive in APFS format (the example accessory).
- Mac with USB-C.
- USB-IF certified USB-C to USB-C Full-Featured cable.
- USB-C breakout board or USB-IF approved test fixture, such as:
  - FS-HUCP available at https://fixturesolution.com/product/usb2-0-type-c-signal-quality-test-fixture/.
  - FS-HUCR available at https://fixturesolution.com/product/usb-type-c-high-speed-signal-quality-test-fixture/ .
- Oscilloscope with a current probe.

24.4.1.2 Setup

1. Using the current probe attach the oscilloscope to the current loop circuit of the accessory, or the USB-C breakout board.
2. Verify the oscilloscope configuration settings match the following:
   a. Acquisition: >5 M samples/s.
   b. Current Channel: 200 mA/div.
   c. Horizontal Channel: 100 µs/div.
   d. Voltage Channel: 1 V/div, bandwidth limited.
   e. Infinite persistence (reset before each test case).
   f. Adjust offset down, to be able see 7 divisions.
   g. Adjust offset towards the left, to maximize the window.
   h. Trigger: Current Channel, Positive Threshold, 900 mA, Normal Mode.
3. Connect the Mac to the external USB drive using the USB-C cable.
4. Launch Terminal on the Mac, and enter the following command:
   - `dd if=/dev/random of=~/Desktop/testfile.dat count=1024 bs=78643200`
5. The new file `~/Desktop/testfile.dat` is the file to use for testing.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

24.4.1.3 Procedure

24.4.1.3.1 Enumeration

1. Verify the external USB drive fully enumerates in the Mac System Report:
   a. Select Apple Menu > 'About this Mac'.
   b. Select 'More Info...'.
   c. Select 'System Report...'.
   d. Select USB from the sidebar.
2. Verify the accessory is displayed in the USB Device Tree.
3. Verify the speed displayed is one of the following:
   a. Up to 5 Gb/s.
   b. Up to 10 Gb/s.

24.4.1.3.2 Idle

1. Record the maximum current while idle.
2. Verify the maximum current does not exceed 900 mA.

24.4.1.3.3 Write to USB Drive

1. Use Finder to copy the `testfile.dat` from the Mac to the USB drive.
2. Record the maximum current.
3. Verify the maximum current does not exceed 900 mA.

24.4.1.3.4 Read from USB Drive

1. Use Finder to copy the `testfile.dat` from the USB drive to the Mac.
2. Record the maximum current.
3. Verify the maximum current does not exceed 900 mA.

24.4.2 VCONN

This test procedure applies to USB 2.0 accessories drawing power from the device.

24.4.2.1 Equipment

The following equipment is necessary:

- iPhone Air

24.4.2.2 Procedure

1. Connect the device to the accessory.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

2. Verify the accessory works as expected.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

25. Accessory Power (Lightning)

Accessory power enables accessories to draw a limited amount of power from a device, thereby avoiding the need to integrate a battery or connect to an external power source. This eliminates the need for users to monitor and charge the accessory and enables the accessory to function as long as the device has power. Accessories designed to temporarily connect to the device are good candidates for using accessory power.

See the Accessory Interface Specification (page 27) for more information.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

26. App Discovery

The App Discovery feature enables accessories to retrieve a list of installed apps on the device capable of communicating with the accessory. See App Launch (page 169) to use the list.

See the Accessory Interface Specification (page 27) for more information.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

27. App Launch

Accessories supporting the App Launch feature can request a device launch an app on its behalf.

Figure 27-1 App Launch alert



See the Accessory Interface Specification (page 27) for more information.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

28. App Match

The App Match feature enables accessories supporting an External Accessory Protocol to match with compatible apps on the App Store.

When connected for the first time, the device asks the user if they would like to visit the App Store and view compatible apps. Subsequently, this action may be repeated using Settings > General > About > '[Accessory name]' > 'Find App for Accessory'.

Figure 28-1 App Match alert



See the Accessory Interface Specification (page 27) for more information.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

29. Bluetooth HFP Siri and Battery Reporting

Apple-specific Bluetooth commands extend accessory capabilities beyond those supported by standard Bluetooth profiles. To enable Apple-specific features, the accessory shall support HFP Command AT+XAPL (page 171), which provides accurate information about the accessory's supported features. The device will use the information sent by this command to enable and disable custom commands.

The accessory shall send the following AT+XAPL command after making a successful HFP Service Level Connection (SLC) to the device. The accessory should send an AT+XAPL command first, before sending any additional Apple-specific commands. See Siri (page 217) and Bluetooth Headset Battery Level Indication (page 172).

29.1 HFP Command AT+XAPL

Description: Enables custom AT commands from an accessory.

Initiator: Accessory

Format: AT+XAPL=*vendorID*-*productID*-*version*,*features*

Parameters:

- *vendorID*: A string representation of the hex value of the vendor ID from the manufacturer, without the `0x` prefix.
- *productID*: A string representation of the hex value of the product ID from the manufacturer, without the `0x` prefix.
- *version*: The software version.
- *features*: A base-10 representation of a bit field. Available features are:
  - Bit 0 = reserved
  - Bit 1 = The accessory supports battery reporting (reserved only for battery operated accessories).
  - Bit 2 = The accessory is docked or powered (reserved only for battery operated accessories).
  - Bit 3 = The accessory supports Siri status reporting.
  - Bit 4 = the accessory supports noise reduction (NR) status reporting.
  - All other values are reserved.

Example: AT+XAPL=ABCD-1234-0100,10 (Supports battery reporting and Siri status)

Response: +XAPL=iPhone,*features*

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

30. Bluetooth Headset Battery Level Indication

Bluetooth headsets may display a battery level to the user as an indicator icon in the device status bar. This feature is supported on all devices supporting the Hands-Free Profile, including iPhone, iPod touch, and iPad.

Headset battery indication is implemented by two Apple-specific Bluetooth HFP AT commands, HFP Command AT+XAPL (page 171) and HFP Command AT+IPHONEACCEV (page 172)

30.1 HFP Command AT+IPHONEACCEV

Description: Reports a headset state change.

Initiator: Accessory

Format: `AT+IPHONEACCEV=`*Number of key/value pairs*`,`*key1*`,`*val1*`,`*key2*`,`*val2*`,...`

Parameters:

- *Number of key/value pairs*: The number of parameters coming next.
- *key*: the type of change being reported:
  - 1 = Battery Level
  - 2 = Dock State
- *val*: the value of the change:
  - Battery Level: string value between '0' and '9'
  - Dock State: 0 = undocked, 1 = docked

Example: `AT+IPHONEACCEV=1,1,3`

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

31. Bluetooth Low Energy Battery Service

Note:
This content is a Developer Preview (page 24).

31.1 Overview

Accessories may communicate battery status using the Battery Level (`0x2A19`) and Battery Level Status (`0x2BED`) characteristics defined in the *Bluetooth Battery Service Specification – Version 1.1*.

If the Battery Level Status characteristic implements the optional Battery Level field, the accessory shall send the same battery value as the Battery Level characteristic.

Accessories shall only notify battery level change with Battery Level characteristic, and Power State change with Battery Level Status characteristic.

31.2 All Accessories

A Characteristic Presentation Format descriptor is only required if there are multiple instances of Battery Service, this descriptor may be excluded for an accessory with a single instance of Battery Service.

The following descriptors are supported:

- Main (`0x0106`)
- Left (`0x010D`)
- Right (`0x010E`)

Note:
The Main descriptor is interpreted as a "Case" when both Left and Right descriptors are present. This applies only to headset accessories.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

31.2.1 Hands Free Profile (HFP) Accessories

Accessories supporting the *Bluetooth Battery Service Specification – Version 1.1* should not use the *Battery Level Indicator* defined in the *Bluetooth Hands-Free Profile Specification – Version 1.8*. The device will ignore the *Battery Level Indicator* value in favor of the Bluetooth Low Energy Battery Service.

The device will read the Bluetooth Low Energy Battery Service value via GATT over Classic to avoid multiple ACL (Asynchronous Connection-oriented logical) transport links.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

32. Device Power (USB-C)

Accessories may provide power to devices using USB-C.

Apple recommends providing power to the device whenever possible for the best user experience.

Accessories providing power to a device shall:

- Connect to the device either through an integrated USB-C Plug (page 310) or a USB-C cable.
- Use USB Type-C Current (page 241) to identify their power capability and should use USB Power Delivery (PD) (page 240) to provide higher power, see https://support.apple.com/en-us/102574.
- Provide power at all times unless a direct user action is taken turning the accessory 'off'. Failure to provide power at all times may result in the accessory being unable to charge a device whose battery level is too low to boot.

Accessories may use the iAP2 (page 246) protocol in conjunction with USB Type-C Current (page 241) to allow for more granular control of the available current after the initial connection. Accessories shall not use iAP2 (page 246) to adjust available current in conjunction with USB Power Delivery (PD) (page 240).

Accessories providing power from a USB-C receptacle, see Providing Power (page 314).

32.1 External Power Source

Accessories drawing power from external power sources and providing all or a portion of their power to the device shall:

- Identify the power source's capability and report accordingly to the device.
- Not manipulate a device into drawing more power from the external power source than the device would normally draw when directly connected to the external power source.
- Derate the available power by the amount of power consumed by the accessory, if applicable.

Accessories drawing power from external power sources may inform the device when power is not available or only available at a reduced level (for example, from an internal battery) or when the user unplugs the accessory from the external power source (for example, an AC power adapter or AC "mains" power outlet). Power to the device shall be restored and the updated power providing capability change shall be communicated to the device when the user re-connects the external power source.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

See AC Power Adapters (page 93), Providing Power (page 314), and User Supplied Cables and AC Power Adapters (page 29) for additional requirements specific to external USB power supplies/cables.

32.2 Power State Changes

Accessories shall not change the amount of power provided to a device unless:

- Direct user action is taken to turn the accessory on or off.
- External power source (for example, mains electricity or battery) is connected to or disconnected from the accessory.
- Accessory's internal power source (for example, a battery) is depleted or loaded to the point where it is no longer capable of supplying its declared power providing capability or is now capable of supplying more power than previously declared.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

33. Device Power (Lightning)

Accessories may provide power to devices using Lightning.

Apple recommends providing power to the device whenever possible for the best user experience.

Accessories providing power to a device shall connect to the device either through an integrated Lightning connector or a USB to Lightning cable. To incorporate an integrated Lightning connector, the accessory developer shall be a member of the Apple MFi Program (page 27).

Accessories providing power to a device shall either:

- Provide direct power, see Direct Power Source (page 177).
- Manage power from external sources, see External Power Source (page 177).

Accessories without the potential for data communication with the device shall provide direct power to the device, see Direct Power Source (page 177).

33.1 Direct Power Source

Accessories providing power directly shall provide power at all times unless disabled by a direct user action. Failure to provide power at all times may result in the accessory being unable to charge a device whose battery level is too low to boot.

Accessory power source testing shall be performed with programmable loads, not devices. Device power draw varies with environmental factors.

33.2 External Power Source

Accessories drawing power from external power sources and providing all or a portion of their power to the device:

- Shall identify the power source's capability and report accordingly to the device.
- Shall not manipulate a device into drawing more power from the external power source than the device would normally draw when directly connected to the external power source.
- Shall not manipulate a device into drawing less than the minimum power required by the accessory compatibility claims if it is available from the external source, see Providing Power using USB Connectors (page 178).

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Accessories drawing power from external power sources may inform the device when power is not available or only available at a reduced level (for example, from an internal battery) or when the user unplugs the accessory from the external power source (for example, an AC power adapter or AC "mains" power outlet). Power to the device shall be restored and the updated power providing capability change shall be communicated to the device when the user re-connects the external power source.

See AC Power Adapters (page 93), Electrical (page 309), and User Supplied Cables and AC Power Adapters (page 29) for additional requirements specific to external USB power supplies/cables.

33.3 Declaring Capability

If the accessory provides power using a:

- USB-A receptacle, it shall use one of the following to declare its power providing capability:
  - USB Power Capability Vendor Request (page 236).
  - USB D+/D- Resistor Networks (page 237).
- USB-C receptacle, then:
  - It shall use one of the following to declare its power providing capability:
    - USB Type-C Current (page 241).
    - USB Power Delivery (PD) (page 240).
  - If the accessory does not have the potential for data communication with the device, it shall also support the *USB Battery Charging Specification –Release 1.2*.

33.4 Providing Power using USB Connectors

Accessories providing power from:

- USB-C receptacle, see USB-C Receptacle (page 313).
- USB-A receptacle, see USB-A Receptacle (page 309).

33.5 Labeling Multiple Connectors

If the accessory has multiple connectors with different device compatibilities, iPad-compatible connectors shall be labeled with the text 'iPad' unless it is physically impossible to connect an iPad to iPhone/iPod compatible connectors.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

33.6 Fast Charge for iPhone (20 W)

Accessories advertising "fast charge" for iPhone (https://support.apple.com/en-us/102574) shall:

- Support USB Power Delivery (PD) (page 240).
- Supply at least 20 W (2.22 A at 9 V) using USB PD.
- Claim compatibility with at least one of the following iPhone models:
  - iPhone 14 Pro Max
  - iPhone 14 Pro
  - iPhone 14 Plus
  - iPhone 14
  - iPhone SE (3rd generation)
  - iPhone 13 Pro Max
  - iPhone 13 Pro
  - iPhone 13
  - iPhone 13 mini
  - iPhone 12 Pro Max
  - iPhone 12 Pro
  - iPhone 12
  - iPhone 12 mini
  - iPhone SE (2nd generation)
  - iPhone 11 Pro Max
  - iPhone 11 Pro
  - iPhone 11
  - iPhone XS Max
  - iPhone XS
  - iPhone XR
  - iPhone X
  - iPhone 8 Plus
  - iPhone 8

Accessories such as charging cables should be capable of supporting up to 60 W (3 A at 20 V) to provide compatibility with a variety of sources and devices.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

33.7 Overcurrent and Short Circuit Protection

Figure 33-1 Overcurrent and short circuit protection



Power-providing accessories shall implement overcurrent and short circuit protection for each region in Figure 33-1 (page 180) according to Table 33-1 (page 180), Table 33-2 (page 180), and Table 33-3 (page 181).

Table 33-1 Overcurrent / short circuit protection current thresholds

Threshold	Definition
I_a	Nominal accessory output current (for example, 1000 mA, 2100 mA, 2400 mA, 3000 mA).
I_b	I_a + 60%.
I_c	Lowest device current draw causing accessory output voltage (measured at Lightning Device Power) to drop below 2 V.

Table 33-2 Overcurrent / short circuit protection time thresholds

Threshold	Definition
T_0	Start of any device current draw transient.
T_1	Accessory overcurrent/short circuit deglitch/debounce time, shall ≥ T_0 + 1 ms.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Table 33-3 Overcurrent / short circuit protection behaviors

Region	Name	Accessory Behavior
A	Normal Operation	Accessory shall not limit or shutdown output current.
B	Overcurrent Transient	Accessory shall not shutdown output current. Accessory may limit output current to I_a or higher.
C	Overcurrent	Accessory shall shutdown output current.
D	Potential Overcurrent	Accessory may shutdown output current.
E	Potential Short Circuit	If Lightning Device Power voltage drops below 2 V, the accessory may trigger short circuit protection. Accessories shall not trigger short circuit protection on device current draw.

33.8 Overcurrent and Short Circuit Protection Resets

Accessory overcurrent and short circuit protection shall reset without mechanical intervention.

33.9 Power State Changes

Accessories shall not change the amount of power provided to a device unless:

- Direct user action is taken to turn the accessory on or off.
- External power source (for example, mains electricity or battery) is connected to or disconnected from the accessory.
- Accessory's internal power source (for example, a battery) is depleted or loaded to the point where it is no longer capable of supplying its declared power providing capability or is now capable of supplying more power than previously declared.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

34. Device Power (Inductive)

Accessories may provide power to devices using inductive power transmitters, specifically:

- Qi Wireless Power (page 182)
- MagSafe (page 183)

34.1 Qi Wireless Power

Devices supporting Qi wireless power:

- iPhone 17 Pro Max
- iPhone 17 Pro
- iPhone 17
- iPhone Air
- iPhone 16e
- iPhone 16 Pro Max
- iPhone 16 Pro
- iPhone 16 Plus
- iPhone 16
- iPhone 15 Pro Max
- iPhone 15 Pro
- iPhone 15 Plus
- iPhone 15
- iPhone 14 Pro Max
- iPhone 14 Pro
- iPhone 14 Plus
- iPhone 14
- iPhone SE (3rd generation)
- iPhone 13 Pro Max
- iPhone 13 Pro
- iPhone 13
- iPhone 13 mini
- iPhone 12 Pro Max
- iPhone 12 Pro
- iPhone 12
- iPhone 12 mini

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- iPhone SE (2nd generation)
- iPhone 11 Pro Max
- iPhone 11 Pro
- iPhone 11
- iPhone XS Max
- iPhone XS
- iPhone XR
- iPhone X
- iPhone 8 Plus
- iPhone 8
- Wireless Charging Case (USB-C) for AirPods 4
- MagSafe Charging Case (USB-C) for AirPods Pro (2nd generation)
- MagSafe Charging Case for AirPods Pro (2nd generation)
- MagSafe Charging Case for AirPods (3rd generation)
- Wireless Charging Case for AirPods

Accessories incorporating a Qi transmitter shall use an embedded Qi Certified subsystem or shall be Qi Certified according to *The Qi Wireless Power Transfer System, Power Class 0 Specification – Version 2.0 or later*, see https://www.wirelesspowerconsortium.com. Accessories should support version 2.2 or later.

34.2 MagSafe

Devices supporting MagSafe:

- iPhone 17 Pro Max
- iPhone 17 Pro
- iPhone 17
- iPhone Air
- iPhone 16 Pro Max
- iPhone 16 Pro
- iPhone 16 Plus
- iPhone 16
- iPhone 15 Pro Max
- iPhone 15 Pro
- iPhone 15 Plus
- iPhone 15
- iPhone 14 Pro Max
- iPhone 14 Pro
- iPhone 14 Plus

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- iPhone 14
- iPhone 13 Pro Max
- iPhone 13 Pro
- iPhone 13
- iPhone 13 mini
- iPhone 12 Pro Max
- iPhone 12 Pro
- iPhone 12
- iPhone 12 mini
- MagSafe Charging Case (USB-C) for AirPods Pro (2nd generation)
- MagSafe Charging Case for AirPods Pro (2nd generation)
- MagSafe Charging Case for AirPods (3rd generation)

34.3 Electromagnetic Compatibility (EMC)

Accessories providing inductive device power should be designed for electromagnetic compatibility.

Apple recommends shielding the magnetic field from the charging coil and maintaining a low impedance shield termination for cables to comply with regulatory EMC requirements for the completed product. Implementation, final compliance testing, report preparation, and labeling are the responsibilities of the company marketing and producing the product.

Cable termination is critical for reduced emissions. Cable termination and connectors should be kept away from the charging coil and cables should be routed away from the charging surface.

If emissions are present, adding clamp-on ferrites/absorbers to the cable can help reduce emissions. Selected ferrite/absorber materials should be rated for the failing frequencies.

Depending on the accessory's supported use cases, testing should be performed with the following power supplies:

- Apple USB-C Power Adapters:
  - Apple 140W USB-C Power Adapter
  - Apple 96W USB-C Power Adapter
  - Apple 70W USB-C Power Adapter
  - Apple 67W USB-C Power Adapter
  - Apple 30W USB-C Power Adapter
  - Apple 20W USB-C Power Adapter
  - Apple 35W Dual USB-C Port Compact Power Adapter
  - Apple 35W Dual USB-C Port Power Adapter
- Apple USB-A Power Adapters:
  - Apple 12W USB Power Adapter

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

  - Apple 5W USB Power Adapter
    - Model A1385 (US)
    - Model A1400 (Int.)
    - Model A1552 (UK)
    - Model A1443 (China)
    - Model A1444 (Australia)
    - Model A1486 (Brazil)
    - Model A1487 (Korea)
    - Model A1501 (Argentina)
- Apple Mac computers:
  - Apple MacBook Pro
  - Apple MacBook Air

If power sources are used differing from those listed above, emission testing should be performed while the power sources are on.

In addition to the use cases above, charging devices should be tested in idle mode for emissions.

Emissions tests should be conducted in accordance with standards referenced in the following:

- FCC CFR 47, Part 15
- ICES-003, Issue 5, CAN/CSA-CEI/IEC CISPR 22-10
- CISPR 22: 2008
- EN 55022: 2010
- AS/NZS CISPR 22:2009, TCVN 7189:2009
- VCCI V-3/2013.04
- GB 9254-2008, GB 17625.1-2012, GB 17625.2-2007, CNS 13438-2006
- CISPR 24: 2010
- EN 55024: 2010

Once the highest emitting combination is identified, complete testing should be performed on the configuration. Some regulatory domains may require EMC certification.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

35. Ethernet over USB

Accessories may support Ethernet over USB using the Network Control Model (NCM) protocol to enable a device to access a wired network.

Accessories shall comply with the *Network Control Model Devices Specification –Revision 1.0*, see https://www.usb.org/document-library/network-control-model-devices-specification-v10-and-errata-and-adopters-agreement.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

36. External Accessory Protocol

The External Accessory (EA) framework provides accessories the means to communicate with one or more apps using EA sessions, providing a read/write bytestream interface. Accessory developers specify a custom protocol between the application and the accessory. The design and maintenance of communication protocols between accessories and applications are entirely the responsibility of the accessory and app developers. External Accessory framework documentation can be found at https://developer.apple.com/documentation/externalaccessory.

See the Accessory Interface Specification (page 27) for more information.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

37. HID Headset Remote

Devices may accept user input from headsets to control audio volume and media playback.

37.1 Requirements

Accessories implementing HID headset remote controls shall:

- Connect to the device using one of the following:
  - USB-C Plug (page 310).
  - Bluetooth (page 258).

HID headset remotes shall support the Human Interface Device (HID) (page 247) protocol.

The HID report descriptor for a headset remote shall declare support for the HID Consumer and/or Telephony pages and only send usages from Table 37-1 (page 188) and Table 37-2 (page 188).

Table 37-1 HID Consumer Page (0x0C) controls for use by headset remotes

Usage ID	Usage Name	Apple Function
0x00B5	Scan Next Track	Transport Right
0x00B6	Scan Previous Track	Transport Left
0x00B9	Random Play	Shuffle
0x00BC	Repeat	Repeat
0x00E2	Mute	Mute
0x00E9	Volume Increment	Volume Up
0x00EA	Volume Decrement	Volume Down
0x025B	Promote	Play More Like This
0x025C	Demote	Play Less Like This

Table 37-2 HID Telephony Page (0x0B) controls for use by headset remotes

Usage ID	Usage Name	Apple Function
0x0021	Flash	Center

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

If a user presses and holds the accessory control surface corresponding to the 'Transport Right' or 'Transport Left' function, devices may scrub forwards or backwards within the current playing media item. Accessories shall not present a separate 'Fast-Forward' or 'Reverse' control surface to the user for the same feature.

37.2 Examples

37.2.1 Headset Remote Example HID Report Descriptor (Telephony)

The following sample HID descriptor demonstrates how to implement telephony and volume controls.

```
USAGE_PAGE (Consumer Devices) 05 0C
USAGE (Consumer Control)      09 01
COLLECTION (Application)      A1 01
  LOGICAL_MINIMUM (0)         15 00
  LOGICAL_MAXIMUM (1)         25 01
  REPORT_SIZE (1)             75 01
  REPORT_COUNT (2)            95 02
  USAGE (Volume Increment)    09 E9    // Volume Up
  USAGE (Volume Decrement)    09 EA    // Volume Down
  INPUT (Data,Var,Abs)        81 02
  USAGE_PAGE (Telephony)      05 0B
  REPORT_COUNT (1)            95 01
  USAGE (Flash)               09 21    // Center
  INPUT (Data,Var,Abs)        81 02
  REPORT_SIZE (5)             75 05
  REPORT_COUNT (1)            95 01
  INPUT (Cnst, Var, Abs)      81 03
END_COLLECTION                C0
```

Each report is one byte, and each bit corresponds to one of the functions. For example, the following sample reports communicate the referenced button having been pressed:

- Volume Up is `0x01`
- Volume Down is `0x02`
- Center is `0x04`

37.2.2 Headset Remote Example HID Report Descriptor (Media Playback)

The following sample HID descriptor demonstrates how to implement media playback controls.

```
USAGE PAGE (Consumer Devices) 05 0C
USAGE (Consumer Control)      09 01
COLLECTION (Application)      A1 01
  LOGICAL MINIMUM (0)         15 00
```

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

```
  LOGICAL MAXIMUM (1)         25 01
  REPORT SIZE (1)             75 01
  REPORT COUNT (7)            95 07
  USAGE (Scan Next Track)     09 B5    // Transport Right
  USAGE (Scan Previous Track) 09 B6    // Transport Left
  USAGE (Mute)                09 E2    // Mute
  USAGE (Shuffle)             09 B9    // Shuffle
  USAGE (Repeat)              09 BC    // Repeat
  USAGE (Promote)             0A 5B 02 // Play More Like This
  USAGE (Demote)              0A 5C 02 // Play Less Like This
  INPUT (Data,Var,Abs)        81 02
END COLLECTION                C0
```

Each report is one byte, and each bit corresponds to one of the functions. For example, the following sample reports communicate the referenced button having been pressed:

- Transport Right is `0x01`
- Transport Left is `0x02`
- Mute is `0x04`

37.2.3 Headset Remote Example HID Report Descriptor (Telephony and Media Playback)

The following sample HID descriptor demonstrates how to implement all possible media playback controls along with the same controls found on the Apple headset remote.

```
USAGE_PAGE (Consumer Devices) 05 0C
USAGE (Consumer Control)      09 01
COLLECTION (Application)      A1 01
  LOGICAL_MINIMUM (0)         15 00
  LOGICAL_MAXIMUM (1)         25 01
  REPORT_SIZE (1)             75 01
  REPORT_COUNT (9)            95 09
  USAGE (Scan Next Track)     09 B5    // Transport Right
  USAGE (Scan Previous Track) 09 B6    // Transport Left
  USAGE (Mute)                09 E2    // Mute
  USAGE (Shuffle)             09 B9    // Shuffle
  USAGE (Repeat)              09 BC    // Repeat
  USAGE (Promote)             0A 5B 02 // Play More Like This
  USAGE (Demote)              0A 5C 02 // Play Less Like This
  USAGE (Volume Increment)    09 E9    // Volume Up
  USAGE (Volume Decrement)    09 EA    // Volume Down
  INPUT (Data,Var,Abs)        81 02
  USAGE_PAGE (Telephony)      05 0B
  REPORT_COUNT (1)            95 01
  USAGE (Flash)               09 21    // Center
  INPUT (Data,Var,Abs)        81 02
  REPORT_SIZE (5)             75 05
  REPORT_COUNT (1)            95 01
  INPUT (Cnst, Var, Abs)      81 03
```

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

```
END COLLECTION                C0
```

Each report is two bytes. The bits are assigned top-to-bottom (from 'Transport Right' to 'Center'). For example, the following sample reports communicate the referenced button having been pressed:

- Transport Right is `0x0100`
- Transport Left is `0x0200`
- Mute is `0x0400`
- Volume Up is `0x8000`
- Volume Down is `0x0001`
- Center is `0x0002`

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

38. Location Information

Location features enable accessories to provide Global Navigation Satellite System (GNSS) and sensor data (for example, speed) to devices in the form of National Marine Electronics Association (NMEA) sentences. Devices can use the additional information to augment built-in location services. For example, some external accessories provide more accurate or more frequent position updates. Additionally, devices can conserve power by using location information from a self-powered external accessory.

See the Accessory Interface Specification (page 27) for more information.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

39. MagSafe Attach

Devices supporting MagSafe Attach:

- iPhone 17 Pro Max
- iPhone 17 Pro
- iPhone 17
- iPhone Air
- iPhone 16 Pro Max
- iPhone 16 Pro
- iPhone 16 Plus
- iPhone 16
- iPhone 15 Pro Max
- iPhone 15 Pro
- iPhone 15 Plus
- iPhone 15
- iPhone 14 Pro Max
- iPhone 14 Pro
- iPhone 14 Plus
- iPhone 14
- iPhone 13 Pro Max
- iPhone 13 Pro
- iPhone 13
- iPhone 13 mini
- iPhone 12 Pro Max
- iPhone 12 Pro
- iPhone 12
- iPhone 12 mini

MagSafe Cases (page 36) shall:

- Claim compatibility with a MagSafe-capable device.
- Integrate a MagSafe Case Magnet Array (page 194).

Other MagSafe accessories shall:

- Claim compatibility with a MagSafe-capable device.
- Integrate a MagSafe Accessory Magnet Array (page 198).

Apple recommends the following magnet array vendors:

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- Baotou INST Magnetic New Materials Co., Ltd. (https://www.instmagnets.com)
- Ningbo Sanhuan Magsound Industry & Trade Co., Ltd. (https://www.magsound.com)
- Quadrant Solutions, Inc. (https://www.quadrant.us)

39.1 MagSafe Case Magnet Array

Figure 39-1 MagSafe case magnet array



39.1.1 Product Design

Cases integrating a MagSafe case magnet array shall:

- Enclose the device.
- Have a uniform thickness no greater than 2.1 mm; Apple recommends 2.0 mm.
- Firmly attach to the device without relying on the magnets.
- Not integrate magnets on the back of the case other than the MagSafe magnets.
- Comply with requirements for Cases (page 36).
- Work with:
  - Apple MagSafe Charger.
  - iPhone FineWoven Wallet with MagSafe.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

39.1.2 Mechanical

Magnets in the MagSafe case magnet array shall be positioned in the same plane.

The case and MagSafe case magnet array shall enable MagSafe accessories to magnetically self align within a 1.55 mm radial maximum.

39.1.2.1 Magnets

MagSafe case magnets shall be N45SH NdFeB with a 8 µm - 16 µm epoxy coating (or similar non-metallic coating) and shall meet the requirements in Table 39-1 (page 195). A reference design is provided for how to achieve the desired retention force for MagSafe accessories, see Figure 39-3 (page 197).

Table 39-1 Magnet properties

Property	Minimum	Maximum
Br	13.2 kGs	13.6 kGs
Hcb	12.75 kOe	
Hcj	20.50 kOe	
BHmax	43 MGOe	46 MGOe

Cases shall not exceed a surface gauss of 0.215 T on either the interior (contacting the device) or exterior (contacting MagSafe accessories) surface of the case.

39.1.2.2 Magnet Array

The magnets shall be positioned in the case following the dimensions and polarity shown in Figure 39-2 (page 196), Figure 39-3 (page 197) and Figure 39-4 (page 197).

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 39-2 MagSafe magnet array dimensions



Figure 39-3 MagSafe magnet ring dimensions and polarity



Figure 39-4 MagSafe orientation magnet dimensions and polarity



39.1.2.3 Magnetic Force

The force normal to the back of the case needed to dislodge a MagSafe accessory, such as the Apple MagSafe Charger, shall have a nominal target between 1000 gf and 1300 gf when the case is attached to the device.

39.1.3 Magnetic Interference

Cases with an integrated MagSafe magnet array shall not interfere with:

- Inductive charging.
- Magnetic stripe cards in an attached iPhone FineWoven Wallet with MagSafe.

39.2 MagSafe Accessory Magnet Array

Figure 39-5 MagSafe accessory magnet array options



The MagSafe accessory magnet array shall implement one of the following magnet array configurations:

- Magnet Ring (page 200): This configuration allows the accessory to attach in any rotational orientation.
- Extended Magnet Ring (page 202): This alternative configuration provides a higher attachment force, especially when used with iPhone Air.

An Orientation Magnet (page 204) may be included in either of the above array configurations to enforce a specific attachment orientation.

39.2.1 Product Design

Accessories integrating the MagSafe accessory magnet array shall not enclose the device.

39.2.2 Mechanical

The accessory shall not interfere with or cause Scratches and Damage (page 29) to the device.

To avoid interference with devices, accessories shall:

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- Not exceed 30 mm from the center of the magnet ring surface towards the top edge of the device for all supported device orientations. If the device can be attached in any orientation, the accessory shall not exceed 30 mm in radius around the center of the magnet ring surface.
- Maintain a clearance of 6 mm from the back of the device (mating surface) for any part of the accessory past the 30 mm keep-in constraint.
- Stay within the MagSafe Accessory Enclosure Geometry (page 207).

Figure 39-6 MagSafe accessory clearance



Magnets in the MagSafe accessory magnet array shall be positioned in the same plane.

The MagSafe accessory's Magnet Ring (page 200) or Extended Magnet Ring (page 202) shall magnetically self align to the device's magnet ring within a 1.55 mm radial maximum.

39.2.2.1 Magnets

MagSafe accessory magnets shall be N48H NdFeB with a 7 µm - 13 µm NiCuNi plating finish (or similar) and shall meet the requirements in Table 39-2 (page 200).

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Table 39-2 Magnet properties

Property	Minimum	Maximum
Br	13.7 kGs	14.1 kGs
Hcb	13.25 kOe	
Hcj	17 kOe	
BHmax	45 MGOe	48 MGOe

Flux density of the MagSafe accessory shall not exceed 0.215 T at the product surface.

39.2.2.2 Magnet Ring

The magnet ring shall be positioned in the accessory in compliance with the dimensions and polarity requirements in Figure 39-7 (page 201) and Figure 39-8 (page 202).

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 39-7 MagSafe magnet ring dimensions



Figure 39-8 MagSafe magnet ring dimensions and polarity



See DC Shield (page 206) for additional requirements of the DC shield specified in Figure 39-8 (page 202).

39.2.2.3 Extended Magnet Ring

The magnet ring shall be positioned in the accessory in compliance with the dimensions and polarity requirements in Figure 39-9 (page 203) and Figure 39-10 (page 203).

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 39-9 MagSafe extended magnet ring dimensions



Figure 39-10 MagSafe extended magnet ring dimensions and polarity



See DC Shield (page 206) for additional requirements of the DC shield specified in Figure 39-12 (page 206).

39.2.2.4 Orientation Magnet

If orientation magnets are included, the magnets shall be positioned according to Figure 39-11 (page 205) and Figure 39-12 (page 206).

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 39-11 MagSafe orientation magnet dimensions



Figure 39-12 MagSafe orientation magnet dimensions and polarity



See DC Shield (page 206) for additional requirements of the DC shield specified in Figure 39-12 (page 206).

39.2.2.5 Magnetic Force

The force normal to the back of the device needed to dislodge the MagSafe accessory shall meet the requirements in Table 39-3 (page 206).

Table 39-3 Magnetic force

Scenario	Minimum	Maximum
Accessory attached to device	650 gf	1510 gf

39.2.2.6 DC Shield

The DC shield shall be low carbon steel (1010, DT4 or similar), per ASTM848, with a 5 µm - 10 µm Ni plating finish or similar.

The DC shield shall have a saturation flux density (B_{sat}) of at least 2.0 T.

Copyright © 2025 Apple Inc. All Rights Reserved.

39.3 MagSafe Accessory Enclosure Geometry

REV	ECO#	DESCRIPTION OF REVISION

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. SPLINE REPRESENTS MAX MATERIAL CONDITION FOR AN EXTERIOR PRODUCT SURFACE. MAGSAFE COMPATIBLE ACCESSORIES SHALL STAY WITHIN THE PROVIDED SPLINE.
2. FOR NON AXISYMMETRIC APPLICATIONS, SPLINE REPRESENTS MAX MATERIAL CONDITION WHEN VIEWED ALONG X AXIS
3. FOR AXISYMMETRIC APPLICATIONS, A REVOLUTION OF THE SPLINE AROUND THE Z AXIS THROUGH THE CENTER POINT OF THE MAGNET ARRAY REPRESENTS THE MAX MATERIAL CONDITION

[4] ANY CURVATURE DEVIATING BEYOND SPLINE TO EXIST BEYOND 5MM Z CLEARANCE FROM TOP OF PRODUCT



SIDE VIEW PROJECTION OF POSTIVE Y PRODUCT EDGE
(CUT IN X AT MAGNET ARRAY CENTER POINT)



DETAIL A
SCALE 50:1

METRIC	Apple Inc.
DRAFTER: APPLE — DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER: APPLE — DATE	
DIMENSIONS ARE IN MILLIMETERS TOLERANCES	TITLE: MAGSAFE COMPATIBLE ENCLOSURE GEOMETRY
DO NOT SCALE DRAWINGS	DRAWING NUMBER — REV. 01
THIRD ANGLE PROJECTION — SIZE D	SCALE NONE — SHT 1 OF 1

NX GENERATED

Copyright © 2025 Apple Inc. All Rights Reserved.

39.4 Verification

39.4.1 MagSafe Case Magnet Array

39.4.1.1 Case Thickness

39.4.1.1.1 Equipment

The following equipment is necessary:

- Digital thickness gauge, such as the Mitutoyo 547-520S.

39.4.1.1.2 Procedure

1. Using the digital thickness gauge, verify the thickness is less than or equal to 2.1 mm at:
   - Four points along the magnet ring.
   - Two points along the orientation magnet.

39.4.1.2 Accessory Clearance

39.4.1.2.1 Equipment

The following equipment is necessary:

- MagSafe-capable device.
- Apple MagSafe Battery Pack.

39.4.1.2.2 Procedure

1. Attach the case to the device.
2. Attach the Apple MagSafe Battery Pack to the back of the case.
3. Verify the case does not interfere with the Apple MagSafe Battery Pack and only the mating surface is in contact.

39.4.1.3 Magnetic Force

39.4.1.3.1 Equipment

The following equipment is necessary:

- MagSafe-capable device.
- Apple MagSafe Charger.
- Non-magnetic eyelet screw.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- Digital force gauge capable of capturing peak values, such as the Chatillon DFX II.
- Hook attachment for digital force gauge.
- Clamps to securely hold the device on a flat level surface.

39.4.1.3.2 Setup

Figure 39-13 Magnetic force test setup



1. Attach the case to the device.
2. Place the device on a flat level surface with the display facing down and clamp it firmly in place.
3. Glue the non-magnetic eyelet to the center of the back of the Apple MagSafe Charger so pulling on the eyelet exerts a force on the center of the charger.

39.4.1.3.3 Procedure

1. Repeat the following steps 5 times:
   a. Attach the Apple MagSafe Charger and eyelet assembly to the back of the case, allowing them to magnetically align.
   b. Connect the force gauge hook to the eyelet.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

c. Reset the force gauge's peak force value.
d. Pull the force gauge vertically until the Apple MagSafe Charger and eyelet assembly dislodge from the case.
e. Note the peak value from the force gauge.

2. Calculate the average of the 5 peak force measurements.
3. Verify the average force is within the range of 800 gf to 1100 gf when removing the mass of the Apple MagSafe Charger and eyelet assembly.

39.4.1.4 iPhone FineWoven Wallet with MagSafe Detection

39.4.1.4.1 Equipment

The following equipment is necessary:

- MagSafe-capable device.
- iPhone FineWoven Wallet with MagSafe.

39.4.1.4.2 Procedure

1. Attach the case to the device.
2. Attach the wallet to the back of the case.
3. Verify the device displays the wallet animation.

39.4.1.5 Magnetic Stripe Cards in iPhone FineWoven Wallet with MagSafe

39.4.1.5.1 Equipment

The following equipment is necessary:

- MagSafe-capable device.
- iPhone FineWoven Wallet with MagSafe.
- Low Coercivity Magnetic stripe (LoCo) cards, such as cards from the following vendors:
  - American Card Service.
  - Allsafe.
  - CI Solutions.
  - PSA.
- LoCo card reader/writer, such as:
  - Q-card Mag3x.
  - Magtek InSpec 9000.
  - Misiri X6BT.
  - Deftun MSR605X.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

39.4.1.5.2 Procedure

1. Attach the accessory to the device.
2. Repeat this procedure for three different brands of LoCo cards:
   a. Write to the LoCo card.
   b. Read from the LoCo card and verify it was written successfully.
   c. Insert the LoCo card into the wallet with the magnetic stripe facing the magnets.
   d. Place additional cards into the wallet to ensure a LoCo card is in contact with the magnetic side of the wallet.
   e. Attach the wallet to the accessory (attached to the device).
   f. Wait 10 seconds.
   g. Remove the wallet from the accessory.
   h. Remove the LoCo card from the wallet.
   i. Verify the LoCo card is readable and its contents have not changed.

39.4.2 MagSafe Accessory Magnet Array

39.4.2.1 Orientation Magnet

If the accessory includes an orientation magnet:

1. Use a straight edge to verify the device contact surfaces of the magnet ring and orientation magnet are coplanar (aligned in the same plane).
2. Attach a MagSafe-capable device to the accessory and align it with the orientation magnet. Verify there are no gaps between the:
   - MagSafe magnet ring and device.
   - MagSafe orientation magnet and device.

39.4.2.2 Magnetic Force

39.4.2.2.1 Equipment

The following equipment is necessary:

- MagSafe-capable device.
- Non-magnetic eyelet to attach to the device.
- Digital force gauge capable of capturing peak values, such as the Chatillon DFX II.
- Hook attachment for digital force gauge.
- Clamps, or a vice, to securely hold the accessory on a flat level surface.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

39.4.2.2.2 Setup

Figure 39-14 Magnetic force test setup



1. Clamp the accessory in place so the MagSafe surface is level.
2. Attach the non-magnetic eyelet to the MagSafe-capable device so pulling on the eyelet exerts a force on the center of the back of the device. A bracket, strong suction cup, or glue may be used.

39.4.2.2.3 Procedure

1. Repeat the following steps 5 times:
   a. Attach the device and eyelet assembly to the accessory, allowing them to magnetically align.
   b. Connect the force gauge hook to the eyelet.
   c. Reset the force gauge's peak force value.
   d. Pull the force gauge vertically until the device and eyelet assembly dislodge from the accessory.
   e. Note the peak value from the force gauge.
2. Calculate the average of the 5 peak force measurements.
3. Verify the average force is within the range of 650 gf to 900 gf when removing the mass of the device and eyelet assembly.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

40. Media Library Access

The Media Library feature allows accessories to download the metadata contents of a device's media libraries (not the media items themselves) and request playback of media items. The feature is divided into the following sub-features:

- Media Library Information informs the accessory about media libraries available on the device.
- Media Library Updates provide an accessory with an updated view of the contents of a particular media library.
- Media Library Playback allows the accessory to request playback of one or more items from a media library.

See the Accessory Interface Specification (page 27) for more information.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

41. Musical Instrument Digital Interface (MIDI)

Compatible USB and Bluetooth Low Energy MIDI accessories can interface directly with iOS 17.0, iPadOS 17.0, and macOS 14.0 Sonoma apps using the Core MIDI framework, see https://developer.apple.com/documentation/coremidi.

41.1 Requirements

Accessories supporting MIDI as a USB device shall implement a MIDI Streaming IN endpoint and shall support either:

- *USB Device Class Definition for MIDI Devices – Version 2.0*, see https://www.usb.org/document-library/usb-class-definition-midi-devices-v20.
- *USB Device Class Definition for MIDI Devices – Release 1.0*, see https://www.usb.org/document-library/usb-midi-devices-10.

Accessories supporting MIDI over Bluetooth Low Energy shall support:

- *MIDI Association MIDI over Bluetooth Low Energy (BLE-MIDI) – Version 1.0a*, see https://midi.org/midi-over-bluetooth-low-energy-ble-midi.

41.2 Verification

Developers should test accessory designs against macOS Tahoe 26.1 using the Audio MIDI Setup app and its MIDI Studio and Test MIDI Setup features. See the user guide at https://support.apple.com/guide/audio-midi-setup/welcome/mac.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

42. Now Playing Updates

The Now Playing feature enables an accessory to display information about the current "Now Playing" media source and media item on a device. Media sources include both the built-in Apple Music and Apple Video apps on devices and certain third-party iOS apps supporting the generation of Now Playing metadata, see *MPNowPlayingInfoCenter* in the iOS SDK documentation. Accessories shall be prepared for the Now Playing media source and media item to change at any time, whether the accessory requested the change or not.

See the Accessory Interface Specification (page 27) for more information.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

43. Out-of-Band Bluetooth Pairing

Accessories with the ability to connect to a device using Bluetooth and a wired transport should use the Out-of-Band Bluetooth Pairing feature to simplify Bluetooth connection setup.

For example, USB to Lightning charge cables or Lightning to USB accessory cables can be used to exchange Bluetooth pairing information upon initial connection. This may reduce or eliminate the need for instruction manuals to describe how to:

- Put the accessory into a discoverable and pairable mode.
- Initiate Bluetooth pairing on the device using the Settings app.
- Download the accessory's companion app and initiate pairing from the app.

See the Accessory Interface Specification (page 27) for more information.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

44. Siri

Siri enables a user to have rich interactions with a device by primarily using their voice.

Accessories supporting Siri over Bluetooth using HFP commands shall not use an icon resembling the Siri microphone icon.

To support Siri using other transports and protocols, the accessory developer shall be a member of the Apple MFi Program (page 27).

44.1 Enabling Custom Siri Commands

Accessories supporting Siri over Bluetooth using HFP commands shall support HFP Command AT+XAPL (page 171). The device will use the information sent by this command to enable and disable custom commands related to Siri.

To receive Siri status events, the accessory shall send the AT+XAPL command after making a successful HFP Service Level Connection (SLC) to the device. The accessory should send an AT+XAPL command first, before sending any of the additional Siri-specific commands described below.

44.2 Obtaining Siri Availability Information

After establishing an HFP profile connection, an accessory can determine if Siri is available and enabled on a device. It can also receive notifications of changes in Siri status. If Siri is disabled, Voice Control will be activated instead.

44.2.1 Obtaining Status Information at Connection

The accessory should send the following command after making a successful HFP profile (SLC) connection and sending an AT+XAPL command.

44.2.1.1 HFP Command AT+APLSIRI?

Description: An accessory sends this command to retrieve Siri status information.

Initiator: Accessory

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Format: `AT+APLSIRI?`

Response: `+APLSIRI:` *value*

Defined Values:
- 0 = Siri is not available on this platform.
- 1 = Siri is available and enabled.
- 2 = Siri is available but not enabled.

Example: `+APLSIRI:1` (Siri is available and enabled)

44.2.2 Receiving Siri Availability Updates from the Device

After initialization has been completed, the device will send the accessory the following notification if there is a change in Siri status. This notification will be provided only if the accessory has requested Siri status (by sending `AT+APLSIRI?`) at least once after connection and if the device has reported Siri is available and enabled.

44.2.2.1 HFP Command +APLSIRI

Description: Unsolicited event indicating a change in Siri status.

Initiator: Device

Format: `+APLSIRI:` *value*

Defined Values:
- 1 = Siri is available and enabled.
- 2 = Siri is available but not enabled.

Example: `+APLSIRI:2` (Siri is available but not enabled)

Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 44-1 Siri is Disabled/Enabled from the Device's Settings



44.3 Initiating a Siri Session

Once support for Siri is established on both the accessory and the device, a Siri session can be started from either one.

44.3.1 Initiating a Session from the Accessory

The accessory should only initiate a Siri session as a result of a direct user action.

The accessory shall use the voice recognition command AT+BVRA defined in the *Bluetooth Hands-Free Profile Specification – Version 1.6, Section 4.25* to initiate a Siri session.

The HFP profile shall be connected and SLC shall exist.

The accessory should use the following command sequence:

- The accessory sends an AT+BVRA=1 command to the device.
- The device sends an OK response.
- The device activates a Siri session and creates a Synchronous Connection (SCO) for the audio.
- If the Siri session is not finished, the accessory shall send AT+BVRA=1 to continue the conversation. This may need to happen multiple times.
- When the Siri session is finished, the device sends a +BVRA:0 result code to the accessory.
- The device disconnects the SCO connection.

While a Siri session is active, the accessory shall let the user continue the conversation and ask follow up questions within the current context. In order to do so, the accessory shall be able to send an AT+BVRA=1 command to the device even after Siri has been already activated and before +BVRA:0

Copyright © 2025 Apple Inc. All Rights Reserved.

is received. Figure 44-2 (page 220) shows an overview of the interaction when Siri is triggered from the accessory, the running session was continued twice and once Siri was finished, the device dismissed the session.

Figure 44-2 Initiating a Siri Session from the Accessory

44.3.2 Initiating a Session from the Device

If the accessory supports voice recognition commands, the device sends a +BVRA event to indicate the start of a Siri session. The accessory shall enable support for voice recognition and indicate it in its feature response as described in the *Bluetooth Hands-Free Profile Specification–Version 1.6, Section 4.34.1*. Specifically, the HFP profile shall be connected, SLC shall exist, and voice recognition activation (bit 3) shall be enabled in the AT+BRSF command. The device will not use virtual call functionality for the Siri session if voice recognition activation is supported by the accessory.

The accessory should expect the following command sequence:

- The device sends a +BVRA`:1` event to the accessory.
- The device activates a Siri session and creates a SCO connection for the audio.
- When the Siri session is finished, the device sends a +BVRA`:0` result code to the accessory.
- The device disconnects the SCO connection.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 44-3 Initiating a Siri Session from the Device



44.3.3 Ending a Session from the Accessory

Once a Siri session is running the accessory shall be capable of ending the session by sending an AT+BVRA=0 command to the device. Figure 44-4 (page 221) shows an example of ending a running Siri session from the accessory. The accessory should only end an active session as a result of a direct user action.

Figure 44-4 Ending a Siri Session from the Accessory



44.4 Siri Eyes Free Mode

Siri Eyes Free mode is a feature to control Siri responses including display information and can be enabled or disabled as needed. In Siri Eyes Free mode, the user experience is tailored towards a driving scenario and interactions with Siri are done primarily using voice to minimize the need for the user to look at a screen. Siri Eyes Free mode is supported only for Bluetooth-enabled vehicle entertainment systems and should not be used by any other accessories. Siri Eyes Free should not be triggered using a voice command.

The device will listen for the HFP AT command `AT+APLEFM` to enable or disable Siri Eyes Free mode.

This command is used by the device to modify Siri responses containing visual information or requiring user interaction. Suitable audio feedback and voice commands will be available to the user based on the initiated Siri use case.

Siri Eyes Free mode is disabled by default. Once the accessory has enabled Siri Eyes Free mode, it remains enabled for all subsequent Siri sessions initiated from the accessory until the accessory disables it or the Bluetooth connection is disconnected.

44.4.1 HFP Command AT+APLEFM

Description: An accessory sends this command to notify a device of the preferred state of Siri Eyes Free mode.

Initiator: Accessory

Format: `AT+APLEFM=`*value*

Response: `OK`

Defined Values:

- `0x00` = Disable Siri Eyes Free mode.
- `0x01` = Enable Siri Eyes Free mode.
- `0x02-0xFF` = reserved

Example: `AT+APLEFM=1`

44.5 Improving Voice Recognition

The microphone audio an accessory sends to the device during a Siri session should be suitable for voice recognition. Audio requirements for optimal voice recognition may differ from requirements for optimal human perception (for example, during a cellular phone call).

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Filtering of the audio signal to remove echoes or feedback noise is acceptable.

To provide the best possible audio quality as Siri input, the accessory shall observe the following recommendations:

- **Echo cancellation and noise suppression (EC/NR)**: Directional microphones and linear beamforming with microphone arrays giving improved SNR are recommended. Linear echo cancellation for reducing unwanted audio sources (such as audio output from the system) without having any other effect on the speech signal is also recommended. Any approach taken should not have any other effect on the speech signal. Single channel noise reduction methods (such as spectrum subtraction) shall not be applied, as they will be detrimental to the speech recognition accuracy. Similarly, automatic gain control, residual echo suppression and attempts to blank out non-speech periods in the waveform shall not be applied.
- **Signal gain**: When adjusting signal levels, the accessory shall avoid artifacts, dropouts, and clipping in all circumstances. Automatic Gain Control is not recommended. If the accessory adjusts signal gain, the gain should be held constant across each spoken utterance. The nominal level measured at the uplink output of the accessory should be A-weighted -30 dB ±2 dB root-mean-square (RMS), expressed in units relative to full-scale (dBFS(A)). Alternatively, the nominal level may be 13 dB ±2 dB SLR if using the ITU measurement procedure.
- **Signal-to-noise ratio (SNR)**: The average SNR should be greater than 20 dB. Below 20 dB, recognition rates will be impacted.
- **Reverberation**: An RT60 time less than 200 ms should be maintained.

44.5.1 Wide Band Speech Support

An accessory using Siri should support 16 kHz wide band speech audio for better audio quality and voice recognition performance. See the *Bluetooth Hands-Free Profile Specification – Version 1.6* for details about wide band speech audio. Narrow band audio signal (8 kHz) is supported but not recommended.

44.6 Optimizing the Siri Experience

The start of a Siri session should not be accompanied by local beeps or verbal indications (such as an announcement of "...voice dialing...") from the accessory. When a Siri session becomes active, the device sends two beeps indicating Siri is ready to receive instructions. Adding extra audible notifications only inserts delays in the system.

The accessory should wait for the device to end each Siri session.

The accessory should not send an `AT+BVRA=0` command unless it is prompted to do so by user interaction.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

The accessory should be capable of rendering audio within 200 ms of SCO connection activation to ensure the user always hears the Siri introductory beeps.

44.7 Common Siri Applications

Siri can send messages, find points of interests, place phone calls, and much more. As Siri capabilities are constantly growing, additional use cases may become available after the initial integration. In Siri Eyes Free mode, some of these use cases may not be accessible as the user experience is tailored towards a driving scenario.

44.7.1 Initialization Procedure After Connection is Established

Figure 44-5 (page 224) outlines the sequence the accessory has to trigger to be able to use Siri on a device. After establishing an HFP profile connection, the accessory shall first enable the custom Siri commands by sending `AT+XAPL` and provide the features it supports. After a confirmation is received from the device, the accessory should determine Siri's availability with `AT+APLSIRI?`.

Vehicles with Bluetooth-enabled infotainment systems can also enable Siri Eyes Free Mode during initialization. This is detailed in Figure 44-6 (page 225).

Figure 44-5 Siri Initialization Procedure



Figure 44-6 Siri Initialization Procedure with Siri Eyes Free



44.7.2 Phone Dialing Using Siri

Upon user request, Siri can initiate an outgoing phone call. The device will initiate HFP call signaling to establish a phone call as described in Bluetooth (page 258). The accessory shall be able to transition to Hands-Free dialing at any time during or after a Siri session when signaled by the device.

44.7.3 Audio Routing and Media Playback Using Siri

Siri can control the media playback on a device, and if Siri determines the user wants to play or pause music, Siri will either start, pause or resume media playback. The device will send a notification to the accessory indicating a change in playback state and any associated track information. The accessory shall respond to the notifications, start or stop the music playback as requested, as well as update the correct playback state (for example, shuffle, repeat).

The accessory shall not force a change in the playback state after a Siri session is ended. If music was playing before Siri was started, it shall continue playing, if it was paused, it shall remain paused.

After Siri starts music playback the accessory shall set its current audio route to match the audio source, depending on how audio is being received from the device (using Bluetooth or by a wired connection).

The available media playback notifications depend on the audio route being used:

- Bluetooth audio routes shall use the approach described in Notifications (page 265) and Audio Data Received using A2DP Profile (page 267).
- Wired audio routes shall use iAP2.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

44.7.4 Turn-By-Turn Directions Using Siri

Siri can initiate active route guidance to provide turn-by-turn directions. In case the device is the active source and is already playing music, turn-by-turn directions will be mixed in as part of the audio stream. In case the device is not playing music, the accessory should be able to mix in turn-by-turn directions with the active audio source.

The device will notify the accessory to play turn-by-turn directions only over Bluetooth. Detailed information on how to distinguish between music playback and turn-by-turn notifications is available in Notifications (page 265).

44.8 User Interaction with Siri Eyes Free in a Vehicle

A vehicle using Siri Eyes Free mode shall integrate the Siri experience with the existing in-vehicle entertainment system and controls. The vehicle should provide a convenient interface to initiate, continue, and end a Siri session. Once a Siri session is running, the vehicle shall display a visual cue indicating voice recognition is in use. Figure 44-7 (page 227) outlines how a Siri interaction should be designed.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 44-7 Siri Eyes Free user interaction



As shown in Figure 44-7 (page 227):

- (*) If the accessory wishes to indicate Siri is active, it shall either:
  - Display the word 'Siri' (as capitalized) with no additional text or icon.
  - Use generic text or icon not resembling the Siri microphone icon.
- (**) If the vehicle is equipped with steering wheel controls, the steering wheel shall have a dedicated button or a long-press action on a button to start, continue and end a Siri session. The button long-press shall be 600 ms or less. If no steering wheel controls are available, a soft button shall be available within the in-vehicle user interface to start, continue or end a Siri session.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

When a vehicle enables Siri Eyes Free mode, the device will not display any onscreen Siri content. If the device was locked at the time the Siri session was activated from the vehicle, it will remain locked and the screen will not wake. If the user unlocks or manually activates the device while in an Eyes Free Session there will be a notification the device is in an active Siri session but there will be no visual Siri content displayed.

44.9 Enabling/Disabling Siri from the Device

The user has the ability to disable or enable Siri from the Settings menu on the device. When Siri is disabled, Voice Control becomes the recognition engine on the device and will be triggered by default. The accessory may choose to either:

- Activate Voice Control (in the same way Siri is activated) as in Figure 44-8 (page 228).
- Display a warning message and not send an activation command to the device as in Figure 44-9 (page 229).

Figure 44-8 Siri is disabled - activating Voice Control



Figure 44-9 Siri is disabled - displaying a warning message



44.10 Verification

44.10.1 Siri Eyes Free

The following test procedures are applicable to accessories interacting with Siri Eyes Free.

The ideal test operator is a native speaker of North American English. If the operator's native language is not North American English, set Siri to the operator's native language and translate the provided phrases into their native language.

44.10.1.1 General

1. Pair and establish a Bluetooth Hands-Free Profile (HFP) connection between the device and the head unit. Activate Siri from the vehicle steering wheel button (for example, by pressing and holding):
   a. Observe the device screen remains inactive after a Siri session has started (a visual indicator will be visible on the device if the screen is activated manually).
   b. Ensure Siri's opening chime is heard completely through the vehicle speakers.
   c. Observe a visual notification in the in-car User Interface (UI) indicating a Siri session is active (for example, text notification, on-screen UI).
2. Activate Siri from the vehicle steering wheel button and say "Send a message to Peter. How are you?". While still saying the message, press the vehicle steering wheel button to cancel Siri:
   a. Ensure the device screen remains inactive (if manually activated, the visual indicator on the phone will disappear).
   b. Verify the in-car Siri UI interaction is dismissed and the head unit returns to its prior state before the Siri interaction.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

3. Activate Siri from the vehicle steering wheel button and say "How is the weather in San Francisco?". Wait for Siri to respond with the weather forecast. Once the weather forecast is complete, resume Siri from the vehicle steering wheel button and say "What about New York?":
   a. Confirm the visual indicator is still active on the phone.
   b. Listen for the Siri opening chime.
   c. Verify the vehicle UI indicates a Siri session is active.
   d. Verify Siri responds with the weather forecast for New York.
4. In case the vehicle UI offers on-screen controls to activate/cancel/resume Siri, repeat steps (1) to (3) for all on-screen controls.
5. Activate Siri from the steering wheel button and say "What's the time?". Listen to the current time and do not interact with Siri or the device. After 5 seconds have expired:
   a. Observe the visual Siri session indicator on the phone is no longer visible.
   b. Verify the in-car UI for Siri interaction was dismissed.
   c. Verify the head unit returned to its prior state before the Siri interaction.
6. Listen to FM radio from the car speakers (for example, no A2DP streaming active). Press and hold the device Side/Top/Home button to activate Siri:
   a. Observe a visual notification in the in-car UI indicating a Siri session is active (textual notification, on-screen UI, etc.).
   b. Observe Siri's interaction on the device screen and ask "What's the time?".
   c. After Siri has responded, lock the device again to dismiss the Siri session by pressing the device Side/Top/Home button.
7. Open Settings and turn Siri off. Activate Siri from the head unit. Observe one of the following depending on the actual implementation (a) Voice Control starts instead of Siri (b) The head unit displays a warning indicating Siri Eyes Free is not available.
8. Open Settings and turn Siri back on. Verify Siri can be activated/cancelled from the head unit and from the device Side/Top/Home button.
9. Open Settings and turn Bluetooth off. Verify Siri cannot be started.
10. Open Settings and turn Bluetooth back on. Verify Bluetooth HFP profile reconnects and Siri can be activated/cancelled from the head unit and from the device Side/Top/Home button.
11. Confirm there is no accessory battery status level indicator icon displayed on the device status bar.

44.10.1.2 Siri Dialog

1. Activate Siri from the vehicle's steering wheel button and say "Send a text message to *insert contact name*". When Siri prompts "What would you like it to say?", dictate a short message. After Siri has read back the dictated message, say "Review it". After Siri has read back the message again, say "Review it" again. Repeat this cycle ~5 times to ensure the head unit is able to handle a long interaction with Siri. At the end say "Send it" and verify the message is sent. Verify the opening

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

chime is audible and the message is sent. After the Siri session is closed, verify the audio playback went back to the audio state it was in before Siri was activated (that is, if audio was paused it remains paused, if it was playing it resumes playing).

2. Start Siri from the vehicle's steering wheel button and ask for directions. Follow up through the dialog until the navigation is started. Verify the Siri session is closed and the audio playback returns to the audio state it was in before Siri was activated (that is, if audio was paused it remains paused, if it was playing it resumes playing).
3. Start Siri from the vehicle's steering wheel button and say "Search the web for polar bears". Verify Siri Eyes Free mode is on and this use case is blocked by Siri. In some implementations the vehicle has to be in motion before Siri Eyes Free is activated by the car kit.
4. Start Siri from the vehicle's steering wheel button and say "What is the current time in Munich?". After Siri answers but before ~5 seconds have elapsed, resume Siri (for example, using a short press on the steering wheel button) and verify Siri is activated again. Say "What about San Francisco?". Repeat (with a different city) and verify this can continue indefinitely as long as there is a short press on the steering wheel button within 5 seconds of the last response.

44.10.1.3 Bluetooth HFP A2DP Music

1. Establish a Bluetooth A2DP connection and switch to Bluetooth audio source on the head unit. Activate Siri and say "Next track". Verify the track advances and audio is played through the vehicle speakers. Verify the Siri in-car UI is dismissed and the head unit returns to its initial audio state.
2. Activate Siri and say "Pause the music". Verify audio remains paused after Siri has been dismissed. Verify the Siri in-car UI is dismissed and the head unit returns to its initial audio state.
3. Pause music playback on the head unit (using AVRCP command). Activate Siri and ask "What time is it?". Verify the music playback remains paused after the Siri session has been dismissed. Verify the Siri in-car UI is dismissed and the head unit returns to its initial audio state.
4. Switch to FM radio on the head unit. Activate Siri and say "Play me a song". Verify the head unit is able to automatically switch to Bluetooth audio and music starts playing. Verify the beginning of the selected track is heard (for example, there is no skipping of audio packets). Verify the Siri in-car UI is dismissed and the head unit returns to its initial audio state.
5. Activate Siri and say "Shuffle all songs". Verify the head unit correctly updates the NowPlaying track information. Verify the Siri in-car UI is dismissed and the head unit returns to its initial audio state.
6. Activate Siri and ask to play a specific artist or title. Verify the Siri session is dismissed after the music starts. Confirm the correct metadata is displayed on the screen. Verify the Siri in-car UI is dismissed and the head unit returns to its initial audio state.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

44.10.1.4 Call

1. Activate Siri and call a contact with more than one phone number (for example, home and mobile). Wait for Siri's response asking which phone number to call. Answer with "home". Verify call transition is handled correctly by the head unit and any Siri UI displayed on the vehicle screen is dismissed.
2. While device music is playing, activate Siri and say "Call *(insert contact to call)*". Verify call transition is handled correctly by the head unit. Verify device music playback resumes after the call has been answered and terminated on the far end. Verify the Siri in-car UI is dismissed and the head unit returns to its initial audio state.
3. While device music is playing, start Siri and say "Call *(insert contact to call)*". Verify call transition is handled correctly by the head unit. Verify device music playback resumes after the call has been answered and terminated on the near end (that is, on the head unit). Verify the Siri in-car UI is dismissed and the head unit returns to its initial audio state.
4. While in a Siri session, receive an incoming call on the head unit. Verify the head unit handles call-signaling correctly and transitions to the phone UI once the call has been accepted. Verify the Siri in-car UI is dismissed and the head unit returns to its initial audio state.

44.10.1.5 Bluetooth + Wired iAP2

1. Connect the device to the head unit. Switch to device audio and verify audio is playing. Activate Siri and say "Next track". Verify the track advances and the head unit displays the track metadata correctly. Verify the Siri in-car UI is dismissed and the head unit returns to its initial audio state.
2. From the head unit UI, select a playlist with a single song and start playing it. Start Siri from the vehicle steering wheel and say "Play ..... *make sure to select a song to play (a) not in the same album as the single-track playlist and (b) not song track index 0 of its album*". Verify the new song starts playing and the head unit correctly displays the track metadata for the new song. Verify the Siri in-car UI is dismissed and the head unit returns to its initial audio state.
3. Turn Shuffle off on the head unit UI. Then start Siri and say "Shuffle all songs". Verify the shuffle indicator on the head unit UI is updated and the correct track metadata for the new now playing song is displayed correctly. Verify the Siri in-car UI is dismissed and the head unit returns to its initial audio state.
4. Switch to FM radio on the head unit. Activate Siri and say "Play me a song". Verify the head unit is able to automatically switch to device audio source and music starts playing through the speakers. Verify there is no skipping of audio at the beginning of the selected track. Verify the Siri in-car UI is dismissed and the head unit returns to its initial audio state.
5. Pause music playback on the head unit (using iAP2 commands). Activate Siri and ask "What time is it?". Verify music playback remains paused after the Siri session has been dismissed. Verify the Siri in-car UI is dismissed and the head unit returns to its initial audio state.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

6. While device music is playing, start Siri and say "Call *(insert contact to call)*". Verify call transition is handled correctly by the head unit. Verify device music playback resumes after the call has been answered and terminated on the far end. Verify the Siri in-car UI is dismissed and the head unit returns to its initial audio state.
7. While device music is playing, start Siri and say "Call *(insert contact to call)*". Verify call transition is handled correctly by the head unit. Verify device music playback resumes after the call has been answered and terminated on the near end (for example, on the head unit). Verify the Siri in-car UI is dismissed and the head unit returns to its initial audio state.
8. Pause music playback on the head unit (using iAP2 commands). Start Siri and say "Call *insert contact name to call*". Verify call transition is handled correctly by the head unit. Verify device music playback remains paused after the call has been answered and terminated on the far end. Verify the Siri in-car UI is dismissed and the head unit returns to its initial audio state.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

45. Wi-Fi Information Sharing

Wi-Fi configuration information can be exchanged between devices and accessories.

Devices can share Wi-Fi configuration information with an accessory. The accessory can initiate this process, but the user shall grant permission for the device to share this information. The device can only share information about the currently connected Wi-Fi network, and this feature will not account for other router-configured access control mechanisms, such as RADIUS or MAC address filtering.

Figure 45-1 Wi-Fi information sharing alert

See the Accessory Interface Specification (page 27) for more information.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Protocols

46. USB Power Capability Vendor Request

If the accessory is a USB host, and it does not implement iAP2 (page 246), then it may send an Apple-specific USB vendor request communicating how much power is available to the device. In this case, the accessory shall enumerate and identify the presence of a device, then send the vendor request. The vendor request shall be sent every time the device is enumerated by the accessory.

Table 46-1 USB Vendor Request for non-iAP2 accessory USB Embedded Host

Field	Value	Comments
`bmRequestType`	`0x40`	Device-to-host request, vendor-defined type, device is recipient.
`bRequest`	`0x40`	Vendor-defined USB get enabled capabilities request.
`wValue`	See comments.	Charging current available, expressed as an offset from 500 mA. Shall be 500 (1000 mA charging current available), 1000 (1500 mA charging current available), 1600 (2100 mA charging current available), 1900 (2400 mA charging current available), or 2500 (3000 mA charging current available).
`wIndex`	See comments.	Shall be the same as wValue.
`wLength`	`0`	0 bytes expected.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

47. USB D+/D- Resistor Networks

Accessories not implementing any of the following may use USB resistor networks to identify their current capability:

- iAP2 (page 246).
- USB Power Capability Vendor Request (page 236).
- USB Type-C Current (page 241).
- USB Power Delivery (PD) (page 240).

Device power draw varies with environmental factors. Accessory power source testing shall be performed with programmable loads, not devices.

47.1 Declaring Power Source Capability

Accessories shall connect the USB D+ and USB D- pins to resistor networks as shown in Figure 47-1 (page 237).

Figure 47-1 USB D+/D- resistor networks



Every iOS device-compatible connector on an accessory using a USB resistor network shall have its own set of resistors. The accessory shall be capable of supplying the total current required when all connectors are in use, regardless of whether the connectors are compatible with devices or not.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

The resistor network shall be connected at all times unless the accessory uses one of the following methods to enable charging or detect the presence of a device. In these cases, it shall immediately present the resistor network. The accessory:

- Uses a direct user action to enable charging.
- Senses the attachment of the device using electromechanical means such as a contact switch.

The accessory shall not monitor the USB D+ and USB D- pins to detect the presence of a device.

Resistors used to implement the networks specified in Figure 47-1 (page 237) shall have a tolerance of 1% or better. The resistor network shall not be emulated by driving the voltage of the USB D+/D- pins using some other means.

Table 47-1 USB D+/D- resistor values

Max Current	R1	R2	R3	R4
3000 mA	43.2 kΩ	49.9 kΩ	24.9 kΩ	49.9 kΩ
2400 mA	43.2 kΩ	49.9 kΩ	43.2 kΩ	49.9 kΩ
2100 mA	43.2 kΩ	49.9 kΩ	75.0 kΩ	49.9 kΩ
1000 mA	75.0 kΩ	49.9 kΩ	43.2 kΩ	49.9 kΩ

47.2 Identifying Power Source Current Limit

Accessories shall take into account the variation of USB VBUS voltage and resistor tolerances.

The resistor network values and corresponding current source limits should be identified using the following procedures:

1. Read the VBUS voltage using an ADC. If value is less than 4.5 V, return no resistors detected.
2. Pull-down the D+ and D- lines and read the voltage using an ADC. If either voltage value is less than 1 V, return no resistors detected.
3. Disable the D+ and D- pull-downs and allow the voltage to return to normal.
4. Read the D+ and D- voltages using an ADC (to determine the value for R1 and R3 respectively):
   - If voltage is >2.995 V (based on 1 MΩ load impedance), assume a resistor value of 24.9 kΩ.
   - If voltage is between 2.320 V and 2.995 V (based on 1 MΩ load impedance), assume a resistor value of 43.2 kΩ.
   - If voltage is < 2.320 V (based on 1 MΩ load impedance), assume a resistor value of 75.0 kΩ.
5. Determine the max current based on Table 47-2 (page 239).
6. If resistor values could not be identified, proceed to identify the power available based on the *USB Battery Charging Specification –Release 1.2*.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Table 47-2 USB D+/D- resistor values

Max Current	R1	R2	R3	R4
1000 mA	24.9 kΩ	49.9 kΩ	24.9 kΩ	49.9 kΩ
1000 mA	24.9 kΩ	49.9 kΩ	43.2 kΩ	49.9 kΩ
1000 mA	24.9 kΩ	49.9 kΩ	75.0 kΩ	49.9 kΩ
3000 mA	43.2 kΩ	49.9 kΩ	24.9 kΩ	49.9 kΩ
2400 mA	43.2 kΩ	49.9 kΩ	43.2 kΩ	49.9 kΩ
2100 mA	43.2 kΩ	49.9 kΩ	75.0 kΩ	49.9 kΩ
1000 mA	75.0 kΩ	49.9 kΩ	24.9 kΩ	49.9 kΩ
1000 mA	75.0 kΩ	49.9 kΩ	43.2 kΩ	49.9 kΩ
500 mA	75.0 kΩ	49.9 kΩ	75.0 kΩ	49.9 kΩ

Copyright © 2025 Apple Inc. All Rights Reserved.

48. USB Power Delivery (PD)

Accessories providing direct power using USB Power Delivery (PD) or drawing power from USB PD sources shall comply with the *USB Power Delivery Specification –Revision 3.2, Version 1.1*, see https://www.usb.org/document-library/usb-power-delivery.

Accessories implementing USB PD shall incorporate a USB-IF certified PD controller with a *Silicon* Test ID from the USB-IF, see https://www.usb.org/products.

Apple recommends the GRL-USB-PD-C2 (see https://www.graniteriverlabs.com/en-us/test-solutions/protocol-power-test-solutions/usb-pd-c2) for USB PD testing and compliance verification.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

49. USB Type-C Current

Accessories providing direct power using USB Type-C Current or drawing power from USB Type-C Current sources shall comply with the *USB Type-C Cable and Connector Specification –Release 2.3, Section 4.6.2*.

Apple recommends the GRL-USB-PD-C2 (see https://www.graniteriverlabs.com/en-us/test-solutions/protocol-power-test-solutions/usb-pd-c2) for USB Type-C Current testing and compliance verification.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

50. Advanced Audio Distribution Profile (A2DP)

Accessories may implement the Advanced Audio Distribution Profile (A2DP) over Bluetooth (page 258) to receive audio from iPhone, iPad, Apple Watch, Apple TV, Mac, and Apple Vision Pro.

The audio content from the device can be broadly classified into two categories:

- Audio content from music, video, or gaming applications.
- System-generated sounds for alerts and notifications.

A2DP is often implemented in speakers and headsets.

Accessories implementing A2DP shall satisfy all requirements stated in Bluetooth (page 258).

50.1 Bluetooth A2DP Specification

Accessories implementing the Advanced Audio Distribution Profile (A2DP) shall meet the requirements of the Bluetooth *Advanced Audio Distribution Profile Specification – Version 1.2*.

50.1.1 AVDTP Transactions

Accessories shall respond to Audio/Video Distribution Transport Protocol (AVDTP) signaling transactions before the device's five second RTX_SIG_TIMER expires or the device will terminate the signaling channel. See Bluetooth *Audio/Video Distribution Transport Protocol – Version 1.3, Section 6.2 Transaction Model and Section 6.4 Signal Command Set*.

50.2 SubBand Codec (SBC)

The SBC Codec Specific Information Elements, defined in *Advanced Audio Distribution Profile Specification – Version 1.2, Section 4.3.2*, applicable to iOS devices and Mac computers are listed in Table 50-1 (page 243).

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Table 50-1 SubBand Codec Information Elements for iOS devices and Mac computers

Element	Value
Sampling Frequency	16 kHz, 32 kHz, 44.1 kHz, and 48 kHz.
Channel Mode	Stereo
Block Length	16
Subbands	8
Allocation Method	Loudness
Bitpool range	2 to 53. Accessories should support 53.

50.3 MPEG 2/4 AAC Codecs

Devices support the non-mandatory codec MPEG-2/4 AAC, as defined in *Advanced Audio Distribution Profile Specification–Version 1.2, Section 4.5*. Accessories should use the AAC codec in addition to SBC, because AAC provides higher audio quality for a given bit rate.

> **Note:**
> The following specifications provide details of Apple's implementation of the MPEG-2/4 AAC codec. In case of conflicts, the A2DP specification governs.

The MPEG 2/4 AAC Codec Specific Information Elements, defined in *Advanced Audio Distribution Profile Specification–Version 1.2, Section 4.5*, applicable to devices are listed in Table 50-2 (page 243).

Table 50-2 MPEG-2/4 AAC Codec Information Elements for devices

Element	Value
Object Type	MPEG-2 AAC LC
Sampling Frequency	8 kHz, 11.025 kHz, 12 kHz, 16 kHz, 32 kHz, 44.1 kHz, 48 kHz, 64 kHz, 88.2 kHz, and 96 kHz.
Channels	2
Bit rate	264,630 bps
VBR	1

AAC audio stream packets in devices have the structure shown in Table 50-3 (page 244).

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Table 50-3 AAC audio packet for devices

L2CAP	AVDTP	MPEG-4 LATM	MPEG-4 AAC
Header	Header	AudioMuxElement	Audio Payload

The AAC Media Payload Format, as defined in *Advanced Audio Distribution Profile Specification –Version 1.2, Section 4.5.4*, is formatted using LATM as defined in *IETF RFC 3016 –Section 4*. The following notes apply to the packet fields shown in Table 50-3 (page 244).

- The recommended L2CAP MTU value for each device's AAC streaming channel is 885 bytes.
- The AVDTP Header is shown as the RTP header in *RFC 3016 –Figure 4*, defined in Bluetooth *Audio/Video Distribution Transport Protocol –Version 1.2, Section 7.2.1*.
- The `AudioMuxElement` is the same as the *RFC 3016 –RTP payload*, defined in *ISO/IEC 14496-3:2009 –Subpart 1, Section 1.7.3, Table 1.41*. The `muxConfigPresent` argument to the `AudioMuxElement` is set to 1 (in-band mode), as recommended in *RFC 3016 –Section 4.1*. As recommended in *RFC 3016 –Section 4.3*, only one `AudioMuxElement` is put into each AVDTP packet.
- The audio payload is encoded using MPEG-4, as recommended in *Advanced Audio Distribution Profile Specification –Version 1.2, Section 4.5.4*.
- The accessory should support AAC-LC VBR and handle bit rate changes without audio gaps. Devices will vary AAC bit rate depending on the content. Accessories supporting VBR shall support a minimum bitrate of 96 kbps.

50.4 Verification

50.4.1 Audio Quality

Verify there are no audio quality issues in each of the following scenarios:

1. Stream music from the Apple Music app.
2. Stream music from a radio station within the Apple Music app.
3. Stream audio using the Apple Podcasts app.

50.4.2 Audio Switching

1. During A2DP streaming, switch audio back to device and switch back to accessory.
2. Verify audio was routed to the intended source, and audio quality was good switching back to Bluetooth.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

50.4.3 HFP Interaction

1. Make incoming/outgoing call during A2DP.
2. Verify audio was suspended during the call and resumed after the call.

50.4.4 Siri

1. Trigger Siri during A2DP.
2. Verify audio resumed after the Siri session.

50.4.5 Video Playback

1. Stream A2DP while watching a video.
2. Verify audio/video synchronization and quality is good.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

51. iAP2

Accessories may use the iAP2 protocol to access advanced device features, such as:

- Communicating securely with third-party iOS/iPadOS apps using the External Accessory Protocol (page 187).
- Accessing the media library and retrieving album artwork using Media Library Access (page 213) and Now Playing Updates (page 215).
- Launching apps using App Launch (page 169).
- Discovering compatible apps using App Discovery (page 168).
- Helping users find compatible apps in the App Store using App Match (page 170).
- Providing GNSS location data using Location Information (page 192).
- Supporting connectivity with Out-of-Band Bluetooth Pairing (page 216) and Wi-Fi Information Sharing (page 234).

See the Accessory Interface Specification (page 27) for more information.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

52. Human Interface Device (HID)

Devices can accept input from and send output to Human Interface Device (HID) accessories, such as external keyboards, trackpads, mice, and game controllers. This capability is made available system-wide for all apps on the device as well as to support features built into iOS, iPadOS, and tvOS. If an accessory is designed to provide human input events to a specific third-party app, the accessory should use the External Accessory Protocol feature instead; see the Accessory Interface Specification (page 27) for more information.

The HID protocol can be implemented over:

- USB
- Bluetooth

52.1 Requirements

Accessories shall only send HID reports for changes in physical or virtual control surfaces declared in the corresponding HID descriptor.

Accessories shall not send a HID report if there has not been any change in the state of the corresponding physical or virtual control surface. For example, the accessory shall never generate a "Play/Pause" event without the user pressing a dedicated "Play/Pause" button.

Each HID report shall contain the correct number of bytes as described in its corresponding HID descriptor.

The accessory shall not anticipate or assume corresponding state changes in the device after sending HID reports.

Unless otherwise specified:

- The accessory shall be capable of generating and receiving all HID usages declared in its HID descriptor.
- The accessory's declared HID usages shall map directly to physical or virtual control surfaces on a 1:1 basis. For example, a button labeled "Play/Pause" shall send a Play/Pause HID usage and not "Play" or "Pause" usages. Compound controls such as knobs, joysticks, and directional pads may be considered multiple control surfaces. For example, clockwise and counterclockwise rotation may map to separate HID usages.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- Physical or virtual control surfaces generating HID reports shall be labeled with appropriate iconography or text corresponding to the resulting device behavior. For example, a Play/Pause button shall be labeled with the text 'Play/Pause' or a Play/Pause icon.
- The accessory shall send one HID report in response to each direct user action on the corresponding physical or virtual control surface. For example:
  - When the user presses a button, one 'button pressed' HID report shall be sent to the device.
  - When the user releases the button, one 'button released' HID report shall be sent to the device.

52.1.1 Report Descriptor

When padding packets to align within a byte boundary, each Main item tag (Input, Output, or Feature) shall be marked constant. Padding bits should be set to 0.

When defining Variable type Input/Output fields, either:

- Report Count number shall correspond to the number of Usages specified.
- Report Size shall be 8 and the Report Count shall correspond to the size of a multi-byte blob.

52.1.2 USB

If implementing HID over USB, the accessory shall comply with the *Device Class Definition for Human Interface Devices (HID) – Version 1.11*, see https://www.usb.org/hid.

52.2 Verification

52.2.1 General

1. Verify the accessory generates and receives all HID usages declared in the component's HID descriptor.
2. Verify the accessory does not send a HID report if there has not been any change in the state of the control surfaces (that is, no polling of HID reports).
3. Verify if any accessory has physical or virtual control surfaces generating accessory HID usages, the controls are labeled with appropriate iconography or text corresponding to the resulting device behavior (for example, a Play/Pause button is labeled with the text "Play/Pause" or a Play/Pause icon).
4. Verify HID usages map to physical or virtual controls on a 1:1 basis (for example, Play button only sends Play usages, not Play/Pause).

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

5. Verify one accessory HID report is sent in response to each direct user action on the corresponding physical or virtual control surface. For example, when the user presses a button, one 'button pressed' usage report is sent, and a separate 'button released' usage report is sent when the user releases the button.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Transports

53. Wi-Fi Aware

Peer devices and accessories integrating Wi-Fi Aware technology shall support the *Wi-Fi Aware Specification – Version 4.0*.

This feature is supported on iOS 26.0 and iPadOS 26.0 or later.

53.1 Overview

Wi-Fi Aware, also known as Neighbor Awareness Networking (NAN), is a Wi-Fi Alliance specification enabling devices to discover, pair, and communicate directly and securely with nearby devices. This connection does not require a traditional access point or an internet connection.

A *peer device* is any third-party product (such as an accessory, embedded system, or non-Apple phone/tablet) communicating with a device using Wi-Fi Aware.

Applications can use the Wi-Fi Aware framework (see https://developer.apple.com/documentation/WiFi-Aware) to discover, pair, and securely connect with Wi-Fi Aware certified accessories and peer devices. Use cases include:

- Smart cameras transferring photos or videos to a device.
- Personal computers transferring files to or from a device.

53.2 Requirements

To ensure compatibility, peer devices shall be Wi-Fi Aware certified and support the following enabled features, as defined in the specification:

- Secure pairing with NIK caching, including pairwise data and management frame protection.
- Multicast Data protection.
- Multicast Management Frame protection.
- Beacon protection.

> **Note:**
> The Neighbor Discovery Protocol (NDP) for IPv6 address resolution is not supported.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

53.3 Peer as a Subscriber

When acting as a subscriber, a peer device can browse for services offered by a device, then pair and connect. To do this, configure the peer device as an active subscriber to discover a publisher of the intended service. The peer device's Subscribe Service Discovery Frames (SDF) shall include the following attributes:

- **Service Descriptor Extension Attribute:** The device, as a publisher, does not use the Service-Specific Information (SSI) field. Therefore, Apple recommends omitting this field. Within the control field, set the `GTK Required` subfield to `1`. This ensures the peer device can encrypt and decrypt multicast data packets. Failing to set this bit will cause the device to reject the data path connection request. See *Wi-Fi Aware Specification – Version 4.0, Section 9.5.4.2, Table 55*.
- **Country Code Attribute:** If the peer device has a user-configured locale or can automatically determine its geo-location (for example, via GPS, Wi-Fi location, or IP address), the country code in the `Condensed Country String` field shall be set to reflect this location. If the locale is unknown, set the field to XZ. When the country code is XZ, the 5 GHz band will not be used for the Wi-Fi Aware protocol. In this case, the peer device should use the country code from the device's beacon or published SDF. See *Wi-Fi Aware Specification – Version 4.0, Section 9.5.12*.
- **WLAN Infrastructure Attribute:** If the peer device is connected to a Wi-Fi access point, all Wi-Fi Aware management frames it transmits shall include the `Extended WLAN Infrastructure Attribute`. The `Non–NAN Operating Channel Information` field shall be set to the Wi-Fi infrastructure channel. The `BSSID` and `MAC Address` fields are not required and may be set to all `0`'s to improve privacy. See *Wi-Fi Aware Specification – Version 4.0, Section 9.5.23.3*.
- **NAN Identity Resolution Attribute (NIRA):** This attribute contains the peer device's identity key, enabling the device to recognize previously paired peer devices.
- **Cipher Suite Information Attribute:** The supported `Cipher Suite ID` are NCS-GTK-CCMP-128 (5) and NCS-PK-PASN-128 (7). Set the `Capabilities` field bits 1 and 2 to `0b10` to specify GTKSA, IGTKSA, and BIGTKSA are supported. See *Wi-Fi Aware Specification – Version 4.0, Section 9.5.21.2*.

After discovery, the peer device initiates pairing with the device for authentication, as defined in *Wi-Fi Aware Specification – Version 4.0, Section 7.6.4*. The peer device initiates the pair setup by transmitting a bootstrap request containing the following attributes:

- **NAN Pairing Bootstrap Attribute:** Set the `Pairing Bootstrap Method` field to `pin–code only (keypad)`. The device, acting as a publisher, currently supports a 6-digit PIN as the pairing method. See *Wi-Fi Aware Specification – Version 4.0, Section 9.5.21.7*.
- **Device Capability Extension Attribute:** This attribute shall be included in `Bootstrap Request` frames. The `NPK/NIK Caching` bit in the `Capability Info` field shall be set to `1` to indicate support for pair verification.
- **Service Descriptor Extension Attribute:** Use the TXT Record (`key=value`) format for the SSI field, as specified in *RFC 6763 – Section 6.3*. Use the following keys with human-readable, UTF-8 string values, each with a maximum length of 63 bytes:

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- `vendorName`: The vendor name of the peer device.
- `modelName`: The model name of the peer device.
- `pairingName`: The hostname of the peer device used for pairing.

For example:

- `vendorName=Apple`
- `modelName=iPhone`
- `pairingName=Joe's iPhone`

Upon completion of pair setup or pair verification, the data path negotiation shall exchange the IGTK, BIGTK, and GTK along with the PTK. The `Data Path Request` frame shall include the following attributes in addition to the mandatory fields:

- **NAN Data Path Extension Attribute:** The `GTK Required` subfield in the `NDPE Control` field shall be set to 1, indicating the device supports encryption and decryption of multicast data frames.

53.4 Peer as a Publisher

When acting as a publisher, a peer device advertises services, allowing a device to discover, pair, and connect to it. To save power, Apple recommends configuring the peer device as a solicited publisher. It may temporarily switch to an unsolicited publisher to announce an update. The peer device's Publish SDFs shall include the following attributes:

- **Service Descriptor Extension Attribute:** When a publisher is in pairing mode, the SSI field shall contain device information in the TXT Record format specified in Peer as a Subscriber (page 252). Conversely, a publisher not in pairing mode shall not include this device information. Within the control field, set the `GTK Required` subfield to 1. See *Wi-Fi Aware Specification – Version 4.0, Section 9.5.4.2, Table 55*.
- **Country Code Attribute:** If the peer device has a user-configured locale or can automatically determine its geo-location (for example, via GPS, Wi-Fi location, or IP address), the country code in the `Condensed Country String` field shall be set to reflect this location. If the locale is unknown, set the field to XZ. When the country code is XZ, the 5 GHz band will not be used for the Wi-Fi Aware protocol. In this case, the peer device should use the country code from the device's beacon or subscribe SDF. See *Wi-Fi Aware Specification – Version 4.0, Section 9.5.12*.
- **WLAN Infrastructure Attribute:** If the peer device is connected to a Wi-Fi access point, all Wi-Fi Aware management frames it transmits shall include the `Extended WLAN Infrastructure Attribute`. The `Non–NAN Operating Channel Information` field shall be set to the Wi-Fi infrastructure channel. The `BSSID` and `MAC Address` fields are not required and may be set to all `0`'s to improve privacy. See *Wi-Fi Aware Specification – Version 4.0, Section 9.5.23.3*.
- **NAN Identity Resolution Attribute:** This attribute contains the peer device's identity key, enabling the device to recognize previously paired peer devices.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- **NAN Pairing Bootstrap Attribute:** Set the `Pairing Bootstrap Method` field to `pin-code only (display)`. The device, acting as a subscriber, currently supports a 6-digit PIN as the pairing method. See *Wi-Fi Aware Specification – Version 4.0, Section 9.5.21.7*.
- **Cipher Suite Information Attribute:** The supported `Cipher Suite ID` are NCS-GTK-CCMP-128 (5) and NCS-PK-PASN-128 (7). Set the `Capabilities` field bits 1 and 2 to `0b10` to specify GTKSA, IGTKSA, and BIGTKSA are supported. See *Wi-Fi Aware Specification – Version 4.0, Section 9.5.21.2*.
- **Device Capability Extension Attribute:** The publisher shall set the `Pairing Setup` subfield to 1 to indicate it is in pairing mode and will accept new pairing requests. When not discoverable for pairing, this subfield shall be set to 0. Publishers should only enter pairing mode temporarily, typically following a user action to pair new devices, and should exit this mode after the process is complete. The `NPK/NIK Caching` bit in the `Capability Info` field shall be set to 1 to enable pair verification.

Upon completion of pair setup or pair verification, the data path negotiation shall exchange the IGTK, BIGTK, and GTK along with the PTK. The `Data Path Request` frame shall include the following attributes in addition to the mandatory fields:

- **NAN Data Path Extension Attribute:** The `GTK Required` subfield in the `NDPE Control` field shall be set to 1, indicating the device supports encryption and decryption of multicast data frames.

53.5 Privacy

Wi-Fi Aware transmissions can be detected by any nearby device, including devices operated by malicious actors. To protect user privacy and prevent tracking, peer devices shall not transmit uniquely identifying information in unauthenticated or unencrypted frames. This information should only be exchanged through the secure, encrypted NAN Datapath established after pairing is complete.

53.5.1 Service & Device Discovery

Data sent in service discovery frames, such as Subscribe, Publish, and Insecure Follow-Up frames, is neither authenticated nor encrypted and may be viewed or manipulated by an attacker. To minimize exposure, devices should only include the recommended minimum information in these frames.

When Pairing Devices:

- Include the service name.
- Include the NAN Identity Resolution Attribute.
- Include pairing-related fields, such as `pairingName`, `vendorName`, and `modelName`.
- Avoid using additional service-specific information.
- Publishers shall set the `Pairing Setup` subfield in the Device Capability Extension attribute to 1 (enabled) to indicate they are in pairing mode and will accept new pairing attempts.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

When Connecting to already-paired devices:

- Include the service name.
- Include the NAN Identity Resolution Attribute to enable discovery and identification between paired devices.
- Do not include pairing-related fields, such as `pairingName`, `vendorName`, or `modelName`.
- Avoid using additional service-specific information.
- Publishers shall set the `Pairing Setup` subfield in the Device Capability Extension attribute to `0` (disabled) to indicate they are not in pairing mode. In this state, the publisher shall allow connections only from previously paired devices and shall not accept any new pairing attempts.

53.5.2 Frame Identifiers

Certain standard fields in Wi-Fi frames can be used to identify and track users if configured improperly. To mitigate this risk, peer devices shall randomize the following information using a secure random number generator each time Wi-Fi Aware is started:

- **MAC Addresses:** Set all Wi-Fi MAC Addresses (including the NMI Address and NDI Addresses) to new, randomly-generated, locally-administered, unicast MAC addresses.
- **NAN Cluster ID:** Set to a new value randomly chosen from the range `50:6F:9A:01:00:00` to `50:6F:9A:01:FF:FF`.
- **NAN TSF:** Set the lower 56 bits to a new random starting value and the upper 8 bits to `0`.
- **NAN Master Preference** and **NAN Random Factor:** Set to `0` until the warmup period expires or the device joins a NAN Cluster, as described in the Wi-Fi Aware specification.
- **Current & Last NAN Anchor Master Record:** Set all fields to `0`.
- **802.11 Sequence Numbers:** Set to a new random starting value.
- **802.11 Scrambler Seed:** Set to a new, random, non-zero starting value.
- **802.11 Dialogue Tokens:** Set to a new random starting value.
- **802.11 BSS Color:** If supported on the NAN interface, set to a new, random, non-zero value not in use by other nearby networks. Otherwise, this is not applicable.

To save power and further limit tracking risks, the Wi-Fi Aware radio should be turned off when idle for an extended period.

53.6 Improving Quality of Service (QoS)

To accelerate initial synchronization with a device, the peer device should park on the social channel for at least 256 TUs and transmit a beacon every 100 TUs for the first two seconds after powering on.

To maintain presence detection and synchronization status, the peer device should transmit a few beacons every 8 seconds, even when in a non-beaconing Wi-Fi Aware role.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

The standard IPv6 Neighbor Discovery Protocol (NDP) can introduce delays before application data can flow. To eliminate this latency, NDP is not supported on this datapath. Instead, the peer device shall immediately derive the device's IPv6 link-local address from its MAC address and update its network routing table directly. Refer to the *Wi-Fi Aware Specification – Version 4.0, Appendix J* for the conversion method.

The Wi-Fi Aware API provides a performance mode parameter to optimize datapath performance for different use cases. To achieve the best results, the committed availability setting should match between the device and the peer device. The device will choose the 5 GHz band for data transmission if the peer device supports both 2.4 GHz and 5 GHz bands.

There are two performance modes:

1. **Bulk Mode:** Designed for efficient, bursty data transfers while minimizing power consumption.
    a. The radio adapts its availability based on transmit/receive activity.
    b. Committed availability is primarily limited to the social channel.
2. **Realtime Mode:** Intended for latency-sensitive applications at the expense of higher power usage.
    a. The radio maintains high availability for fast packet exchange.
    b. Committed availability spans the social channel, the peer device's Wi-Fi infrastructure channel, and the device's Wi-Fi infrastructure channel.
    c. Potential availability should include the infrastructure channel with a usage preference set to 3 in the NAN Availability attribute, as defined in *Wi-Fi Aware Specification – Version 4.0, Section 9.5.17.1*.
    d. Requires synchronized availability between peers for consistent, low-latency performance. See Figure 53-1 (page 257) for different availability scenarios based on the Wi-Fi infrastructure channel.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 53-1 Availability Cases

		Device A					
		Infra Not Associated	Infra 2.4 GHz e.g. Channel 11	Infra 5GHz (non-DFS) e.g. Channel 36	Infra 5GHz (non-DFS) e.g. Channel 161	Infra 5GHz DFS e.g. Channel 60	Infra 6GHz e.g. Channel 69
Device B	Infra Not Associated	Case 0-0	1-0	0-1	0-1	0-1	0-1
	Infra 2.4 GHz e.g Channel 11	1-0	1-0	1-1	1-1	1-1	1-1
	Infra 5 GHz non-DFS e.g. Channel 36	0-1	1-1	0-1	0-2	0-X	0-2
	Infra 5GHz DFS e.g. Channel 60	0-1	1-1	0-X	0-X	0-1	0-X
	Infra 6GHz e.g. Channel 69	0-1	1-1	0-2	0-2	0-X	0-1

Case 0-0

	512 TUs								512 TUs							
	64 TUs								64 TUs							
	Slot 0	Slot 1	Slot 2	Slot 3	Slot 4	Slot 5	Slot 6	Slot 7	Slot 8	Slot 9	Slot 10	Slot 11	Slot 12	Slot 13	Slot 14	Slot 15
map 0	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6
map 1	149	149	149	149	149	149	149	149	149	149	149	149	149	149	149	149

Case 0-1

	512 TUs								512 TUs							
	64 TUs								64 TUs							
	Slot 0	Slot 1	Slot 2	Slot 3	Slot 4	Slot 5	Slot 6	Slot 7	Slot 8	Slot 9	Slot 10	Slot 11	Slot 12	Slot 13	Slot 14	Slot 15
map 0	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6
map 1	I	I	149	I	I	I	I	I	I	I	149	I	I	I	I	I

Case 1-0

	512 TUs								512 TUs							
	64 TUs								64 TUs							
	Slot 0	Slot 1	Slot 2	Slot 3	Slot 4	Slot 5	Slot 6	Slot 7	Slot 8	Slot 9	Slot 10	Slot 11	Slot 12	Slot 13	Slot 14	Slot 15
map 0	6	I	I	I	I	I	I	I	6	I	I	I	I	I	I	I
map 1	149	149	149	149	149	149	149	149	149	149	149	149	149	149	149	149

Case 0-2

	512 TUs								512 TUs							
	64 TUs								64 TUs							
	Slot 0	Slot 1	Slot 2	Slot 3	Slot 4	Slot 5	Slot 6	Slot 7	Slot 8	Slot 9	Slot 10	Slot 11	Slot 12	Slot 13	Slot 14	Slot 15
map 0	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6
map 1	149	149	149	149	I1	I1	I2	I2	149	149	149	149	I1	I1	I2	I2

Case 1-1

	512 TUs								512 TUs							
	64 TUs								64 TUs							
	Slot 0	Slot 1	Slot 2	Slot 3	Slot 4	Slot 5	Slot 6	Slot 7	Slot 8	Slot 9	Slot 10	Slot 11	Slot 12	Slot 13	Slot 14	Slot 15
map 0	6	I1	I1	I1	I1	I1	I1	I1	6	I1	I1	I1	I1	I1	I1	I1
map 1	I2	I2	149	I2	I2	I2	I2	I2	I2	I2	149	I2	I2	I2	I2	I2

Case 0-X

	512 TUs								512 TUs							
	64 TUs								64 TUs							
	Slot 0	Slot 1	Slot 2	Slot 3	Slot 4	Slot 5	Slot 6	Slot 7	Slot 8	Slot 9	Slot 10	Slot 11	Slot 12	Slot 13	Slot 14	Slot 15
map 0	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6
map 1	149	149	149	149	0	0	0	0	149	149	149	149	0	0	0	0

6	2.4GHz DW
149	5GHz DW
I1	Infra Channel device A
I2	Infra Channel device B

I1 < I2

54. Bluetooth

Accessories integrating Bluetooth technology shall support the *Bluetooth Core Specification – Version 2.1+EDR or later*.

54.1 Enhanced Data Rate

The Enhanced Data Rate (EDR) feature introduced in the *Bluetooth 2.0 Specification* enables accessories to communicate more efficiently. Accessories shall use EDR for the following reasons:

- EDR provides higher data rates compared to Basic Data Rate (BDR).
- EDR communicates more efficiently, transferring more data bits in less time.
- EDR reduces power consumption per bit transferred.
- EDR improves coexistence with Wi-Fi and other Bluetooth accessories by using less airtime.
- EDR improves performance in multipoint configurations.

54.2 Adaptive Frequency Hopping

Adaptive Frequency Hopping (AFH) introduced in the *Bluetooth 1.2 Specification* improves coexistence with Wi-Fi and other connected Bluetooth accessories. Accessories shall use AFH.

54.3 Sniff Mode for Low Power Consumption

Minimizing power consumption is critical for all mobile devices, therefore accessories shall:

- Support and should request Bluetooth sniff mode.
- Accept sniff mode requests and support valid parameters from the Bluetooth specification.
- Support a sniff interval of 15 ms.
- Support sniff subrating.
- Not renegotiate sniff mode after it is established.

Accessories should use sniff mode values of:

- Max Interval: 15 ms
- Min Interval: 15 ms
- Sniff Attempt: 1

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- Sniff Timeout: 0

Accessories compatible with iOS devices and Mac computers should use sniff mode as often as possible, especially when there is little or no data being transmitted over the Bluetooth link. Sniff mode enables better antenna sharing with Wi-Fi, in addition to the power consumption advantages.

Sniff mode parameters are specific to the usage model and Bluetooth profile. Accessories should request sniff mode with appropriate parameters for specific usage models. If the accessory does not send a sniff mode request, the device may send a sniff mode request. When the device sends a sniff mode request, the accessory shall accept the request and parameters without negotiation.

If the accessory requests sniff mode, the accessory shall set the sniff interval to less than a third of the Bluetooth baseband Link Supervision Timeout (page 261), to make the Bluetooth link less susceptible to interference. To improve link robustness, the accessory should use a shorter sniff interval instead of multiple sniff attempts.

Links with a sniff interval of 1 second or more require a large correlation window, which has to be taken into account when calculating the number of sniff attempts. With sniff intervals shorter than 1 second, multiple sniff attempts can improve link robustness, but will increase power consumption.

54.4 Role and Topology Management

Accessories shall:

- Accept device Role Switch requests.
- Continue with the connection when the device rejects a request for Role Switch.

In a Bluetooth connection, there are two entities:

- The Central entity establishes a common clock and frequency hopping synchronization reference.
- The Peripheral entity synchronizes with the Central entity.

The Central entity can be synchronized with multiple Peripheral entities, thus forming a piconet. The Central entity can also be a Peripheral entity to another Central entity, creating a scatternet.

Accessories simultaneously connecting to multiple iOS devices or Mac computers shall support creating a scatternet.

Scatternets create complications since the device has to alternate between piconets, wasting valuable bandwidth. Efficiently managing network topology is important to maximize performance. The device may request a Role Switch, depending on its current topology, and the accessory shall accept the request. The device may also reject a Role Switch request due to topology concerns, as suboptimal topologies may degrade audio quality and the user experience.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Accessories should avoid requesting to be the Central entity, as in more frequently occurring scenarios the device needs to be the Central entity. Accessories insisting on being the Central entity may negatively impact the overall user experience.

54.5 Extended Inquiry Response

Accessories shall provide the following information in their Extended Inquiry Response packet:

- Local Name of the accessory (Complete or Shortened).
- TX Power Level.

During Bluetooth discovery, devices display accessories Friendly Names when available. Extended Inquiry Response enables accessories to proactively send their Local Name, and other information, as part of an Inquiry Response to increase the speed and efficiency of the discovery process.

Accessory Local Name should match the accessory's labeling and packaging without colons ':' or semi-colons ';'. Accessories may append up to six differentiating characters to their Local Name, such as the last few digits of a serial number or MAC address, if users are likely to encounter multiple accessories at the same time using the same name. If the accessory allows a user to customize the Local Name parameter, the accessory should provide a means to restore the factory default name.

54.6 Secure Simple Pairing

Accessories shall:

- Use Secure Simple Pairing.
- Use the Numerical Comparison method, if it has a display and input device supporting it.

Secure Simple Pairing greatly increases security, and is a mandatory security feature in the *Bluetooth 2.1 Specification*. To protect against a 'man-in-the-middle' attack, the Numerical Comparison association model should be used whenever feasible. See *Bluetooth 2.1+EDR Specification – Volume 1, Section 5.4*.

54.7 Pairing Button

If the accessory has a labeled dedicated pairing control, it should use official Bluetooth branding. See https://www.bluetooth.com/develop-with-bluetooth/marketing-branding/.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

54.8 Class of Device (CoD)

iOS devices and Mac computers use the accessory's Class of Device for UI purposes or to configure specific features. Accessories shall accurately set their Class of Device using the Bluetooth SIG defined Major Device Class and Minor Device Class. See *Bluetooth 5.0 Specification – Volume 3, Part C, Section 3.2.4*. For example, an audio/video accessory intended to operate in a vehicle should set Major Device Class to 'audio/video' and Minor Device Class to 'car-audio'.

54.9 Link Supervision Timeout

Link supervision timeout is used to detect link loss between an accessory and a device. An accessory shall set the link supervision timeout to 2 seconds or greater when it is the Central entity, to account for the unpredictable nature of RF signals, as well as the device's need to service other concurrent wireless systems.

54.10 Delay Reporting

As of iOS 8.2, devices support Delay Reporting commands as specified in the Bluetooth *Audio/Video Distribution Transport Protocol – Version 1.3*. Accessories should provide this information to improve audio/video synchronization for video playback. Accessories should not report a delay of more than 1000 ms, and should not update the delay more than 1 time per second.

54.11 Profiles

The Apple Bluetooth profiles knowledge base article https://support.apple.com/kb/ht3647 provides a complete list of the profiles supported by devices. Bluetooth specifications are the starting point for designing accessories compatible with these devices. The following sections provide additional information and requirements for common profiles to help accessory developers achieve superior results.

54.11.1 Device ID Profile (DID)

Accessories shall:

- Support Bluetooth Device ID Profile, Version 1.3 or later.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- Use their Company Identifier from the Assigned Numbers specification assigned by the Bluetooth SIG as the Vendor ID value (VID), see https://www.bluetooth.com/specifications/assigned-numbers/. Bluetooth HID Profile accessories may use a VID assigned by the USB Implementers Forum (USB-IF), see https://www.usb.org/getting-vendor-id, if the manufacturer does not have a Bluetooth SIG Company Identifier.
- Use its VID value for the end product manufacturer.
- Not use the Company ID assigned to Apple by the Bluetooth SIG, or the Vendor ID assigned to Apple by the USB Implementers Forum.
- Use the Vendor ID Source field to identify which organization assigned the value used in the Vendor ID field. See *Bluetooth Device ID Profile Specification – Section 5.6*.
- Use a ProductID value uniquely identifying the product.
- Use a Version value uniquely identifying the software version.

The Device ID record enables devices to identify the implementation of the accessory, which is used to bridge alternate interpretations of the Bluetooth specification when communicating with an accessory. It is important the information in the Device ID record uniquely identify the implementation in use.

In the case of Bluetooth car kit devices, the same car kit may be present in different car models. Ideally, the two car kits should have different ProductIDs. However, it is acceptable for them to have the same ProductID as long as they have identical hardware, software, and features. If the implementations differ at all, they should have different ProductIDs. The accessory can also use a secondary Device ID record to uniquely identify the product ID, or model number.

54.11.2 Service Discovery Protocol (SDP)

To facilitate caching Service Discovery Protocol service records, accessories shall:

- Support the ServiceDiscoveryServer Service Class.
- Support the ServiceDatabaseState attribute.
  - Attribute's value shall change whenever any SDP service record or attributes within a record are added, removed, or modified.
  - Attribute's value shall not change based on RFCOMM channel protocol parameters. Devices query these values separately at connection time.

54.11.3 Hands-Free Profile (HFP)

Accessories supporting Hands-Free Profile should meet the requirements of the *Bluetooth Hands-Free Profile Specification – Version 1.5 or later*.

Accessories can use the Bluetooth Hands-Free Profile for telephony. To achieve the best user experience, the accessory should support the following features, which are optional in the Bluetooth specification.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

54.11.3.1 Remote Audio Volume Control

Accessories supporting HFP should:

- Support Remote Audio Volume Control, so speaker volume on the hands-free accessory can be controlled from the device as described in *Bluetooth Hands-Free Profile Specification – Version 1.5, Section 4.28*.
- Set the Remote Volume Control bit in the Supported Features bitmap sent with the `AT+BRSF=` command.

In some situations it is easier for the user to control the output volume through the device, instead of directly on the accessory. For example, a car passenger (or if the car is parked, the driver) could use the volume slider on the phone to control audio volume. Volume control synchronization is outlined in *Bluetooth Hands-Free Profile Specification – Version 1.5, Section 4.48.2*.

54.11.3.2 Indicator Event Reporting

Accessories supporting HFP should use Indicator Event Reporting, and not perform repetitive status polling.

iOS devices and Mac computers support all mandatory and optional indicators specified in HFP version 1.5 (`service`, `call`, `callsetup`, `callheld`, `signal`, `roam`, `battchg`). To minimize unnecessary status polling using the `AT+CIND?` command, the accessory should enable Indicator Event Reporting by sending an `AT+CMER` command. The device will then send a `+CIEV` event when there is a status change. The accessory should request initial status using the `AT+CIND=?` and `AT+CIND?` commands, according to the HFP specification.

54.11.3.3 Voice Recognition Activation

Accessories supporting HFP shall:

- Support Voice Recognition Activation, both Audio Gateway (AG) and Hands-Free (HF), initiated as described in *Bluetooth Hands-Free Profile Specification – Version 1.5, Section 4.25*.
- Set the Voice Recognition Activation bit in the Supported Features bitmap sent with the `AT+BRSF=` command.

iOS devices and Mac computers support voice recognition initiated by accessories (Hands-Free), and devices (Audio Gateway).

54.11.3.4 Echo Cancellation and Noise Reduction

When echo cancellation and noise reduction are performed locally on a hands-free accessory, the accessory should disable echo cancellation and noise reduction on the device by sending an `AT+NREC` command, as described in *Bluetooth Hands-Free Profile Specification – Version 1.5, Section 4.24*.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

iOS devices and Mac computers support echo cancellation and noise reduction by default. If a hands-free accessory performs echo cancellation and noise reduction, the accessory needs to turn these features off on the device (the Audio Gateway), to avoid unnecessary audio quality degradation due to duplicate audio processing.

54.11.3.5 In-Band Ringing

Accessories supporting HFP should also support In-Band Ringing as specified in *Bluetooth Hands-Free Profile Specification – Version 1.5, Section 4.13.1*. If the user sets a ring tone on the device, the same ring tone should sound on the hands-free accessory.

54.11.3.6 Synchronous Connection

Accessories supporting HFP shall:

- Support eSCO parameter set S2 and S3 and accept requests for these settings. See *Bluetooth Hands-Free Profile Specification – Version 1.5, Section 5.6*.
- Request eSCO parameter set S2 or S3 when setting up a Synchronous Connection. eSCO parameter set S1 should not be requested.
- Render audio within 40 ms after the SCO/eSCO connection has been set up.

eSCO packet types offer packet retransmission, whereas traditional SCO packets are not retransmitted. This improves audio quality and the user experience. eSCO packet types 2-EV3 and 3-EV3 offer a greater time interval between packets, which can improve Wi-Fi performance and allow time for other concurrent Bluetooth connections to send data.

Apple strongly recommends the use of 2-EV3 and 3-EV3 packets for SCO connections. Using HV3 packets is highly discouraged. HV3 packets require more link time and do not allow audio packet retransmission, which impacts audio performance in the presence of RF interference.

54.11.3.7 Wide Band Speech

Accessories supporting HFP should support Wide Band Speech as described in the *Bluetooth Hands-Free Profile Specification – Version 1.6, Section 5.7.4*. If Wide Band Speech is supported, the accessory should support the T2 link parameter settings.

Devices running iOS 5 or later support Wide Band Speech. If both the device and the accessory support Wide Band Speech, the device will use it for eSCO connection scenarios such as cellular calls, FaceTime, and Siri.

54.11.4 Message Access Profile (MAP)

Accessories supporting Message Access Profile shall:

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- Support Message Notification, as described in *Bluetooth Message Access Profile Specification –Version 1.1, Section 4.1*
- Register for notifications immediately after the connection is established, as described in *Message Access Profile Specification –Version 1.1, Section 4.5*.

Devices running iOS 13.0 or later support MAP 1.1.

54.11.5 Audio/Video Remote Control Profile (AVRCP)

Accessories supporting Audio/Video Remote Control Profile should meet the requirements of the *Bluetooth Audio/Video Remote Control Profile Specification –Version 1.4*.

54.11.5.1 Supported Operations

iOS devices and Mac computers support the following operation_IDs in passthrough commands:

- Play
- Stop
- Pause
- Fast Forward
- Rewind
- Forward
- Backward

54.11.5.2 Repeat and Shuffle Modes

Every device in the role of an AVRCP target supports Repeat and Shuffle modes. An AVRCP controller may use `SetPlayerApplicationSettingValue` to set a value on the device and `GetPlayerApplicationSettingValue` to read a value, as described in *Bluetooth Audio/Video Remote Control Profile Specification –Version 1.4, Sections 6.5.4 and 6.4.3*.

54.11.5.3 Notifications

Accessories supporting AVRCP shall:

- Register for notifications.
- Not perform repetitive device status polling.

Every device in the role of an AVRCP Target supports registering for notifications, as described in *Bluetooth Audio/Video Remote Control Profile Specification –Version 1.4, Section 6.7*. The commands `RegisterNotification` and `GetPlayStatus` are supported for these notifications:

- EVENT_PLAYBACK_STATUS_CHANGED
- EVENT_TRACK_CHANGED
- EVENT_NOW_PLAYING_CONTENT_CHANGED

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- EVENT_AVAILABLE_PLAYERS_CHANGED
- EVENT_ADDRESSED_PLAYER_CHANGED
- EVENT_VOLUME_CHANGED

54.11.5.4 Play/Pause Button

Accessories supporting AVRCP implementing a Play/Pause control surface shall confirm the playback status of the device using AVRCP Notifications (page 265), before sending a Play or Pause command. See Supported Operations (page 265). Specifically:

- If a device notifies the accessory it is paused, pressing the accessory's Play/Pause control surface should send a Play command.
- If a device notifies the accessory it is playing, pressing the accessory's Play/Pause control surface should send a Pause command.
- The accessory should not infer device playback status based on the number of times the Play/Pause control surface has been pressed.

54.11.5.5 Volume Handling

Accessories supporting AVRCP should support Absolute Volume, as described in *Bluetooth Audio/Video Remote Control Profile Specification – Version 1.4, Section 6.13*.

Every device in the role of AVRCP Controller supports volume handling.

54.11.5.6 Browsing

Accessories supporting Browsing (in controller role) as part of AVRCP shall:

- Not try to index or cache the entire library upon connection. The device may contain tens of thousands of media items, and each may be present multiple times in the hierarchy.
- Not fetch all items when browsing a folder; only fetch items displayed to the user. The accessory may prefetch a few items to improve the responsiveness of the user interface.
- Not reorder items (for example, alphabetically).
- Not assume UIDs to be statically defined, especially in the root folder. The ordering and UIDs of folders and items may change at any point in future releases.
- Send the `SetBrowsedPlayer` command after receiving an EVENT_UIDS_CHANGED notification.
- Not assume the UID passed to the `PlayItem` command will result in the media player playing the UID.

Currently only the built-in Music app supports browsing. When switching between players, an EVENT_AVAILABLE_PLAYERS_CHANGED notification, and an EVENT_ADDRESSED_PLAYER_CHANGED notification will be generated. The UI needs to look at the feature bit mask of the listed player to determine whether browsing is currently available.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Devices running iOS 6.0 or later support AVRCP Browsing.

54.11.5.7 iOS App-Provided Metadata

An audio app running on a device may use the iOS Media Player Framework to provide metadata about the current audio stream to the accessory using AVRCP. Requirements and usage for these messages may be found in the `MPNowPlayingInfoCenter` class in Apple Media Player Framework documentation.

54.11.6 Advanced Audio Distribution Profile (A2DP)

See Advanced Audio Distribution Profile (A2DP) (page 242).

54.12 Audio Routing

Accessories can differentiate between various audio content provided by a device, and determine playback behavior.

An accessory can receive audio data from the device using either of two Bluetooth profiles:

- HFP using eSCO channel.
- A2DP using ACL channel.

The device determines which channel to use, depending on how the audio content is used. An audio path created for two-way communication (for example, phone calls or FaceTime) always uses the HFP (eSCO) route for sending audio data. Music and similar content uses the A2DP channel route. In the absence of a defined route, audio playback defaults to the device.

54.12.1 Audio Data Received using HFP Profile

Most of the audio content sent using HFP (eSCO) route requires two-way communication. Scenarios where HFP (eSCO) is used include, but are not limited to: cellular calls, FaceTime, and voice mail.

The accessory speaker and microphone should be dedicated to the HFP (eSCO) route, and not mixed/muxed with any other audio sources.

54.12.2 Audio Data Received using A2DP Profile

Audio content transferred using A2DP profiles can be broadly classified into two categories:

- Audio content from music, video, or game-like applications.
- System-generated sounds used for alerts and notifications.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

54.12.2.1 Differentiating Audio Content from System Sounds

Music-like content can be differentiated from system sounds by adding support for Audio/Video Remote Control Profile (AVRCP) version 1.3 or later. The AVRCP profile allows an accessory to be aware of the audio playback device state, using notifications. See Audio/Video Remote Control Profile (AVRCP) (page 265).

When a device initiates audio playback over an A2DP channel for playing music content, an AVRCP notification EVENT_PLAYBACK_STATUS_CHANGED is sent to indicate playback status has changed to the play state. See *Bluetooth Audio/Video Remote Control Profile Specification–Version 1.4, Section 6.7.2*. This indicates audio data using the A2DP profile contains music. When a device initiates audio playback over an A2DP channel for playing system sounds, no AVRCP notifications are sent.

Figure 54-1 (page 268) and Figure 54-2 (page 269) show the difference between notifications for music playback, and system sounds.

Figure 54-1 Initiate Audio Playback (for example, music)



2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 54-2 Initiate System Sound (such as turn-by-turn directions)



54.12.2.2 Expected Audio Routing Behavior for A2DP

The accessory should tune its audio routing behavior based on audio content over the A2DP channel.

If audio data contains music, accessory speakers are expected to be dedicated to audio data using the Bluetooth link, and any other audio playback is paused. If audio data contains system sounds, it is expected the accessory can render audio as desired. If the accessory is playing audio from a different source, it is not necessary to pause existing audio playback on the device, and system sound data can be mixed with the existing track for playback.

54.13 HID

When implementing HID over Bluetooth, the accessory should:

- Support Bluetooth HID Profile 1.1.
- Support Sniff Mode for Low Power Consumption (page 258).

The accessory should:

- Use the following parameters in SDP for sniff subrating:
  - HIDSSRHostMaxLatency - 450 ms (720 slots)
  - HIDSSRHostMinTimeout - 45 ms (72 slots)
- Use a typical report packet of 22 bytes or less. This is small enough to fit into a DH1 packet with L2CAP and HID header.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

55. Bluetooth Low Energy (BLE)

Accessories integrating Bluetooth Low Energy (BLE) technology shall support the *Bluetooth 4.0 Specification* or later.

55.1 Role

The accessory should implement either the Peripheral role or the Broadcaster role as defined in the *Bluetooth 4.0 Specification – Volume 3, Part C, Section 2.2.2.3 and Section 2.2.2.1*.

55.2 Advertising Channels

The accessory should advertise on all three advertising channels (37, 38, and 39) at each advertising event. See the *Bluetooth 4.0 Specification – Volume 6, Part B, Section 4.4.2.1*.

55.3 Advertising PDU

The accessory should use one of the following advertising PDUs:

- ADV_IND
- ADV_NOCONN_IND
- ADV_SCAN_IND

ADV_DIRECT_IND should not be used. See the *Bluetooth 4.0 Specification – Volume 6, Part B, Section 2.3.1*.

55.4 Advertising Data

The advertising data sent by the accessory should contain at least the following information as described in the *Bluetooth Core Specification Supplement – Part A*:

- Flags
- TX Power Level
- Local Name

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- Services

The Local Name should match the accessory's markings and packaging and not contain a colon ':' or semi-colon ';'.

The accessory may put the Local Name and the TX Power Level data in the SCAN_RSP PDU if, for example, it needs to reduce power consumption or not all of the advertising data fit into the advertising PDU. Depending on its state, the device may not always perform active scanning.

The primary services should always be advertised in the advertising PDU. Secondary services should not be advertised. Services not significant to the primary use case of the accessory may be omitted if space is limited in the Advertising PDU.

The advertising data and the scan response data in the SCAN_RSP PDU should comply with the formatting guidelines in the *Bluetooth 4.0 Specification – Volume 3, Part C, Section 18*: it starts with a length field, followed by AD Type and AD Data.

55.5 Advertising Interval

The accessory should first use the recommended advertising interval of 20 ms for at least 30 seconds.

If it is not discovered within the initial 30 seconds, Apple recommends using one of the following longer intervals to increase chances of discovery by the device:

- 152.5 ms
- 211.25 ms
- 318.75 ms
- 417.5 ms
- 546.25 ms
- 760 ms
- 852.5 ms
- 1022.5 ms
- 1285 ms

> **Note:**
> Longer advertising intervals usually result in longer discovery and connect times, but may lower accessory power consumption.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

55.6 Connection Parameters

If both the Central and Peripheral support the Connection Parameters Request procedure, then either shall use the procedure. The device will not read or use the parameters in the Peripheral Preferred Connection Parameters characteristic. See *Bluetooth 5.3 Specification – Volume 6, Part B, Section 5.1.1 Connection Update*.

Connection parameter requests may be rejected if they do not meet these guidelines.

General connection parameter request guidelines:

- Peripheral Latency ≤ 30 connection intervals.
- Supervision Timeout from 6 seconds to 18 seconds.
- Interval Min ≥ 15 ms.
- Interval Min ≤ 2 seconds.
- Interval Min is a multiple of 15 ms.
- One of the following:
  - Interval Max at least 15 ms greater than Interval Min.
  - Interval Max and Interval Min are both 15 ms.
- Interval Max * (Peripheral Latency + 1) of 6 seconds or less.
- Supervision Timeout greater than Interval Max * (Peripheral Latency + 1) * 3.

If Bluetooth Low Energy HID is one of the connected services of an accessory, a connection interval down to 11.25 ms may be accepted by some devices.

> **Note:**
> When Interval Max and Interval Min are both 15 ms, some devices (such as Apple Watch) will offer a 30 ms interval to better balance power and performance constraints.

Apple Watch connection parameter request guidelines:

- Interval Min ≥ 30 ms.
- Interval Min is a multiple of 30 ms.
- One of the following:
  - Interval Max at least 30 ms greater than Interval Min.
  - Interval Max and Interval Min are both 30 ms.

55.7 Data Packet Length Extension

Data Packet Length Extension increases the maximum data length from 27 to 251. Using larger per-packet data lengths improves radio efficiency, greatly increasing application data rates and boosting battery life. See *Bluetooth 5.0 Specification – Volume 6, Part B, Section 4.6.6*.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 55-1 Data Packet Length Extension



Accessories should support Data Packet Length Extension for best performance with devices.

iOS devices and Mac computers operating as the Central will negotiate optimal data packet lengths based on various factors, such as connection event length, system topology, and protocol.

55.8 Privacy

The accessory should be able to resolve a Resolvable Private Address in all situations. Due to privacy concerns, the device will use a Random Device Address as defined in the *Bluetooth 4.0 Specification –Volume 3, Part C, Section 10.8*.

55.9 Permissions

The accessory should not require special permissions, such as pairing, authentication, or encryption to discover services and characteristics. It may require special permissions only for access to a characteristic value or a descriptor value. See the *Bluetooth 4.0 Specification –Volume 3, Part G, Section 8.1*, fifth paragraph.

55.10 Pairing

The accessory should not request pairing until an ATT request is rejected using the Insufficient Authentication error code. See *Bluetooth 4.0 Specification –Volume 3, Part F, Section 4*.

If, for security reasons, the accessory requires a bonded relationship with the Central, the Peripheral should reject the ATT request using the Insufficient Authentication error code, as appropriate. As a result, the device may proceed with the necessary security procedures.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Similarly, if the device acts as a Central and a GATT server, it may reject an ATT request using the Insufficient Authentication error code. The accessory should initiate the security procedure for pairing in response.

Pairing may require user authorization depending on device. Once an accessory is paired with a device, the accessory shall retain the distributed keys of both central and peripheral for future use. If the pairing is no longer required, the accessory shall delete both sets of keys.

55.11 MTU Size

An accessory supporting packet length extension shall perform the packet length update procedure before performing the Exchange MTU Request handshake, see Data Packet Length Extension (page 272).

Devices will support and request an MTU size larger than the default during the Exchange MTU Request handshake. See the *Bluetooth 4.0 Specification –Volume 3, Part F, Section 3.2.8*.

When operating as ATT client, the device will request the optimal MTU size based on factors such as the Bluetooth topology, connection event length, maximum data length, and protocol (GATT or connection-oriented L2CAP).

An accessory operating as ATT server should select an MTU equal to or greater than the device's MTU request.

55.12 Services

55.12.1 Generic Access Profile Service

The accessory should implement the Device Name characteristic per the *Bluetooth 4.0 Specification –Volume 3, Part C, Section 12.1*. The Device Name characteristic should be writeable.

55.12.2 Generic Attribute Profile Service

The accessory shall implement the Service Changed characteristic only if the accessory has the ability to change its services during its lifetime.

The device may use the Service Changed characteristic to determine if it can rely on previously read (cached) information from the device. See the *Bluetooth 4.0 Specification –Volume 3, Part G, Section 7.1*.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

55.12.3 Device Information Service

The accessory shall implement the Device Information Service. The service UUID for this service should not be advertised in the Advertising Data. The following characteristics should be supported:

- Manufacturer Name String (26 characters maximum).
- Model Number String (26 characters maximum).
- Firmware Revision String
- Software Revision String

55.12.4 Available Services

With iOS 7.0, any device makes Battery Service, Current Time Service and Apple Notification Center Service (ANCS) available to an accessory. The Current Time Service supports the current time and local time information characteristics. The service does not provide an "Adjust Reason" when the current time changes. ANCS uses `7905F431-B5CE-4E99-A40F-4B1E122D00D0` as its UUID.

These services are not guaranteed to be available immediately after connection and the accessory shall support Characteristic Value Indication of the Service Changed characteristic (see *Bluetooth 4.0 Specification – Volume 3, Part G, Section 7.1*) to be notified when the services become available. The device will maintain a connection to an accessory as long as it is paired and uses one of the available services.

55.13 GATT Server

With iOS 6.0, applications may contribute services and characteristics to the GATT server the device makes available to the accessory.

The following services are implemented internally by iOS and shall not be published by third-party iOS applications:

- Generic Attribute Profile Service
- Generic Access Profile Service
- Bluetooth Low Energy HID Service
- Battery Service
- Current Time Service
- Apple Notification Center Service

The device implements the GAP Service Changed characteristic, because the database contents can change at any time. The accessory should therefore support the Characteristic Value Indication of this characteristic and, upon receiving indications, invalidate its database cache accordingly. See the *Bluetooth 4.0 Specification – Volume 3, Part G, Section 7.1*.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

The accessory should minimize the use of ATT/GATT requests and commands and only send what is necessary. For example, do not use GATT Discover All Services when the accessory is looking for specific services. Use Discover Primary Service By Service UUID instead. Less airtime equals less power consumption and better performance for both the accessory and the device.

When third-party iOS applications discover services on the accessory, the following services are used internally by iOS and are filtered out from the list of discovered services:

- Generic Attribute Profile Service
- Generic Access Profile Service
- Bluetooth Low Energy HID Service
- Apple Notification Center Service

The accessory should be robust enough to handle any error gracefully. Pairing and Characteristic Value reads/writes may fail if the application owning the service is not in the foreground and is not entitled to run in the background.

If an ATT Prepare Write Request is used, all queued attributes are contained within the same GATT Service.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Modules

56. Apple USB-C Analog Headset Module

The Apple USB-C Analog Headset Module (C125) may be used to create USB-IF compliant Headsets (page 97) supporting up to 24-bit/384 kHz stereo and up to 24-bit/48 kHz mono (microphone) audio. C125 supports Apple Music Lossless and Hi-Res Lossless.

Figure 56-1 USB-C Analog Headset Module (C125)



56.1 Overview

C125 is a USB-IF compliant USB Audio Device Class 2.0 and 3.0 codec with an integrated USB-IF certified USB-C plug (Test ID: 11559).

C125 supports:

- 16-bit and 24-bit samples.
- 44.1 kHz, 48 kHz, 88.2 kHz, 96 kHz stereo headphone-level output.
- Optional:
  - 176.4 kHz, 192 kHz, 384 kHz stereo headphone-level output.
  - 7-band output EQ.
- 44.1 kHz, 48 kHz mono microphone input.
- Optional:
  - 7-band microphone input EQ.
  - 3-band sidetone EQ.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- Volume Up, Volume Down, and Center buttons.

C125 does not support USB-C to 3.5 mm headset jack adapters.

56.1.1 Additional Specifications & Support

Additional software and support for C125 is available from Cirrus Logic, Inc.

Get started at https://www.cirrus.com/support/c125.

56.1.2 Procurement

The C125 is available at https://c125.proscalnext.com/:

Variant	Part Number
C125	AB23169-1A033-AH

56.2 Mechanical

C125 has the following mechanical characteristics:

- Integrated USB-C connector.
- Not encapsulated.
- -20 °C to 65 °C working temperature range.

See C125 Dimensions (page 283) for dimensional drawing.

C125 headsets shall:

- Meet the requirements for USB-C connector integration, see Mechanical (page 310).
- Encapsulate both sides of C125.

56.2.1 Shielding

C125 headsets shall:

- Protect the C125 electronic components with a SUS shield.
- Laser weld the SUS shield to the C125 ground ring.

Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 56-2 C125 recommended three-part shield design



Apple recommends the following three-part shield design as shown in Figure 56-2 (page 280) for C125:

- C125 Recommended Clamshell Shields (page 284)
- C125 Recommended Rear Shield (page 285)

56.3 Pad Assignments

Figure 56-3 (page 280) and Table 56-1 (page 281) detail the layout, names, description, and assignments of the C125 pads.

Figure 56-3 C125 pads



Table 56-1 C125 pad assignments

Pad	Name	Assignments
1	Left Driver	Left Driver
2	Microphone Bias	Microphone Bias
3	Reserved	NC
4	Ground	Right Return, Left Return, Microphone Return
5	Right Driver	Right Driver

56.4 Electrical

C125 headsets shall incorporate the Headset Remote and Microphone Transmitter (page 287) using Tone Mode (page 301).

The C125 shield may be treated as an electrical ground.

56.4.1 DAC Characteristics

The C125 DAC receives lossless 24-bit stereo audio from the device.

Table 56-2 C125 DAC characteristics, 24-bit/96 kHz mode

Driver	Parameter	Typical
32 Ω, 1 nF	Dynamic range (A-weighted)	117 dB
	THD+N (FS = 48 kHz, BW = 20 kHz)	-91 dB
	Full-scale output voltage	2.4 V_{PP}
	Output power	22.6 mW
16 Ω, 1 nF	Dynamic range (A-weighted)	112 dB
	THD+N (FS = 48 kHz, BW = 20 kHz)	-83 dB
	Full-scale output voltage	1.3 V_{PP}
	Output power	14.2 mW

Table 56-3 C125 DAC characteristics, 24-bit/384 kHz mode

Driver	Parameter	Typical
32 Ω, 500 pF	Dynamic range (A-weighted)	117 dB

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Driver	Parameter	Typical
	THD+N (FS = 48 kHz, BW = 20 kHz)	-91 dB
	THD+N (FS = 192 kHz, BW = 80 kHz)	-90 dB
	Full-scale output voltage	2.4 V_{PP}
	Output power	22.6 mW
16 Ω, 500 pF	Dynamic range (A-weighted)	112 dB
	THD+N (FS = 48 kHz, BW = 20 kHz)	-84 dB
	THD+N (FS = 192 kHz, BW = 80 kHz)	-83 dB
	Full-scale output voltage	1.3 V_{PP}
	Output power	14.2 mW

The characteristics in Table 56-2 (page 281) and Table 56-3 (page 281) were measured under the following conditions:

- Left Driver, Right Driver, and Ground pads on C125 connected to a load and an audio analyzer, such as the Audio Precision APx series.
- Microphone Bias pad connected to the Ground pad.
- Full-scale 1 kHz sine wave input test signal.

Copyright © 2025 Apple Inc. All Rights Reserved.

56.5 C125 Dimensions



56.6 C125 Recommended Clamshell Shields

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. ALL DIMENSIONS AND TOLERANCES APPLY PER ASME Y14.5M, 1994. IT IS EXPECTED THAT THE SUPPLIER UNDERSTAND AND COMPLY WITH ALL TOLERANCES AS DESCRIBED IN THIS STANDARD AND APPLIED TO THIS DRAWING.
2. DIMENSIONS ARE MEASURED AFTER PLATING.
3. ALL DIMENSIONS THAT LOCATE GEOMETRICAL TOLERANCE FEATURES (PROFILE AND POSITION CHARACTERISTICS) ARE CONSIDERED BASIC AS DEFINED IN THE ASME Y14.5M, 1994 STANDARD.
4. WHEN DATUMS ARE SPECIFIED ON A DRAWING, DIMENSIONS ARE RELATED TO DATUM A (AS THE PRIMARY DATUM), DATUM B (SECONDARY), AND DATUM C (TERTIARY).
5. PERFECT ORIENTATION AND/OR PERFECT LOCATION AT MMC REQUIRED FOR THE INTERRELATIONSHIP OF ALL DATUM FEATURES OF SIZE, UNLESS OTHERWISE SPECIFIED ON DRAWING.
6. UNLESS OTHERWISE SPECIFIED, ALL SURFACES TO BE WITHIN A SURFACE PROFILE TOLERANCE OF ⌓ 0.1 A B C.
7. ALL BURRS TO BE LESS THAN 0.02 mm.
8. BREAK ALL EDGES 0.05 mm R UNLESS SPECIFIED.
9. PART NEEDS TO SURVIVE 8HR SALT SPRAY TEST.
10. MATERIAL: SUS304-1/2H, 0.25mm THK
11. FINISH: 2-5 μm NICKEL PLATING PER AMS QQ-N-290
12. ALL PLATING TO OCCUR AFTER PART STAMPING AND FORMING

13 BURRS SHALL BE SUBFLUSH TO DATUM A





METRIC	Apple Inc.
DRAWN / DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER / DATE	
DIMENSIONS ARE IN MILLIMETERS TOLERANCES	TITLE
DRAWING NUMBER / REV.	
DO NOT SCALE DRAWINGS	
THIRD ANGLE PROJECTION / SIZE D / SCALE NONE / SHT 1 OF 1	

NX GENERATED

Copyright © 2025 Apple Inc. All Rights Reserved.

56.7 C125 Recommended Rear Shield



Components

57. Headset Remote and Microphone Transmitter

Devices can receive button presses from Headsets (page 97) incorporating a Headset Remote and Microphone Transmitter using the Apple USB-C Analog Headset Module (page 278).

A Headset Remote and Microphone Transmitter conveys Volume Up, Volume Down, and Center button controls over the microphone bias signal.

57.1 Overview

The Headset Remote and Microphone Transmitter is available from Texas Instruments:

Variant	Part Number
Noise-occluding, for headsets blocking or canceling outside sound. See https://www.ti.com/product/CD3268A.	TI CD3268A0YZPR
Non-occluding, for standard headsets. See https://www.ti.com/product/CD3269A.	TI CD3269A0YZPR

Subjective listening tests with the latest devices are recommended to determine which part produces the best user experience.

57.2 Requirements

Headsets and headset cables implementing the Headset Remote and Microphone Transmitter shall:

- Locate the microphone 120-160 mm from the center of a headset driver when worn by the user.
- Have three physical remote buttons for Volume Up, Volume Down, and Center button functions.
- Use six wires from the plug corresponding to the following signals:
  - Right Driver
  - Right Return
  - Left Driver
  - Left Return
  - Microphone Bias
  - Microphone Return
- Run signals separately to their respective components.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Headsets and headset cables integrating the Headset Remote and Microphone Transmitter shall integrate a MEMS analog microphone.

Headset drivers shall have:

- Minimum load impedance of 16 Ω.
- Maximum load capacitance of 150 pF.

Headsets and headset cables shall implement one of the following configurations. The microphone and remote buttons may be located on either the left or right side of the headset.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 57-1 Headset plug, single detachable cable



Figure 57-2 Headset plug, single built-in cable



Figure 57-3 Headset plug, split detachable cable



Figure 57-4 Headset plug, split built-in cable



Figure 57-5 USB-C Analog Headset Module (C125), single detachable cable



2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 57-6 USB-C Analog Headset Module (C125), single built-in cable



2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 57-7 USB-C Analog Headset Module (C125), split detachable cable



Figure 57-8 USB-C Analog Headset Module (C125), split built-in cable



57.3 Usage

The transmitter operates with a receiver in C125 to enable remote button press detection using the microphone bias line. The C125 provides regulated downstream power (nominally 2.7 V or 2.0 V) to the transmitter and MEMS microphone through the microphone bias line, and the C125 decodes the button information from the transmitter.

The transmitter sends button press state over the microphone bias line in either:

- Button mode.
- Tone mode.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

If the voltage on the microphone bias line is less than 2.35 V, the microphone is not in use. The transmitter enters button mode and sends button-press information as discrete voltage levels.

If the voltage on the microphone bias line greater than 2.35 V, the microphone is in use. The transmitter enters tone mode and sends button-press information as ultrasonic tone sequences in the range of 99 kHz to 300 kHz.

57.3.1 Pin Assignments

Table 57-1 Headset Remote and Microphone Transmitter pin assignments

Name	I/O	Description
TONE	Output	Tone generator output
GND	Power	Audio return
MIC	Input	Microphone bias
REM	Input/output	Remote switch network
VSHUNT	Input	Shunt regulator supply
MICPWR	Output	Microphone power

57.3.2 Maximum Voltage and Current Ratings

Table 57-2 (page 297) lists the transmitter's maximum voltage and current ratings while operating over a free-air temperature range (T_A) of -40 °C to +85 °C.

Voltages are measured with respect to ground. Input and output clamp-current ratings shall be observed.

Table 57-2 Maximum voltage and current ratings

Symbol	Description	Minimum	Maximum
V_{SUPPLY}	Supply voltage, VSHUNT, MIC	-0.5 V	4.6 V
V_I	Input voltage, REM	-0.5 V	4.6 V
V_O	Output voltage, MICPWR, TONE	-0.5 V	4.6 V
I_{IK}	Input clamp current, REM (V_I < 0)	-20 mA	
I_{OK}	Output clamp current, MICPWR, TONE (V_O < 0)	-20 mA	
I_{SUPPLY}, I_{GND}	Continuous current through VSHUNT, MIC, or GND	-50 mA	50 mA

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

57.3.3 Electrical Characteristics

Table 57-3 (page 298), Table 57-4 (page 299), and Table 57-5 (page 299) list the transmitter's electrical and timing characteristics under the following conditions:

- Operating temperature = -40 °C to +85 °C.
- MIC is connected to $V_{MICBIAS}$ through a 2.21 kΩ ±1% resistor.
- Button mode, $V_{MICBIAS}$ = 1.8 to 2.1 V.
- Tone mode, $V_{MICBIAS}$ = 2.56 to 2.84 V.

The values in the Typical column of the tables are measured at 25 °C.

Table 57-3 Electrical characteristics (general)

Symbol	Parameter	Test Conditions	Minimum	Typical	Maximum
$I_{MICBIAS-B}$	Quiescent current into MIC+VSHUNT	Button mode, $V_{MICBIAS}$ = 2.1 V		3 µA	6 µA
$I_{MICBIAS-B}$	Quiescent current into MIC+VSHUNT	Button mode, $V_{MICBIAS}$ = 1.5 V		3 µA	6 µA
I_{MIC-T}	Quiescent current into MIC	Tone mode		34 µA	46 µA
$I_{VSHUNT-T}$	Quiescent current into VSHUNT	Tone mode (see note below)		60 µA	70 µA
I_{MIC-TA}	Active current into MIC	Tone mode		35 µA	45 µA
$I_{VSHUNT-TA}$	Active current into VSHUNT	(see note below)		104 µA	118 µA
V_{TR}	Tone mode threshold voltage	MIC rising (Microphone enable), V_{MICPWR} = 1.0 V	2.20 V	2.35 V	2.50 V
V_{TF}	Tone mode threshold voltage	MIC falling (Microphone disable), V_{MICPWR} = 400 mV	0.55 V	0.8 V	1 V
V_{MICPWR}	MICPWR output voltage	I_{MICPWR} = 120 - 150 µA	1.51 V	1.56 V	1.61 V
R_{SO}	Shunt regulator output impedance	Freq = 100 Hz	5 Ω	18 Ω	25 Ω
R_{SO}	Shunt regulator output impedance	Freq = 20 Hz	12 Ω	21 Ω	35 Ω
R_{ONA}	Switch A, R_{DSON}	Tone mode, I_{MICPWR} = 1 mA, $V_{MICBIAS}$ = 2.56 V		40 Ω	55 Ω
R_{ONB}	Switch B, R_{DSON}	V_{MIC} = 1.2 V, I_{REM} = 1 mA		22 Ω	30.5 Ω

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Note:
This current is pulled through R_{VSHUNT} between MIC and VSHUNT and is the minimum current to keep VSHUNT regulated at 1.56 V. Excess current through R_{VSHUNT} is available to the load at MICPWR. Excess current not used by the load at MICPWR is internally shunted to GND.

Table 57-4 Electrical characteristics (tone mode)

Symbol	Parameter	Test Conditions	Minimum	Typical	Maximum
$e_{n\text{-}mic100}$	MIC integrated noise	100 Hz to 20 kHz		1.5 µVrms	2 µVrms
f_{TONE1}	Button 1 frequency	R_{REM} = 6.81 kΩ	109 kHz	130 kHz	159 kHz
f_{TONE2}	Button 2 frequency	R_{REM} = 9.42 kΩ	138 kHz	165 kHz	200 kHz
f_{REL}	Button released frequency		81 kHz	97 kHz	117 kHz
R_{BT1}	Button 1 boundary		6.61 kΩ	6.81 kΩ	7.01 kΩ
R_{BT2}	Button 2 boundary		9.33 kΩ	9.42 kΩ	9.51 kΩ
V_{TA}	Tone amplitude	R_{TONE} = 1 MΩ	350 mV	550 mV	720 mV
V_{TA}	Tone amplitude	R_{TONE} = 100 kΩ	300 mV	515 mV	710 mV

Table 57-5 Electrical characteristics (button mode)

Symbol	Parameter	Test Conditions	Minimum	Typical	Maximum
t_{ONA}	Switch A enable time		0.8 ms	1.2 ms	2 ms
t_{OFFB}	Switch B disable time		0.7 ms	1 ms	2 ms
t_{REG}	Shunt regulator enable time	Time from MIC = 2.3 V to MICPWR = 1.56 V	1 ms	2.5 ms	3.5 ms

57.3.4 Theory of Operation

The transmitter provides:

- Interface to a button switch-resistor network.
- Power for a colocated microphone.
- Tone generator for sending discrete frequency tones on the microphone bias line corresponding to button events.

Copyright © 2025 Apple Inc. All Rights Reserved.

The receiver provides regulated downstream power (nominally 2.7 or 2.0 V) to the transmitter and microphone through the microphone bias line. Figure 57-9 (page 300) illustrates the functional components of the transmitter. In this diagram, a latch drives the configuration of switches A and B. The power-on reset monitors voltage on the MIC pin to ensure there is a enough power before initiating the power-on sequence; it shuts the transmitter down if there is insufficient voltage.

Figure 57-9 Block diagram



Button events are sent from the transmitter to the receiver in one of two modes, button mode or tone mode. When a microphone is not present or is not in use, the transmitter is put in button mode by the receiver, and button events are detected using discrete voltage levels. These discrete voltage levels are a percentage of a regulated output voltage on the microphone bias line. When a microphone is in use, the receiver puts the transmitter into tone mode by placing more than 2.35 V on the microphone bias line, and the transmitter then sends button events using tone sequences of discrete frequencies in the range 99 kHz to 300 kHz.

57.3.5 Button Mode

In button mode, the transmitter operates as a passthrough element switching a button switch-resistor network onto the bias line. Each switch represents a unique button. When a button is pressed, the DC level on the bias line is changed and detected by the receiver. Table 57-6 (page 301) shows the DETECT pin voltages with $V_{MICBIAS}$ = 2.0 V.

Copyright © 2025 Apple Inc. All Rights Reserved.

Table 57-6 DETECT pin voltages

Switch Closed	Voltage
S0	0.000 V ±1%
S1	1.510 V ±1%
S2	1.603 V ±1%

When the transmitter is in button mode (V_{MIC} has never reached 2.35 V), it shorts the MIC and REM pins together and disables all other inputs and outputs. When a button event occurs, the DC voltage on the microphone bias line changes. Table 57-6 (page 301) shows the DC voltage corresponding to a given button press when using the R1 and R4 resistor values listed in Table 57-7 (page 306). This DC level is then detected by the receiver. Switch S0 is a unique switch shorting the V_{MIC} line to ground.

When the V_{MIC} line is shorted to ground, power is removed from the transmitter. When power recovers, the transmitter enters button mode or tone mode, depending on the voltage detected at the MIC pin.

57.3.6 Tone Mode

When the transmitter detects a voltage greater than 2.35 V at the MIC pin, it enters tone mode. With a microphone biased and in use, the switch-resistor network used for button mode would cause large DC level shifts in the bias voltage. Such shifts would result in unwanted audible clicks or pops or would cause de-biasing of the microphone. To prevent this problem, when the transmitter enters tone mode it disconnects the switch-resistor network from the microphone bias line, enables the microphone using the FET switch, and engages the tone generation circuit shown in Figure 57-9 (page 300).

In tone mode the transmitter has two functions. First, it powers on the MEMS microphone by forcing a FET switch to ground. Second, it detects button events and places a discrete tone sequence onto the microphone bias line. The tone frequencies in each sequence are unique to each button press. The receiver detects the tones on the bias line and determines the corresponding button event.

The transmitter's startup timing when it enters tone mode is shown in Figure 57-10 (page 302). Values for the timing parameters are given in Table 57-4 (page 299).

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 57-10 Startup timing



The tone mode startup sequence is as follows:

1. Upon detecting V_{MIC} > 2.35 V, the switch connecting the MIC and REM pins together is opened after time t_{OFFB}, see Figure 57-10 (page 302) and Table 57-4 (page 299).
2. After a delay of t_{REG} after V_{MIC} > 2.35 V, the SHUNT pin and the MICPWR pins are shorted. The microphone is enabled using the FET switch through the MICPWR pin.
3. Once the noise prevention process has settled, the transmitter sends a preset acknowledge (ACK) tone sequence.
4. The receiver detects the ACK sequence, see Figure 57-11 (page 303), and authenticates the presence of the transmitter.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 57-11 Tone mode ACK sequence



The tone generation circuit of the transmitter internally detects each button press and sends a high frequency tone sequence between 99 kHz and 300 kHz. The high frequency tone sequence is unique to each button. The receiver detects the frequency of each tone and translates it into a predetermined button event. A button release has a different frequency than a button press.

The transmitter sends two tones for each button press as shown in Figure 57-12 (page 304) to improve accuracy. The first tone, lasting 1 ms, is a calibration frequency and the second, lasting 2 ms, is the unique frequency for the selected button. The ratio of these two frequencies is calculated and translated into button press information. This provides a very accurate result independent of clock frequency variation.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 57-12 Tone transmit/decode method



The transmitter remains in tone mode until the MIC pin is pulled below 0.8 V. When power recovers, the transmitter enters button mode or tone mode depending on the voltage detected at the MIC pin.

57.4 Button Detection Circuitry Usage

The circuits in the accessory supporting these components shall be those shown in Figure 57-13 (page 305) and Figure 57-14 (page 306). The nominal values of the components shown in these schematics are given in Table 57-7 (page 306).

These circuits are designed to produce a tone amplitude between the microphone bias line and the microphone return, at the end of a cable 1 meter long, of at least 30 mV peak-to-peak into a 2 kΩ load. If necessary, the value of R3 shall be adjusted to achieve this result. Figure 57-14 (page 306) shows how a voltage on the Microphone Power line from the transmitter enables the MEMS microphone chip through Q1. It also shows components R7, C4, and R8, which control the microphone frequency response. The equation determines the values of these components is given in Button Detection Circuitry Adjustments (page 307).

Figure 57-13 (page 305) and Figure 57-14 (page 306) are two parts of one circuit:

- The two microphone return lines shown in these sub-circuits shall be connected at the component locations.
- Their common return line and the return lines for each of the two drivers shall then be routed separately through the cable going to the device. The return lines shall be tied together only at the headset connector.

The above configuration minimizes crosstalk between the separate driver channels and the microphone.

Figure 57-13 Transmitter circuit



Figure 57-14 Microphone circuit



Table 57-7 Transmitter circuit components

Symbol	Description	Notes
C1	Capacitor, 0.1 µF ±10%, 6.3 V	
C2	Capacitor, 220 pF ±5%, 25 V	Ceramic
C4	Capacitor, 2.2 µF ±10%, 6.3 V	
D1	ESD protection diode, 5 pF, 6.1 V	ST Micro ESDALC6V1-1BU2; install as close to transmitter pin B1 as possible.
Q1	MOS field-effect transistor	CEDM 7001
R1	Resistor, 6.81 kΩ ±0.5%, 1/20 W	
R2	Resistor, 2 kΩ ±1%, 1/20 W	
R3	Resistor, 1.2 kΩ ±0.5%, 1/20 W	
R4	Resistor, 2.61 kΩ ±0.5%, 1/20 W	
R5	Resistor, 887 kΩ ±1%, 1/20 W	
R6	Resistor, 49.9 Ω +0.2%/-1%, 1/20 W	Shall not exceed 50 Ω.
R7	Resistor, 17.4 kΩ ±1%, 1/20 W	
R8	Resistor, value depends on U2.	See Additional Specifications & Support (page 279).
S0	Dome switch	Center button; shall not exceed 20 Ω when closed.
S1	Dome switch	Volume down; shall not exceed 20 Ω when closed.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Symbol	Description	Notes
S2	Dome switch	Volume up; shall not exceed 20 Ω when closed.
U1	Headset interface transmitter	Headset Remote and Microphone Transmitter
U2	MEMS analog microphone	See Additional Specifications & Support (page 279).

57.4.1 Button Detection Circuitry Adjustments

The values of some of the components listed in Table 57-7 (page 306) may be adjusted to optimize the performance of the headset accessory, using these formulas:

- **High-pass filter corner frequency in Hertz** $\approx 1/(2\pi \cdot R_8 \cdot C_4)$, where R_8 is the value of resistor R8 in ohms and C_4 is the value of capacitor C4 in Farads. This formula assumes the value of R7 is greater than the value of R8.
- **System sensitivity at 1 Pascal in Volts** = $(M_0/R_8) \cdot R_2$, where M_0 is the microphone sensitivity in Volts per Pascal, R_8 is the value of resistor R8 in ohms, and R_2 is the value of resistor R2 in ohms in parallel with 1.05 kΩ.
- **Maximum excursion of the microphone in Volts** = $(1/R_7) \cdot R_2$, where R_7 is the value of resistor R7 in ohms, and R_2 is the value of resistor R2 in ohms in parallel with 1.05 kΩ.

Note:
If the microphone bias voltage drops below 1.6 V, the transmitter will begin to fail and the microphone chip may produce indeterminate outputs.

Copyright © 2025 Apple Inc. All Rights Reserved.

Connectors

58. USB-A Receptacle

Accessories may incorporate a USB-A receptacle to:

- Provide power to a device.

58.1 Mechanical

The USB-A receptacle shall meet or exceed all applicable USB-IF mechanical specifications.

58.2 Electrical

The USB-A receptacle shall meet or exceed all applicable USB-IF electrical specifications.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

59. USB-C Plug

Accessories incorporating a USB-C plug shall comply with the *USB Type-C Cable and Connector Specification –Release 2.3*.

Accessories may incorporate a USB-C plug to:

- Provide power to device.
- Draw power from USB Type-C Current sources.
- Draw power from USB Power Delivery sources.
- Draw power from USB Dedicated Charging Ports and USB hosts.

Accessories benefiting from integrating a USB-C plug include cables, headsets, battery packs, and adapters.

59.1 Overview

The USB-C plug shall comply with the *USB Type-C Cable and Connector Specification –Release 2.3*.

59.2 Mechanical

Accessories incorporating a USB-C plug shall comply with USB-C plug interface dimensions as specified in *USB Type-C Cable and Connector Specification –Release 2.3*.

USB-C plug enclosures shall not exceed the following dimensions as shown in Figure 59-1 (page 311):

- 'A' ≤ 12.35 mm.
- 'B' ≤ 6.50 mm.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 59-1 USB-C plug example



USB-C plug enclosures should have full radii rounded edges for the greatest compatibility with the widest variety of cases, see USB-C receptacle accessory keep-out (page 315).

59.3 Electrical

59.3.1 Drawing Power

Accessories drawing power from the USB-C plug shall:

- Correctly identify all USB Type-C Current (page 241) sources.
- Correctly identify all USB Dedicated Charging Ports (DCP) as defined in the *USB Battery Charging Specification –Release 1.2*.
- Enumerate as a USB device when connected to a USB host and:
  - Not draw more than 100 mA of current until they have been successfully enumerated.
  - Request no more than 500 mA of charging current in their USB device descriptor.
- Not draw more power than the USB power source claims it is capable of providing using one of the above methods.

Accessories may also correctly identify all USB Power Delivery (PD) (page 240) sources.

Accessories drawing power from a device may do so using one of the following protocols:

- USB Type-C Current (page 241)
- USB Power Delivery (PD) (page 240)

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

59.3.2 Providing Power

Accessories providing power to a device using a USB-C plug shall:

- Provide at least 15 W (3 A at 5.0 V) of power.
- Support USB Type-C Current (page 241).

The accessories should:

- Support USB Power Delivery (PD) (page 240).
- Label the receptacle indicating how much power is supplied in watts.

59.4 Verification

59.4.1 Mechanical

Verify the dimensions of the USB-C plug comply with interface dimensions.

59.4.2 Drawing Power

This procedure applies to accessories drawing power using the USB-C plug.

59.4.2.1 Equipment

The following equipment is necessary:

- Apple 140W USB-C Power Adapter
- Apple 96W USB-C Power Adapter
- Apple 70W USB-C Power Adapter
- Apple 67W USB-C Power Adapter
- Apple 30W USB-C Power Adapter
- Apple 20W USB-C Power Adapter
- Apple 35W Dual USB-C Port Compact Power Adapter
- Apple 35W Dual USB-C Port Power Adapter
- Bundled USB-C power adapter (if applicable)

59.4.2.2 Procedure

1. Verify the accessory correctly identifies all Apple branded or bundled power sources:
   a. Verify each USB-C power adapter is correctly identified and provides power.
2. Verify the accessory correctly identifies a Mac and iPad:
   a. Verify the Mac is correctly identified and provides power.
   b. Verify the iPad is correctly identified and provides power.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

60. USB-C Receptacle

Accessories incorporating a USB-C receptacle shall comply with the *USB Type-C Cable and Connector Specification –Release 2.3*.

Accessories may incorporate a USB-C receptacle to:

- Provide power to device.
- Draw power from Apple branded power sources.
- Draw power from USB Type-C Current sources.
- Draw power from USB Power Delivery sources.
- Draw power from USB Dedicated Charging Ports and USB hosts.

Accessories benefiting from incorporating a USB-C receptacle include AC Power Adapters (page 93), Battery Packs (page 96), and speakers.

60.1 Overview

The USB-C receptacle shall comply with the *USB Type-C Cable and Connector Specification –Release 2.3*.

60.2 Mechanical

Accessories incorporating a USB-C receptacle shall comply with USB-C receptacle interface dimensions as specified in *USB Type-C Cable and Connector Specification –Release 2.3*.

See the recommended minimum USB-C receptacle accessory keep-out (page 315).

60.3 Electrical

60.3.1 Drawing Power

Accessories drawing power from the USB-C receptacle shall:

- Correctly identify all Apple branded power sources.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- Correctly identify all USB Type-C Current (page 241) sources.
- Enumerate as a USB device when connected to a USB host and:
  - Not draw more than 100 mA of current until they have been successfully enumerated.
  - Request no more than 500 mA of charging current in their USB device descriptor.
- Correctly identify all USB Dedicated Charging Ports (DCP) as defined in the *USB Battery Charging Specification –Release 1.2*.
- Not draw more power than the USB power source claims it is capable of providing using one of the above methods.

Accessories may also correctly identify all USB Power Delivery (PD) (page 240) sources.

60.3.2 Providing Power

Accessories providing power to a device using a USB-C receptacle shall:

- Provide at least 15 W (3 A at 5.0 V) of power.
- Support USB Type-C Current (page 241).

The accessories should:

- Support USB Power Delivery (PD) (page 240).
- Label the receptacle indicating how much power is supplied in watts.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

60.4 USB-C receptacle accessory keep-out

NOTES: (UNLESS OTHERWISE SPECIFIED)



METRIC	Apple Inc.
DRAFTER / DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER / DATE	
DIMENSIONS ARE IN MILLIMETERS TOLERANCES	TITLE: PROFILE,USB-C
DO NOT SCALE DRAWINGS	DRAWING NUMBER / REV.
THIRD ANGLE PROJECTION / SIZE D	SCALE 30:1 / SHT 1 OF 1

NX GENERATED

Copyright © 2025 Apple Inc. All Rights Reserved.

60.5 Verification

60.5.1 Drawing Power

This procedure applies to accessories drawing power using the USB-C receptacle.

60.5.1.1 Equipment

The following equipment is necessary:

- Apple USB-C Charge Cable (1 m)
- Apple USB-C Charge Cable (2 m)
- Bundled USB-C to USB-C cable (if applicable)
- Bundled USB-A to USB-C cable (if applicable)
- 3rd-party USB-A to USB-C cable
- Apple 140W USB-C Power Adapter
- Apple 96W USB-C Power Adapter
- Apple 70W USB-C Power Adapter
- Apple 67W USB-C Power Adapter
- Apple 30W USB-C Power Adapter
- Apple 20W USB-C Power Adapter
- Apple 35W Dual USB-C Port Compact Power Adapter
- Apple 35W Dual USB-C Port Power Adapter
- Apple 12W USB Power Adapter
- Apple 5W USB Power Adapter
- Bundled USB-C power adapter (if applicable)
- Bundled USB-A power adapter (if applicable)

60.5.1.2 Procedure

1. Verify the accessory correctly identifies all Apple branded or bundled power adapters:
   a. Using each USB-A to USB-C cable, verify each USB-A power adapter is correctly identified and provides power.
   b. Using each USB-C to USB-C cable, verify each USB-C power adapter is correctly identified and provides power.
2. Verify the accessory correctly identifies a Mac and iPad:
   a. Using each USB-A to USB-C cable and USB-C to USB-C cable, verify the Mac is correctly identified and provides power.
   b. Using each USB-A to USB-C cable and USB-C to USB-C cable, verify the iPad is correctly identified and provides power.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

60.5.2 Providing Power

This procedure applies to accessories providing power using the USB-C receptacle.

60.5.2.1 Equipment

The following equipment is necessary:

- Apple USB-C to Lightning Cable (1 m)
- Apple USB-C to Lightning Cable (2 m)
- Apple USB-C Charge Cable (1 m)
- Apple USB-C Charge Cable (2 m)
- Bundled USB-C to USB-C cable (if applicable)

60.5.2.2 Procedure

1. Verify the accessory correctly provides power to devices:
   a. Using each USB-C to Lightning cable, verify the accessory uses USB Type-C Current or USB PD to identify at least 15 W of power providing capability.
   b. Using each USB-C to Lightning cable, verify the accessory provides power to the device.
2. Verify the accessory correctly identifies a Mac and iPad:
   a. Using each USB-C to USB-C cable, verify the accessory is correctly identified and provides power to the Mac.
   b. Using each USB-C to USB-C cable, verify the accessory is correctly identified and provides power to the iPad.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

61. Headset Plug (3.5 mm)

Accessories may incorporate a 3.5 mm headset plug to pass audio and control signals between the accessory and a device or another accessory.

Figure 61-1 Headset plug

An accessory headset plug may support the following features (that is, the full functionality of the EarPods with 3.5 mm Headphone Plug):

- Stereo audio input.
- Microphone output.
- Center button.
- Volume Up and Volume Down buttons.

If an accessory supports three control buttons (volume up, volume down, and center), it shall use one of the following:

- Headset Remote and Microphone Transmitter (page 287).
- Direct electrical connection to a headset jack (3.5 mm) on the accessory.

61.1 Mechanical

The headset plug shall:

- Conform to the JEITA standard *RC 5325A, 4-Pole Miniature Concentric Plugs and Jacks*.
- Have a length and diameter matching those specified in Figure 61-2 (page 319).
- Be mechanically compatible with the headset jack (3.5 mm).

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 61-2 Headset plug dimensions and details



Headset plugs intended for insertion into a device's headset jack shall have a:

- Non-conductive flange as shown in Figure 61-2 (page 319).
- Cable shell with a maximum diameter 'B' of 5.9 mm and with no bends, curves, or protrusions for a minimum length 'A' of 11 mm from where the flange starts as shown in Figure 61-3 (page 319).

Figure 61-3 Headset plug cable shell dimensions



61.2 Pins

Table 61-1 (page 320) lists pin assignments for the headset plug corresponding to Figure 61-2 (page 319).

Table 61-1 Headset plug pin assignments

Pin	Description
1	Audio Output (Left)
2	Audio Output (Right)
3	Signal Return
4	Microphone Input

Some devices will apply and then measure a voltage across Pin 3 and Pin 4 in order to determine whether the headset is wired as specified in Table 61-1 (page 320) or not. The measured voltage shall be greater than 1.5 V.

Some devices will also apply a reverse bias voltage across Pin 3 and Pin 4 and then measure the response for the same purpose. The measured voltage shall not be less than -0.75 V.

61.3 Example Circuitry

Figure 61-4 (page 321) is an example of circuitry in an accessory with a single control button.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Figure 61-4 Typical headset plug circuitry



Table 61-2 Recommended component values for typical headset plug circuitry

Component	Value
C1	1 µF
R1	2.21 kΩ ±1%
R2	Codec input impedance ≥2 kΩ
L01/L02	600 Ω at 100 MHz
SW	Control button
VAR1	12 V varistor

Note:
The value given for L01 and L02 is typical. These ferrite chokes reduce time division multiple access (TDMA) noise; their exact values depend on the specific accessory design.

Switch SW shorts the microphone signal to ground. The device treats its closure as a headset button press and initiates a context-specific action (for example, answering a phone call). The microphone bias current shall be between 210 and 500 µA, measured into a circuit pulled up to 2.7 V through 2.21 kΩ, to ensure button press detection.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

The recommended microphone sensitivity is -44 dBV with a maximum impedance of 2.2 kΩ at the output of the equivalent circuit shown above, measured under test conditions of V_S = 2.0 V, R_L = 2.2 kΩ, T_A = 20 °C, and relative humidity = 65%.

61.4 Verification

1. If the accessory connects to the device using a detachable cable:
   a. Verify the end of the cable closest to the microphone is inserted into the headset and not the device.
   b. Perform subsequent tests on the device end of the cable.
2. Verify connector has non-conductive flange.
3. Verify the 3.5 mm shell diameter does not exceed 5.9 mm for a minimum length of 11 mm from where the flange starts.
4. Verify the 3.5 mm plug length is 14.00 mm ±0.10 mm.
5. Verify the 3.5 mm plug diameter is 3.50 mm +0.03/-0.05 mm.
6. Verify the 3.5 mm plug can be fully inserted into the device's headset jack. Verify there are no physical defects in the 3.5 mm plug preventing insertion.
7. Verify there are no grounding issues, heavy static, or audio interference when headset is attached to device.
   a. Repeatedly plug the headset in and out of the headset jack.
   b. Wiggle the connector.

61.4.1 Connectivity

1. Connect the accessory to the device.
2. Verify the following will not wake the device from a sleep state:
   a. Connect the accessory to the device.
   b. Press any button other than the center button on the headset remote.
   c. Disconnect the accessory from the device.
3. Connect the accessory to the device and verify the Controls (page 323).

61.4.2 Microphone

While the accessory is connected to the device:

1. Connect the accessory to the device.
2. Start an audio recording using the Voice Memo app.
3. Blow or tap on the headset microphone and verify audio is clearly recorded.
4. Blow or tap on the device microphone and verify minimal audio is recorded.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

5. Stop audio recording.

61.4.3 Controls

While the accessory is connected to the device:

1. Connect the accessory to the device.
2. Verify the device will enter a sleep state after a period of inactivity while the accessory is still connected.
3. Verify pressing the center button on the accessory will wake the device from a sleep state.
4. Verify pressing any other button on the accessory will not wake the device from a sleep state.
5. After the device enters a sleep state, activate Siri by pressing and holding the accessory center button. Verify the Siri tone is heard in full.
6. After the device enters a sleep state, trigger a notification (for example, send an iMessage to the device). Verify the notification sound is heard in full.
7. Verify pressing volume up increases the volume on the device.
8. Verify pressing volume down decreases the volume on the device.
9. Verify pressing the center button matches the behavior of a directly connected Apple headset:
    a. Verify Play and Pause works for songs and video tracks when pressing the center button.
    b. Verify Next Track works when pressing center button twice quickly.
    c. Verify Fast Forward works when pressing then press-and-holding the center button.
    d. Verify Previous Track works when pressing center button 3 times quickly.
    e. Verify pressing center button once will answer an incoming phone call or start playing music.
    f. Verify pressing center button once will end a phone call or stop playing music.
    g. Verify pressing and holding the center button will activate Siri.

61.4.4 Audio Quality

1. Connect the accessory to the device.
2. Verify there are no audible pops/clicks/artifacts and no audible grounding issue, heavy static, or audio interference at all times in the following scenarios:
    a. When the device is not playing music through the accessory:
        a. Repeatedly plug and unplug the accessory at slow, normal, and rapid speeds.
        b. Wiggle the connector.
        c. Repeat plug/unplug/wiggle steps while holding the accessory center button pressed.
        d. Repeat all (plug/unplug/wiggle, with/without center button pressed) with the device screen on (face-up) and off (face-down).
    b. When the device is playing music through the accessory.
    c. When the device is shutting down (open Settings > General > Shut Down) or powering on.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Tools

62. Accessory Developer Assistant (ADA)

Some test procedures in this specification require use of the Accessory Developer Assistant app, available from the App Store at https://apps.apple.com/us/app/accessory-developer-assistant/id1635862694.

The Accessory Developer Assistant app is a set of utilities designed to help accessory makers test new accessories. Use the Accessory Developer Assistant app to ensure iPhone and iPad performance for features such as:

- Camera Control (page 74)
- Autofocus & Optical Image Stabilization (page 80)
- Image Quality
- Near-Field Communication (NFC) (page 80)
- Compass (page 81)

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

62.1 Autofocus & Optical Image Stabilization Test Profile

The Autofocus & Optical Image Stabilization (page 80) test procedure requires an additional profile to be installed:

1. Use the device to access the ADA Camera Test profile at https://download.developer.apple.com/Developer_Tools/Accessory_Developer_Assistant_Camera_Test_Profile/ADACamera.mobileconfig.
2. Install the profile to the device.
3. Open Settings > Profile Downloaded and complete the installation.
4. Reboot the device.

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

References

63. Device Dimensional Drawings

iPhone dimensional drawings:

- iPhone 17 Pro Max, 1 of 4 (page 333)
- iPhone 17 Pro, 1 of 4 (page 337)
- iPhone 17, 1 of 4 (page 341)
- iPhone Air, 1 of 4 (page 345)
- iPhone 16e, 1 of 2 (page 349)
- iPhone 16 Pro Max, 1 of 4 (page 351)
- iPhone 16 Pro, 1 of 4 (page 355)
- iPhone 16 Plus, 1 of 4 (page 359)
- iPhone 16, 1 of 4 (page 363)
- iPhone 15 Pro Max, 1 of 3 (page 367)
- iPhone 15 Pro, 1 of 3 (page 370)
- iPhone 15 Plus, 1 of 3 (page 373)
- iPhone 15, 1 of 3 (page 376)
- iPhone 14 Pro Max, 1 of 3 (page 379)
- iPhone 14 Pro, 1 of 3 (page 382)
- iPhone 14 Plus, 1 of 3 (page 385)
- iPhone 14, 1 of 3 (page 388)
- iPhone SE (3rd generation) and iPhone SE (2nd generation) (page 407)
- iPhone 13 Pro Max, 1 of 2 (page 391)
- iPhone 13 Pro, 1 of 2 (page 393)
- iPhone 13, 1 of 2 (page 395)
- iPhone 13 mini, 1 of 2 (page 397)
- iPhone 12 Pro Max, 1 of 2 (page 399)
- iPhone 12 Pro, 1 of 2 (page 401)
- iPhone 12, 1 of 2 (page 403)
- iPhone 12 mini, 1 of 2 (page 405)
- iPhone 11 Pro Max (page 408)
- iPhone 11 Pro (page 409)
- iPhone 11 (page 410)
- iPhone XS Max (page 411)
- iPhone XS (page 412)
- iPhone XR (page 413)
- iPhone X (page 414)

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- iPhone 8 Plus (page 415)
- iPhone 8 (page 416)
- iPhone 7 Plus (page 417)
- iPhone 7 (page 418)
- iPhone 6s Plus (page 419)
- iPhone 6s (page 420)
- iPhone 6 Plus (page 421)
- iPhone 6 (page 422)
- iPhone SE and iPhone 5s (page 423)
- iPhone 5c (page 424)
- iPhone 5 (page 425)

iPad dimensional drawings:

- iPad Pro 13-inch (M5) and iPad Pro 13-inch (M4), 1 of 5 (page 426)
- iPad Pro 11-inch (M5) and iPad Pro 11-inch (M4), 1 of 5 (page 431)
- iPad Air 13-inch (M3) and iPad Air 13-inch (M2), 1 of 5 (page 436)
- iPad Air 11-inch (M3) and iPad Air 11-inch (M2), 1 of 5 (page 441)
- iPad (A16) and iPad (10th generation), 1 of 7 (page 446)
- iPad mini (A17 Pro), 1 of 6 (page 453)
- iPad Pro 12.9-inch (6th generation), 1 of 5 (page 459)
- iPad Pro 11-inch (4th generation), 1 of 5 (page 464)
- iPad Air (5th generation) and iPad Air (4th generation), 1 of 5 (page 469)
- iPad mini (6th generation), 1 of 6 (page 474)
- iPad (9th generation), iPad (8th generation) and iPad (7th generation), 1 of 4 (page 480)
- iPad Pro 12.9-inch (5th generation), 1 of 5 (page 484)
- iPad Pro 11-inch (3rd generation), 1 of 5 (page 489)
- iPad Pro 12.9-inch (4th generation), 1 of 5 (page 494)
- iPad Pro 11-inch (2nd generation), 1 of 5 (page 499)
- iPad Air (3rd generation), 1 of 3 (page 504)
- iPad Air (3rd generation) with Cellular, 1 of 3 (page 507)
- iPad mini (5th generation), 1 of 3 (page 510)
- iPad mini (5th generation) with Cellular, 1 of 3 (page 513)
- iPad Pro 12.9-inch (3rd generation), 1 of 3 (page 516)
- iPad Pro 11-inch (1st generation), 1 of 3 (page 519)
- iPad Pro 12.9-inch (2nd generation) (page 522)
- iPad Pro 12.9-inch (2nd generation) with Cellular (page 523)
- iPad Pro 12.9-inch (2nd generation) Magnet/Hall Effect Sensors, 1 of 2 (page 524)
- iPad Pro 10.5-inch (page 526)
- iPad Pro 10.5-inch with Cellular (page 527)
- iPad Pro 10.5-inch Magnet/Hall Effect Sensors, 1 of 2 (page 528)

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- iPad (5th and 6th generation) with Cellular (page 530)
- iPad (5th and 6th generation) Magnet/Hall Effect Sensors, 1 of 2 (page 531)
- iPad Pro 9.7-inch (page 533)
- iPad Pro 9.7-inch with Cellular (page 534)
- iPad Pro 9.7-inch Magnet/Hall Effect Sensors, 1 of 2 (page 535)
- iPad Pro 12.9-inch (1st generation) (page 537)
- iPad Pro 12.9-inch (1st generation) with Cellular (page 538)
- iPad Pro 12.9-inch (1st generation) Magnet/Hall Effect Sensors, 1 of 2 (page 539)
- iPad mini 4 (page 541)
- iPad mini 4 with Cellular (page 542)
- iPad mini 4 Magnet/Hall Effect Sensors (page 543)
- iPad Air 2 (page 544)
- iPad Air 2 with Cellular (page 545)
- iPad mini 3 and iPad mini 2 (page 546)
- iPad mini 3 and iPad mini 2 with Cellular (page 547)
- iPad Air (page 548)
- iPad Air with Cellular (page 549)
- iPad mini (page 550)
- iPad mini with Cellular (page 551)
- iPad (4th generation) (page 552)
- iPad (4th generation) with Cellular (page 553)

iPod dimensional drawings:

- iPod touch (7th generation) and iPod touch (6th generation) (page 554)
- iPod touch (5th generation) (page 555)

Apple Watch dimensional drawings:

- Apple Watch Ultra 3 & Apple Watch Ultra 2, 1 of 3 (page 556)
- Apple Watch Series 11 & Apple Watch Series 10, 46 mm (page 559)
- Apple Watch Series 11 & Apple Watch Series 10, 42 mm (page 560)
- Apple Watch SE 3 & Apple Watch SE 2, 44 mm (page 561)
- Apple Watch SE 3 & Apple Watch SE 2, 40 mm (page 562)
- Apple Watch Series 9, 45 mm (page 563)
- Apple Watch Series 9, 41 mm (page 564)
- Apple Watch Ultra, 1 of 3 (page 565)
- Apple Watch Series 8, 45 mm (page 568)
- Apple Watch Series 8, 41 mm (page 569)
- Apple Watch Series 7, 45 mm (page 570)
- Apple Watch Series 7, 41 mm (page 571)
- Apple Watch Series 6, 44 mm (page 572)
- Apple Watch Series 6, 40 mm (page 573)

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

- Apple Watch SE, 44 mm (page 574)
- Apple Watch SE, 40 mm (page 575)
- Apple Watch Series 5, 44 mm (page 576)
- Apple Watch Series 5, 40 mm (page 577)
- Apple Watch Series 5 Ceramic, 44 mm (page 578)
- Apple Watch Series 5 Ceramic, 40 mm (page 579)
- Apple Watch Series 4, 44 mm (page 580)
- Apple Watch Series 4, 40 mm (page 581)
- Apple Watch Series 3 Ceramic, 42 mm (page 582)
- Apple Watch Series 3 Ceramic, 38 mm (page 583)
- Apple Watch Series 3 Metal, 42 mm (page 584)
- Apple Watch Series 3 Metal, 38 mm (page 585)
- Apple Watch Series 2 Ceramic, 42 mm (page 586)
- Apple Watch Series 2 Ceramic, 38 mm (page 587)
- Apple Watch Series 2 Metal, 42 mm (page 588)
- Apple Watch Series 2 Metal, 38 mm (page 589)
- Apple Watch Series 1 and Apple Watch (1st generation), 42 mm (page 590)
- Apple Watch Series 1 and Apple Watch (1st generation), 38 mm (page 591)

Apple Vision Pro dimensional drawings:

- Apple Vision Pro, 1 of 8 (page 592)
- Apple Vision Pro Battery (page 600)
- Apple Vision Pro Audio Strap (page 601)
- ZEISS Optical Inserts, 1 of 4 (page 602)

AirPods dimensional drawings:

- MagSafe Charging Case for AirPods Pro 3, 1 of 3 (page 606)
- AirPods Pro 3 (page 609)
- Wireless Charging Case (USB-C) for AirPods 4, 1 of 3 (page 610)
- AirPods 4 (page 613)
- MagSafe Charging Case (USB-C) for AirPods Pro (2nd generation), 1 of 3 (page 614)
- MagSafe Charging Case for AirPods Pro (2nd generation), 1 of 3 (page 617)
- AirPods Pro (2nd generation) (page 620)
- MagSafe Charging Case for AirPods (3rd generation) (page 621)
- AirPods (3rd generation) (page 622)
- AirPods Max, 1 of 6 (page 623)
- Wireless Charging Case for AirPods Pro (1st generation) (page 629)
- AirPods Pro (1st generation) (page 630)
- Wireless Charging Case for AirPods (page 631)
- AirPods (2nd generation) and AirPods (1st generation) (page 632)

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Additional dimensional drawings:

- Apple MagSafe Charger (1 m) and Apple MagSafe Charger (2 m) (page 633)
- Apple MagSafe Charger (page 634)
- AirTag (page 635)
- Apple TV 4K (3rd generation) (page 636)
- Siri Remote (3rd generation) (page 637)

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

63.1 iPhone 17 Pro Max, 1 of 4



63.2 iPhone 17 Pro Max, 2 of 4



63.3 iPhone 17 Pro Max, 3 of 4



Copyright © 2025 Apple Inc. All Rights Reserved.

63.4 iPhone 17 Pro Max, 4 of 4



63.5 iPhone 17 Pro, 1 of 4



Copyright © 2025 Apple Inc. All Rights Reserved.

63.6 iPhone 17 Pro, 2 of 4





2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

63.8 iPhone 17 Pro, 4 of 4



Copyright © 2025 Apple Inc. All Rights Reserved.

63.9 iPhone 17, 1 of 4



63.10 iPhone 17, 2 of 4



Copyright © 2025 Apple Inc. All Rights Reserved.

63.11 iPhone 17, 3 of 4



Copyright © 2025 Apple Inc. All Rights Reserved.

63.12 iPhone 17, 4 of 4



63.13 iPhone Air, 1 of 4



63.14 iPhone Air, 2 of 4



Copyright © 2025 Apple Inc. All Rights Reserved.


DETAIL N
SECTION S - S
SECTION T - T
SECTION U - U
DETAIL M
SECTION P - P
SECTION R - R
FRONT CAMERA AND FORWARD FACING SENSORS BASE OF KEEPOUT CONES
RECEIVER KEEPOUT
ALS SENSOR BASE OF KEEPOUT CONE
FRONT SENSOR KEEPOUT
FRONT CAMERA KEEPOUT
REAR CAMERA KEEPOUT CONE
FLASH OUTER KEEPOUT CONE
FLASH INNER KEEPOUT CONE
FLASH INNER BASE DIAMETER
FRONT FLASH KEEPOUT CONE BASE TO COVER GLASS
SENSOR KEEPOUT BASE TO COVER GLASS
NOTICE OF PROPRIETARY PROPERTY
SIZE
SCALE NONE
SHT 3 OF 4


KEEP OUT AREA 1
KEEP OUT AREA 2
100°
100°
0.00
33.14
128.42
134.57
5.92
69.53
127.12
29.35
17.32
6.02
66.70
DO NOT OBSTRUCT THIS AREA WITH METAL OR OTHER CONDUCTIVE MATERIAL INCLUDING SIDEWALLS!
DO NOT OBSTRUCT THIS AREA WITH METAL OR OTHER CONDUCTIVE MATERIAL INCLUDING SIDEWALLS!
0.00
34.17
78.34
PRODUCT CENTER
2X 113.75
R 49.39
151.29
18.11
37.35
PRODUCT CENTER
28.83
[5] [7] COMPASS
[5] [7] DO NOT OBSTRUCT THIS AREA WITH METAL OR OTHER CONDUCTIVE MATERIAL, OR MAGNETIC MATERIAL
Ø61.50
[5] [7] DO NOT OBSTRUCT THIS AREA WITH METAL OR OTHER CONDUCTIVE MATERIAL EXCEPT MAGSAFE MAGNETS
KEEPOUT 2 MEASURED AT GLASS SURFACE
1
0.00
-29.72
-43.80
0.00
2.96
8.79
25.41
48.76
2
KEEPOUT 1 DIMENSIONS MEASURED AT GLASS SURFACE
[5] DO NOT OBSTRUCT THIS AREA WITH METAL OR OTHER CONDUCTIVE MATERIAL INCLUDING SIDEWALLS! NON-CONDUCTIVE MATERIAL TO BE UNIFORM IN THICKNESS
-22.03
-28.32
NOTICE OF PROPRIETARY PROPERTY:
THE SIZE
NONE
SHT 4 OF 4

63.17 iPhone 16e, 1 of 2



63.18 iPhone 16e, 2 of 2



Copyright © 2025 Apple Inc. All Rights Reserved.

63.19 iPhone 16 Pro Max, 1 of 4



2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

63.20 iPhone 16 Pro Max, 2 of 4



Copyright © 2025 Apple Inc. All Rights Reserved.

63.21 iPhone 16 Pro Max, 3 of 4



Copyright © 2025 Apple Inc. All Rights Reserved.


0.00
14.00
63.58
32.77
24.60
14.00
136.83
137.40
149.03
DO NOT OBSTRUCT THIS AREA WITH METAL OR OTHER CONDUCTIVE MATERIAL INCLUDING SIDEWALLS!
DO NOT OBSTRUCT THIS AREA WITH METAL OR OTHER CONDUCTIVE MATERIAL INCLUDING SIDEWALLS!
0.00
14.00
63.58
46.54
45.22
81.78
PRODUCT CENTER
38.79
PRODUCT CENTER
56.00
2X 115.44
R 49.39
Ø57.50
158.58
5 7 COMPASS
5 7 DO NOT OBSTRUCT THIS AREA WITH METAL OR PERMEABLE MATERIAL EXCEPT MAGSAFE MAGNETS
5 7 DO NOT OBSTRUCT THIS AREA WITH CONDUCTIVE MATERIAL, OR MAGNETIC MATERIAL
DO NOT OBSTRUCT THIS AREA WITH METAL OR OTHER CONDUCTIVE MATERIAL INCLUDING SIDEWALLS!
0.00
52.02
59.08
61.06
68.03
9.57
10.47
24.61
35.43
1 KEEPOUT DIMENSIONS MEASURED AT GLASS SURFACE
2 KEEPOUT DIMENSIONS MEASURED AT GLASS SURFACE
5 DO NOT OBSTRUCT THIS AREA WITH METAL OR OTHER CONDUCTIVE MATERIAL INCLUDING SIDEWALLS! NON-CONDUCTIVE MATERIAL TO BE UNIFORM IN THICKNESS
KEEP OUT AREA 1
80°
KEEP OUT AREA 2
120°
NOTICE OF PROPRIETARY PROPERTY:
THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC.
THE POSSESSION OR USE OF THIS DOCUMENT IN CONFLICT WITH THE TERMS AND CONDITIONS AGREED TO BY THE RECIPIENT, OR WITHOUT THE PRIOR WRITTEN CONSENT OF APPLE INC. IS STRICTLY PROHIBITED. DO NOT COPY OR REPRODUCE IN WHOLE OR PART WITHOUT THE PRIOR WRITTEN CONSENT OF APPLE INC. ALL RIGHTS RESERVED.
SIZE
D
SCALE
NONE
SHT 4 OF 4

63.23 iPhone 16 Pro, 1 of 4



Copyright © 2025 Apple Inc. All Rights Reserved.

63.24 iPhone 16 Pro, 2 of 4



63.25 iPhone 16 Pro, 3 of 4



Copyright © 2025 Apple Inc. All Rights Reserved.

63.26 iPhone 16 Pro, 4 of 4



63.27 iPhone 16 Plus, 1 of 4



63.28 iPhone 16 Plus, 2 of 4



Copyright © 2025 Apple Inc. All Rights Reserved.

63.29 iPhone 16 Plus, 3 of 4



DETAIL P



SECTION G-G



SECTION J-J



SECTION N-N





DETAIL O



SECTION S-S

SECTION T-T

NOTICE OF PROPRIETARY PROPERTY:
THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING:
(i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE
(ii) NOT TO REPRODUCE OR COPY IT
(iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART
(iv) ALL RIGHTS RESERVED

Apple Inc.

SIZE D | DRAWING NUMBER | REV.

SCALE: NONE | SHT 3 OF 4

63.30 iPhone 16 Plus, 4 of 4



Copyright © 2025 Apple Inc. All Rights Reserved.

63.31 iPhone 16, 1 of 4



63.32 iPhone 16, 2 of 4



Copyright © 2025 Apple Inc. All Rights Reserved.

63.33 iPhone 16, 3 of 4



Copyright © 2025 Apple Inc. All Rights Reserved.

63.34 iPhone 16, 4 of 4



63.35 iPhone 15 Pro Max, 1 of 3

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. NO METAL CONTACT WITH PRODUCT.
2. DO NOT OBSTRUCT PORTS.
3. DO NOT OBSTRUCT THE IMAGING FEATURES: FRONT CAMERA, REAR CAMERAS, REAR FLASH.
4. DO NOT OBSTRUCT FORWARD FACING SENSORS.
5. RELATIVE MAGNETIC PERMEABILITY OF ANY METAL USED ON CASE: 1.05 MAX, PER ASTM A342/A342M-14.
6. DO NOT TOUCH GLASS.
7. NO MAGNETS ON REAR OF PRODUCT EXCEPT MAGSAFE MAGNETS.
8. CASE THICKNESS ON BACKSIDE OF PRODUCT: 2.1 mm MAX TO ENSURE FULL FUNCTIONALITY.



CORNER PROFILE (ALL FOUR CORNERS)
DETAIL D



DETAIL A













PROFILE (ALL SIDES)
DETAIL B





DETAIL C

METRIC	
DRAFTER / DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO COPY OR REPRODUCE IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER / DATE	
DIMENSIONS ARE IN MILLIMETERS TOLERANCES X.X ±0.2 X.XX ±0.10 X.XXX ±0.050 ANGLES ±0.5° DO NOT SCALE DRAWINGS	TITLE: IPHONE 15 PRO MAX
THIRD ANGLE PROJECTION	DRAWING NUMBER / REV.
SIZE D	SCALE NONE
	SHT 1 OF 3

NX GENERATED

Copyright © 2025 Apple Inc. All Rights Reserved.

63.36 iPhone 15 Pro Max, 2 of 3



Copyright © 2025 Apple Inc. All Rights Reserved.

63.37 iPhone 15 Pro Max, 3 of 3



Copyright © 2025 Apple Inc. All Rights Reserved.

63.38 iPhone 15 Pro, 1 of 3

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. NO METAL CONTACT WITH PRODUCT.
2. DO NOT OBSTRUCT PORTS.
3. DO NOT OBSTRUCT THE IMAGING FEATURES: FRONT CAMERA, REAR CAMERAS, REAR FLASH.
4. DO NOT OBSTRUCT FORWARD FACING SENSORS.
5. RELATIVE MAGNETIC PERMEABILITY OF ANY METAL USED ON CASE: 1.05 MAX, PER ASTM A342/A342M-14.
6. DO NOT TOUCH GLASS.
7. NO MAGNETS ON REAR OF PRODUCT EXCEPT MAGSAFE MAGNETS.
8. CASE THICKNESS ON BACKSIDE OF PRODUCT: 2.1 mm MAX TO ENSURE FULL FUNCTIONALITY.



CORNER PROFILE (ALL FOUR CORNERS)
DETAIL A



DETAIL D













PROFILE (ALL SIDES)
DETAIL B





DETAIL C

METRIC		
DRAFTER	DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER	DATE	
DIMENSIONS ARE IN MILLIMETERS TOLERANCES X.X ±0.2 X.XX ±0.10 X.XXX ±0.050 ANGLES ±0.5° DO NOT SCALE DRAWING		TITLE: IPHONE 15 PRO
		DRAWING NUMBER / REV.
THIRD ANGLE PROJECTION	SIZE D	SCALE NONE / SHT 1 OF 3

NX GENERATED

63.39 iPhone 15 Pro, 2 of 3



63.40 iPhone 15 Pro, 3 of 3



Copyright © 2025 Apple Inc. All Rights Reserved.

63.41 iPhone 15 Plus, 1 of 3



63.42 iPhone 15 Plus, 2 of 3



63.43 iPhone 15 Plus, 3 of 3



Copyright © 2025 Apple Inc. All Rights Reserved.

63.44 iPhone 15, 1 of 3



63.45 iPhone 15, 2 of 3



63.46 iPhone 15, 3 of 3



63.47 iPhone 14 Pro Max, 1 of 3

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. NO METAL CONTACT WITH iPHONE.
2. DO NOT OBSTRUCT PORTS.
3. DO NOT OBSTRUCT THE IMAGING FEATURES: FRONT CAMERA, REAR CAMERAS, REAR FLASH.
4. DO NOT OBSTRUCT FORWARD FACING SENSORS.
5. RELATIVE MAGNETIC PERMEABILITY OF ANY METAL USED ON CASE: 1.05 MAX, PER ASTM A342/A342M-14.
6. DO NOT TOUCH GLASS.
7. NO MAGNETS ON REAR OF PRODUCT EXCEPT MAGSAFE MAGNETS.
8. CASE THICKNESS ON BACKSIDE OF PRODUCT: 2.1 mm MAX TO ENSURE FULL FUNCTIONALITY.



CORNER PROFILE (ALL FOUR CORNERS)
DETAIL D



DETAIL A













PROFILE (ALL SIDES)
DETAIL B





DETAIL C

METRIC	Apple Inc.
DRAFTER / DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVERSE ENGINEER OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER / DATE	
DIMENSIONS ARE IN MILLIMETERS TOLERANCES 0 < - < 2 ±0.05 2 < - < 10 ±0.08 10 < - < 50 ±0.10 50 < - < 100 ±0.20 100 < - < 200 ±0.30 200 < - ±0.40 ANGLES ±0.50° DO NOT SCALE DRAWING	TITLE: IPHONE 14 PRO MAX
THIRD ANGLE PROJECTION / SIZE D	DRAWING NUMBER / REV.
	SCALE NONE / SHT 1 OF 3

NX GENERATED

63.48 iPhone 14 Pro Max, 2 of 3



63.49 iPhone 14 Pro Max, 3 of 3



63.50 iPhone 14 Pro, 1 of 3

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. NO METAL CONTACT WITH iPHONE.
2. DO NOT OBSTRUCT PORTS.
3. DO NOT OBSTRUCT THE IMAGING FEATURES: FRONT CAMERA, REAR CAMERAS, REAR FLASH.
4. DO NOT OBSTRUCT FORWARD FACING SENSORS.
5. RELATIVE MAGNETIC PERMEABILITY OF ANY METAL USED ON CASE: 1.05 MAX, PER ASTM A342/A342M-14.
6. DO NOT TOUCH GLASS.
7. NO MAGNETS ON REAR OF PRODUCT EXCEPT MAGSAFE MAGNETS.
8. CASE THICKNESS ON BACKSIDE OF PRODUCT: 2.1 mm MAX TO ENSURE FULL FUNCTIONALITY.



CORNER PROFILE (ALL FOUR CORNERS)
DETAIL A



DETAIL D













PROFILE (ALL SIDES)
DETAIL B





DETAIL C

METRIC	Apple Inc.
DRAWTER / DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER / DATE	TITLE: IPHONE 14 PRO
DIMENSIONS ARE IN MILLIMETERS TOLERANCES 0 < - < 2 ±0.05 2 < - < 10 ±0.08 10 < - < 50 ±0.10 50 < - < 100 ±0.20 100 < - < 200 ±0.30 200 < - ±0.40 ANGLES ±0.50° DO NOT SCALE DRAWING	DRAWING NUMBER / REV.
THIRD ANGLE PROJECTION / SIZE D	SCALE NONE / SHT 1 OF 3

NX GENERATED


FRONT SENSOR KEEPOUTS
DETAIL E
SECTION G - G
DETAIL H
SECTION J - J
DETAIL F
Apple Inc.
NONE
SHT 2 OF 3

63.52 iPhone 14 Pro, 3 of 3



63.53 iPhone 14 Plus, 1 of 3

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. NO METAL CONTACT WITH iPHONE.
2. DO NOT OBSTRUCT PORTS.
3. DO NOT OBSTRUCT THE IMAGING FEATURES: FRONT CAMERA, REAR CAMERAS, REAR FLASH.
4. DO NOT OBSTRUCT FORWARD FACING SENSORS.
5. RELATIVE MAGNETIC PERMEABILITY OF ANY METAL USED ON CASE: 1.05 MAX, PER ASTM A342/A342M-14.
6. DO NOT TOUCH GLASS.
7. NO MAGNETS ON REAR OF PRODUCT EXCEPT MAGSAFE MAGNETS.
8. CASE THICKNESS ON BACKSIDE OF PRODUCT: 2.1 mm MAX TO ENSURE FULL FUNCTIONALITY.



CORNER PROFILE (ALL FOUR CORNERS)
DETAIL D



DETAIL A













DETAIL B





DETAIL C

METRIC	Apple Inc.
DRAWTER / DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVERSE ENGINEER OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER / DATE	
DIMENSIONS ARE IN MILLIMETERS TOLERANCES 0 < - < 2 ±0.05 2 < - < 10 ±0.08 10 < - < 50 ±0.10 50 < - < 100 ±0.20 100 < - < 200 ±0.30 200 < - ±0.40 ANGLES ±0.50° DO NOT SCALE DRAWING	TITLE: IPHONE 14 PLUS
THIRD ANGLE PROJECTION / SIZE D	DRAWING NUMBER / REV.
	SCALE NONE / SHT 1 OF 3

NX GENERATED

Copyright © 2025 Apple Inc. All Rights Reserved.

63.54 iPhone 14 Plus, 2 of 3



Copyright © 2025 Apple Inc. All Rights Reserved.

63.55 iPhone 14 Plus, 3 of 3



Copyright © 2025 Apple Inc. All Rights Reserved.

63.56 iPhone 14, 1 of 3

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. NO METAL CONTACT WITH iPHONE.
2. DO NOT OBSTRUCT PORTS.
3. DO NOT OBSTRUCT THE IMAGING FEATURES: FRONT CAMERA, REAR CAMERAS, REAR FLASH.
4. DO NOT OBSTRUCT FORWARD FACING SENSORS.
5. RELATIVE MAGNETIC PERMEABILITY OF ANY METAL USED ON CASE: 1.05 MAX, PER ASTM A342/A342M-14.
6. DO NOT TOUCH GLASS.
7. NO MAGNETS ON REAR OF PRODUCT EXCEPT MAGSAFE MAGNETS.
8. CASE THICKNESS ON BACKSIDE OF PRODUCT: 2.1 mm MAX TO ENSURE FULL FUNCTIONALITY.





















METRIC	Apple Inc.
DRAWTER / DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER / DATE	
DIMENSIONS ARE IN MILLIMETERS TOLERANCES 0 < - < 2 ±0.05 2 < - < 10 ±0.08 10 < - < 50 ±0.10 50 < - < 100 ±0.20 100 < - < 200 ±0.30 200 < - ±0.40 ANGLES ±0.50° DO NOT SCALE DRAWING	TITLE: IPHONE 14
THIRD ANGLE PROJECTION / SIZE D	DRAWING NUMBER / REV.
	SCALE NONE / SHT 1 OF 3

NX GENERATED

Copyright © 2025 Apple Inc. All Rights Reserved.

63.57 iPhone 14, 2 of 3



Copyright © 2025 Apple Inc. All Rights Reserved.

63.58 iPhone 14, 3 of 3



63.59 iPhone 13 Pro Max, 1 of 2

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. NO METAL CONTACT WITH IPHONE.
2. DO NOT OBSTRUCT PORTS.
3. DO NOT OBSTRUCT THE IMAGING FEATURES: FRONT CAMERA, REAR CAMERAS, REAR FLASH.
4. DO NOT OBSTRUCT FORWARD FACING SENSORS.
5. RELATIVE MAGNETIC PERMEABILITY OF ANY METAL USED ON CASE: 1.05 MAX, PER ASTM A342/A342M-14.
6. DO NOT TOUCH GLASS.
7. NO MAGNETS ON REAR OF PRODUCT EXCEPT MAGSAFE MAGNETS.
8. CASE THICKNESS ON BACKSIDE OF PRODUCT: 2.1 mm MAX TO ENSURE FULL FUNCTIONALITY.



CORNER PROFILE (ALL FOUR CORNERS)
DETAIL A











DETAIL D





PROFILE (ALL SIDES)
DETAIL B





DETAIL C

METRIC		Apple Inc.	
DRAFTER	DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED	
DESIGNER	DATE		
0 < - < 2 ±0.05 2 < - < 10 ±0.08 10 < - < 50 ±0.10 50 < - < 100 ±0.20 100 < - < 200 ±0.30 200 < - ±0.40 ANGLES ±0.50°		TITLE: iPhone 13 Pro Max	
		DRAWING NUMBER	REV.
THIRD ANGLE PROJECTION	SIZE D	SCALE NONE	SHT 1 OF 2

NX GENERATED

Copyright © 2025 Apple Inc. All Rights Reserved.

63.60 iPhone 13 Pro Max, 2 of 2



Copyright © 2025 Apple Inc. All Rights Reserved.

63.61 iPhone 13 Pro, 1 of 2

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. NO METAL CONTACT WITH IPHONE.
2. DO NOT OBSTRUCT PORTS.
3. DO NOT OBSTRUCT THE IMAGING FEATURES: FRONT CAMERA, REAR CAMERAS, REAR FLASH.
4. DO NOT OBSTRUCT FORWARD FACING SENSORS.
5. RELATIVE MAGNETIC PERMEABILITY OF ANY METAL USED ON CASE: 1.05 MAX, PER ASTM A342/A342M-14.
6. DO NOT TOUCH GLASS.
7. NO MAGNETS ON REAR OF PRODUCT EXCEPT MAGSAFE MAGNETS.
8. CASE THICKNESS ON BACKSIDE OF PRODUCT: 2.1 mm MAX TO ENSURE FULL FUNCTIONALITY.



CORNER PROFILE (ALL FOUR CORNERS)
DETAIL A











DETAIL D





PROFILE (ALL SIDES)
DETAIL B





DETAIL C

METRIC	Apple Inc.
DRAFTER: APPLE INC. — DATE: 05/14/21	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER: APPLE INC. — DATE: 05/14/21	
0 < - < 2 ±0.05 2 < - < 10 ±0.08 10 < - < 50 ±0.10 50 < - < 100 ±0.20 100 < - < 200 ±0.30 200 < - ±0.40 ANGLES ±0.50°	TITLE: iPhone 13 Pro
	DRAWING NUMBER — REV.
THIRD ANGLE PROJECTION — SIZE D — SCALE NONE — SHT 1 OF 2	

NX GENERATED

63.62 iPhone 13 Pro, 2 of 2



Copyright © 2025 Apple Inc. All Rights Reserved.

63.63 iPhone 13, 1 of 2

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. NO METAL CONTACT WITH IPHONE.
2. DO NOT OBSTRUCT PORTS.
3. DO NOT OBSTRUCT THE IMAGING FEATURES: FRONT CAMERA, REAR CAMERAS, REAR FLASH.
4. DO NOT OBSTRUCT FORWARD FACING SENSORS.
5. RELATIVE MAGNETIC PERMEABILITY OF ANY METAL USED ON CASE: 1.05 MAX, PER ASTM A342/A342M-14.
6. DO NOT TOUCH GLASS.
7. NO MAGNETS ON REAR OF PRODUCT EXCEPT MAGSAFE MAGNETS.
8. CASE THICKNESS ON BACKSIDE OF PRODUCT: 2.1 mm MAX TO ENSURE FULL FUNCTIONALITY.



CORNER PROFILE (ALL FOUR CORNERS)
DETAIL A



DETAIL D













PROFILE (ALL SIDES)
DETAIL B





DETAIL C

METRIC	Apple Inc.
DRAWTER: APPLE INC.	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVERSE ENGINEER OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER: APPLE INC.	TITLE: iPhone 13
0 < - < 2 ±0.05; 2 < - < 10 ±0.08; 10 < - < 50 ±0.10; 50 < - < 100 ±0.20; 100 < - < 200 ±0.30; 200 < - ±0.40; ANGLES ±0.50°	DRAWING NUMBER; REV.
THIRD ANGLE PROJECTION; SIZE D; SCALE NONE; SHT 1 OF 2	

NX GENERATED

63.64 iPhone 13, 2 of 2



Copyright © 2025 Apple Inc. All Rights Reserved.

63.65 iPhone 13 mini, 1 of 2

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. NO METAL CONTACT WITH IPHONE.
2. DO NOT OBSTRUCT PORTS.
3. DO NOT OBSTRUCT THE IMAGING FEATURES: FRONT CAMERA, REAR CAMERAS, REAR FLASH.
4. DO NOT OBSTRUCT FORWARD FACING SENSORS.
5. RELATIVE MAGNETIC PERMEABILITY OF ANY METAL USED ON CASE: 1.05 MAX, PER ASTM A342/A342M-14.
6. DO NOT TOUCH GLASS.
7. NO MAGNETS ON REAR OF PRODUCT EXCEPT MAGSAFE MAGNETS.
8. CASE THICKNESS ON BACKSIDE OF PRODUCT: 2.1 mm MAX TO ENSURE FULL FUNCTIONALITY.



CORNER PROFILE (ALL FOUR CORNERS)
DETAIL X



DETAIL Y













PROFILE (ALL SIDES)
DETAIL AA





DETAIL Z

METRIC	Apple Inc.
DRAFTER: APPLE INC. — DATE: 05/14/21	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVERSE ENGINEER OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER: APPLE INC. — DATE: 05/14/21	TITLE: iPhone 13 mini
0 < - < 2 ±0.05 2 < - < 10 ±0.08 10 < - < 50 ±0.10 50 < - < 100 ±0.20 100 < - < 200 ±0.30 200 < - ±0.40 ANGLES ±0.50°	DRAWING NUMBER — REV.
THIRD ANGLE PROJECTION — SIZE D	SCALE NONE — SHT 1 OF 2

NX GENERATED

63.66 iPhone 13 mini, 2 of 2



Copyright © 2025 Apple Inc. All Rights Reserved.

63.67 iPhone 12 Pro Max, 1 of 2

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. NO METAL CONTACT WITH IPHONE.
2. DO NOT OBSTRUCT PORTS.
3. DO NOT OBSTRUCT THE IMAGING FEATURES: FRONT CAMERA, REAR CAMERAS, REAR FLASH.
4. DO NOT OBSTRUCT FORWARD FACING SENSORS.
5. RELATIVE MAGNETIC PERMEABILITY OF ANY METAL USED ON CASE: 1.05 MAX, PER ASTM A342/A342M-14.
6. DO NOT TOUCH GLASS.
7. NO MAGNETS ON REAR OF PRODUCT EXCEPT MAGSAFE MAGNETS.
8. CASE THICKNESS ON BACKSIDE OF PRODUCT: 2.1 mm MAX TO ENSURE FULL FUNCTIONALITY.



CORNER PROFILE (ALL FOUR CORNERS)
DETAIL A



DETAIL D













PROFILE (ALL SIDES)
DETAIL B





DETAIL C

METRIC	Apple Inc.
DRAFTER: APPLE INC. — DATE: 10/13/20	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO COPY OR REPRODUCE IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER: APPLE INC. — DATE: 10/13/20	TITLE: iPhone 12 Pro Max
	DRAWING NUMBER — REV.
THIRD ANGLE PROJECTION — SIZE: D	SCALE: NONE — SHT 1 OF 2

NX GENERATED

63.68 iPhone 12 Pro Max, 2 of 2



63.69 iPhone 12 Pro, 1 of 2

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. NO METAL CONTACT WITH IPHONE.
2. DO NOT OBSTRUCT PORTS.
3. DO NOT OBSTRUCT THE IMAGING FEATURES: FRONT CAMERA, REAR CAMERAS, REAR FLASH.
4. DO NOT OBSTRUCT FORWARD FACING SENSORS.
5. RELATIVE MAGNETIC PERMEABILITY OF ANY METAL USED ON CASE: 1.05 MAX, PER ASTM A342/A342M-14.
6. DO NOT TOUCH GLASS.
7. NO MAGNETS ON REAR OF PRODUCT EXCEPT MAGSAFE MAGNETS.
8. CASE THICKNESS ON BACKSIDE OF PRODUCT: 2.1 mm MAX TO ENSURE FULL FUNCTIONALITY.





















METRIC	Apple Inc.
DRAFTER: APPLE INC. — DATE: 10/13/20	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER: APPLE INC. — DATE: 10/13/20	TITLE: iPhone 12 Pro
	DRAWING NUMBER — REV.
THIRD ANGLE PROJECTION — SIZE: D	SCALE: NONE — SHT 1 OF 2

NX GENERATED

63.70 iPhone 12 Pro, 2 of 2



63.71 iPhone 12, 1 of 2

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. NO METAL CONTACT WITH IPHONE.
2. DO NOT OBSTRUCT PORTS.
3. DO NOT OBSTRUCT THE IMAGING FEATURES: FRONT CAMERA, REAR CAMERAS, REAR FLASH.
4. DO NOT OBSTRUCT FORWARD FACING SENSORS.
5. RELATIVE MAGNETIC PERMEABILITY OF ANY METAL USED ON CASE: 1.05 MAX, PER ASTM A342/A342M-14.
6. DO NOT TOUCH GLASS.
7. NO MAGNETS ON REAR OF PRODUCT EXCEPT MAGSAFE MAGNETS.
8. CASE THICKNESS ON BACKSIDE OF PRODUCT: 2.1 mm MAX TO ENSURE FULL FUNCTIONALITY.



CORNER PROFILE (ALL FOUR CORNERS)
DETAIL A











DETAIL D





PROFILE (ALL SIDES)
DETAIL B





DETAIL C

METRIC		Apple Inc.	
DRAWTER: APPLE INC.	DATE: 10/13/20	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) TO USE IT ONLY FOR THE PURPOSE FOR WHICH IT WAS NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED	
DESIGNER: APPLE INC.	DATE: 10/13/20	TITLE: iPhone 12	
		DRAWING NUMBER	REV.
THIRD ANGLE PROJECTION	SIZE: D	SCALE: NONE	SHT 1 OF 2

NX GENERATED

63.72 iPhone 12, 2 of 2



Copyright © 2025 Apple Inc. All Rights Reserved.

63.73 iPhone 12 mini, 1 of 2

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. NO METAL CONTACT WITH IPHONE.
2. DO NOT OBSTRUCT PORTS.
3. DO NOT OBSTRUCT THE IMAGING FEATURES: FRONT CAMERA, REAR CAMERAS, REAR FLASH.
4. DO NOT OBSTRUCT FORWARD FACING SENSORS.
5. RELATIVE MAGNETIC PERMEABILITY OF ANY METAL USED ON CASE: 1.05 MAX, PER ASTM A342/A342M-14.
6. DO NOT TOUCH GLASS.
7. NO MAGNETS ON REAR OF PRODUCT EXCEPT MAGSAFE MAGNETS.
8. CASE THICKNESS ON BACKSIDE OF PRODUCT: 2.1 mm MAX TO ENSURE FULL FUNCTIONALITY.



CORNER PROFILE (ALL FOUR CORNERS)
DETAIL A









DETAIL D





PROFILE (ALL SIDES)
DETAIL B





DETAIL C

METRIC		Apple Inc.	
DRAFTER: APPLE INC.	DATE: 10/13/20	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED	
DESIGNER: APPLE INC.	DATE: 10/13/20		
		TITLE: iPhone 12 mini	
		DRAWING NUMBER	REV.
THIRD ANGLE PROJECTION	SIZE: D	SCALE: NONE	SHT 1 OF 2

NX GENERATED

Copyright © 2025 Apple Inc. All Rights Reserved.

63.74 iPhone 12 mini, 2 of 2



Copyright © 2025 Apple Inc. All Rights Reserved.

63.75 iPhone SE (3rd generation) and iPhone SE (2nd generation)



Copyright © 2025 Apple Inc. All Rights Reserved.

63.76 iPhone 11 Pro Max



Copyright © 2025 Apple Inc. All Rights Reserved.

63.77 iPhone 11 Pro



63.78 iPhone 11



Copyright © 2025 Apple Inc. All Rights Reserved.

63.79 iPhone XS Max



Copyright © 2025 Apple Inc. All Rights Reserved.

63.80 iPhone XS



Copyright © 2025 Apple Inc. All Rights Reserved.

63.81 iPhone XR



2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

63.82 iPhone X



63.83 iPhone 8 Plus



Copyright © 2025 Apple Inc. All Rights Reserved.

63.84 iPhone 8



Copyright © 2025 Apple Inc. All Rights Reserved.

63.85 iPhone 7 Plus



Copyright © 2025 Apple Inc. All Rights Reserved.

63.86 iPhone 7



Copyright © 2025 Apple Inc. All Rights Reserved.

63.87 iPhone 6s Plus



Copyright © 2025 Apple Inc. All Rights Reserved.

63.88 iPhone 6s



63.89 iPhone 6 Plus



Copyright © 2025 Apple Inc. All Rights Reserved.

63.90 iPhone 6



Copyright © 2025 Apple Inc. All Rights Reserved.

63.91 iPhone SE and iPhone 5s



Copyright © 2025 Apple Inc. All Rights Reserved.

63.92 iPhone 5c



Copyright © 2025 Apple Inc. All Rights Reserved.

63.93 iPhone 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.94 iPad Pro 13-inch (M5) and iPad Pro 13-inch (M4), 1 of 5



63.95 iPad Pro 13-inch (M5) and iPad Pro 13-inch (M4), 2 of 5




MAGNET DETAIL
SECTION AC-AC
SECTION R-R
SECTION S-S
MAGNETIC FLUX KEEP-OUT EXTENDS ENTIRE PRODUCT THICKNESS
MAGNET KEEP-OUT ZONE EXTENDS ABOVE AND BELOW PRODUCT THICKNESS
MAGNETIC FLUX KEEP-OUT 3MM THICK CENTERED IN PRODUCT THICKNESS MAXIMUM 0.25MT IN CROSS-HATCHED REGION
FLUX KEEP-OUT MAXIMUM 0.5MT ANYWHERE ALONG THIS LINE B FIELD DIRECTION
FLUX KEEP-OUT
COMPASS -3.80
COMPASS 264.90
HES1 -93.23
HES2 95.15
HES1 46.60
HES2 36.56
KEEP-OUT -92.21
KEEP-OUT -83.41
KEEP-OUT 90.76
KEEP-OUT 105.46
KEEP-OUT 111.47
HES1 ACTIVATED WITH B-FIELD NORTH IN THIS DIRECTION
0.89 BOTTOM OF HES1 TO OUTSIDE OF HOUSING
2.04 BOTTOM OF HES1 TO OUTSIDE OF HOUSING
Apple Inc.

63.97 iPad Pro 13-inch (M5) and iPad Pro 13-inch (M4), 4 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.98 iPad Pro 13-inch (M5) and iPad Pro 13-inch (M4), 5 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.99 iPad Pro 11-inch (M5) and iPad Pro 11-inch (M4), 1 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.100 iPad Pro 11-inch (M5) and iPad Pro 11-inch (M4), 2 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.


MAGNET DETAIL
SECTION AB - AB
SECTION R - R
SECTION S - S
COMPASS 233.03
COMPASS -3.80
MAGNETIC FLUX KEEP-OUT EXTENDS ENTIRE PRODUCT THICKNESS
MAGNETIC FLUX KEEP-OUT ZONE EXTENDS ABOVE AND BELOW PRODUCT THICKNESS
MAGNETIC FLUX KEEP-OUT 5mT IN CROSS-HATCHED REGION
MAGNETIC FLUX KEEP-OUT 2.5mT IN HATCHED REGION
MAXIMUM 1.3mT ANYWHERE ALONG THIS LINE
B FIELD DIRECTION
FLUX KEEP-OUT
HES1 ACTIVATED WITH B-FIELD NORTH IN THIS DIRECTION
CENTER PIN
Apple Inc.

63.102 iPad Pro 11-inch (M5) and iPad Pro 11-inch (M4), 4 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.103 iPad Pro 11-inch (M5) and iPad Pro 11-inch (M4), 5 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.104 iPad Air 13-inch (M3) and iPad Air 13-inch (M2), 1 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.105 iPad Air 13-inch (M3) and iPad Air 13-inch (M2), 2 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.106 iPad Air 13-inch (M3) and iPad Air 13-inch (M2), 3 of 5



2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

63.107 iPad Air 13-inch (M3) and iPad Air 13-inch (M2), 4 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.108 iPad Air 13-inch (M3) and iPad Air 13-inch (M2), 5 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.109 iPad Air 11-inch (M3) and iPad Air 11-inch (M2), 1 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.110 iPad Air 11-inch (M3) and iPad Air 11-inch (M2), 2 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.111 iPad Air 11-inch (M3) and iPad Air 11-inch (M2), 3 of 5



LOCATION	POLARITY TOWARD OUTER COSMETIC SURFACE OF ENCLOSURE	POLARITY TOWARD INSIDE OF PRODUCT
BV1-11	N	S
BV1-12	S	N
BV1-21	S	N
BV1-22	N	S
BV1-23	S	N
BV1-31	N	S
BV1-32	S	N
BV1-33	N	S
BV1-41	N	S
BV1-42	N	S
BV1-43	S	N
BV2-11	N	S
BV2-12	N	S
BV2-13	S	N
BV2-21	S	N
BV2-22	N	S
BV2-31	S	N
BV2-32	S	N
BV2-41	N	S
BV2-42	S	N
BV2-43	N	S
BV3-11	S	N
BV3-12	N	S
BV3-21	N	S
BV3-22	S	N
BV3-31	S	N
BV3-32	N	S
BV3-41	N	S
BV3-42	S	N
BV3-51	S	N
BV3-52	S	N
BV3-61	N	S
BV3-62	N	S
BV4-11	S	N
BV4-12	N	S
BV4-31	S	N
BV4-32	N	S
BV4-33	S	N
BV4-41	N	S
BV4-42	S	N
BV4-43	S	N
BV4-51	S	N
BV4-52	N	S
BV4-53	N	S
CV1	S	N
CV2	N	S
CV3	N	S
CV4	S	N
HE1	N	S
OR1	S	N
OR2	N	S
OR3	N	S
OR4	S	N
PM-CH-1	S (TOWARD USB-C)	N (TOWARD REAR CAM)
PM-CH-2	S	N
PM-CH-3	N (TOWARD USB-C)	S (TOWARD REAR CAM)
PM-CH-4	N	S
PM-FH-1	N	S
PM-FH-2	S (TOWARD USB-C)	N (TOWARD REAR CAM)
PM-FH-3	S	N
PM-FH-4	N (TOWARD USB-C)	S (TOWARD REAR CAM)
SP-CH-1	S	N
SP-CH-2	N	S
SP-FH-1	N	S
SP-FH-2	S	N
A1	S	N
A2	N	S
A3	S	N
CG1	N (TOP HALF), S (BOTTOM HALF)	S (TOP HALF), N (BOTTOM HALF)
CG2	S (TOP HALF), N (BOTTOM HALF)	N (TOP HALF), S (BOTTOM HALF)

63.112 iPad Air 11-inch (M3) and iPad Air 11-inch (M2), 4 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.113 iPad Air 11-inch (M3) and iPad Air 11-inch (M2), 5 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.114 iPad (A16) and iPad (10th generation), 1 of 7



Copyright © 2025 Apple Inc. All Rights Reserved.

63.115 iPad (A16) and iPad (10th generation), 2 of 7



Copyright © 2025 Apple Inc. All Rights Reserved.

63.116 iPad (A16) and iPad (10th generation), 3 of 7



Copyright © 2025 Apple Inc. All Rights Reserved.

63.117 iPad (A16) and iPad (10th generation), 4 of 7



LOCATION	POLARITY TOWARDS INSIDE OF ENCLOSURE	POLARITY TOWARDS OUTSIDE OF ENCLOSURE
PM-FH-1	N	S
PM-FH-2	SEE DWG DETAIL	SEE DWG DETAIL
PM-FH-3	S	N
PM-CH-1	S	N
PM-CH-2	SEE DWG DETAIL	SEE DWG DETAIL
PM-CH-3	N	S
CG-FH-1	S	N
CG-FH-2	S	N
CG-FH-3	N	S
CG-CH-1	N	S
CG-CH-2	S	N
SP-FH-1	N	S
SP-FH-2	S	N
SP-FH-3	N	S
SP-FH-4	S	N
SP-FH-5	N	S
SP-FH-6	S	N
SP-FH-7	N	S
SP-FH-8	S	N
SP-FH-9	N	S
SP-FH-10	S	N
SP-FH-11	N	S
SP-CH-1	S	N
SP-CH-2	N	S
SP-CH-3	S	N
SP-CH-4	N	S
SP-CH-5	S	N
SP-CH-6	S	N
SP-CH-7	N	S
SP-CH-8	S	N
SP-CH-9	N	S
SP-CH-10	S	N
L-FH-1	N	S
L-FH-2	S	N
L-FH-3	N	S
L-FH-4	S	N
L-CH-1	S	N
L-CH-2	N	S
L-CH-3	S	N
L-CH-4	N	S
C1-1	N	S
C1-2	S	N
C2-1	S	N
C2-2	N	S
C2-3	S	N
C2-4	N	S
C2-5	S	N
C2-6	N	S
C3-1	N	S
C3-2	S	N
C3-3	N	S
C3-4	S	N
C3-5	N	S
C3-6	S	N

LOCATION	STEEL GRADE	SHUNT CENTER Z DIST. TO CG TOP SURFACE (MM)	THICKNESS (Z,MM)	WIDTH (Y,MM)	LENGTH (X,MM)
C3 SHUNT	1010	6.444	0.15	6.84	21.47

Copyright © 2025 Apple Inc. All Rights Reserved.

63.118 iPad (A16) and iPad (10th generation), 5 of 7



LOCATION	POLARITY TOWARDS INSIDE OF ENCLOSURE	POLARITY TOWARDS OUTSIDE OF ENCLOSURE
PM-FH-1	N	S
PM-FH-2	SEE DWG DETAIL	SEE DWG DETAIL
PM-FH-3	S	N
PM-CH-1	S	N
PM-CH-2	SEE DWG DETAIL	SEE DWG DETAIL
PM-CH-3	N	S
CG-FH-1	S	N
CG-FH-2	S	N
CG-FH-3	N	S
CG-CH-1	N	S
CG-CH-2	S	N
SP-FH-1	N	S
SP-FH-2	S	N
SP-FH-3	N	S
SP-FH-4	S	N
SP-FH-5	N	S
SP-FH-6	S	N
SP-FH-7	N	S
SP-FH-8	S	N
SP-FH-9	N	S
SP-FH-10	S	N
SP-FH-11	N	S
SP-CH-1	S	N
SP-CH-2	N	S
SP-CH-3	S	N
SP-CH-4	N	S
SP-CH-5	S	N
SP-CH-6	S	N
SP-CH-7	N	S
SP-CH-8	S	N
SP-CH-9	N	S
SP-CH-10	S	N
L-FH-1	N	S
L-FH-2	S	N
L-FH-3	N	S
L-FH-4	S	N
L-CH-1	S	N
L-CH-2	N	S
L-CH-3	S	N
L-CH-4	N	S
C1-1	N	S
C1-2	S	N
C2-1	S	N
C2-2	N	S
C2-3	S	N
C2-4	N	S
C2-5	S	N
C2-6	N	S
C3-1	N	S
C3-2	S	N
C3-3	N	S
C3-4	S	N
C3-5	N	S
C3-6	S	N

Copyright © 2025 Apple Inc. All Rights Reserved.

63.119 iPad (A16) and iPad (10th generation), 6 of 7



Copyright © 2025 Apple Inc. All Rights Reserved.

63.120 iPad (A16) and iPad (10th generation), 7 of 7



Copyright © 2025 Apple Inc. All Rights Reserved.

63.121 iPad mini (A17 Pro), 1 of 6



Copyright © 2025 Apple Inc. All Rights Reserved.

63.122 iPad mini (A17 Pro), 2 of 6



Copyright © 2025 Apple Inc. All Rights Reserved.

63.123 iPad mini (A17 Pro), 3 of 6



LOCATION	POLARITY TOWARD SURFACE OF ENCLOSURE
PM-FH-3	N
PM-FH-1	S
PM-CH-1	S
PM-CH-3	N
BVA-11	N
BVA-12	N
BVA-13	S
BVA-14	N
BVA-15	S
BVA-21	S
BVA-22	N
BVB-11	N
BVB-12	S
BVB-13	N
BVC-11	S
BVC-12	N
BVC-13	S
BVE-11	S
BVE-12	N
BVE-13	S
BVE-14	N
BVE-15	S
BVE-21	S
BVE-22	N
BVF-11	N
BVF-12	S
BVF-13	N

Copyright © 2025 Apple Inc. All Rights Reserved.

63.124 iPad mini (A17 Pro), 4 of 6

MAGNET, HES, COMPASS DETAIL -PT 2

TOP MODULE MAGNETS
POLARITY AT SURFACE OF COVER GLASS INDICATED



Apple Inc.

NONE

63.125 iPad mini (A17 Pro), 5 of 6



63.126 iPad mini (A17 Pro), 6 of 6



Copyright © 2025 Apple Inc. All Rights Reserved.

63.127 iPad Pro 12.9-inch (6th generation), 1 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.128 iPad Pro 12.9-inch (6th generation), 2 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.129 iPad Pro 12.9-inch (6th generation), 3 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.130 iPad Pro 12.9-inch (6th generation), 4 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.131 iPad Pro 12.9-inch (6th generation), 5 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.132 iPad Pro 11-inch (4th generation), 1 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.133 iPad Pro 11-inch (4th generation), 2 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.134 iPad Pro 11-inch (4th generation), 3 of 5



2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

63.135 iPad Pro 11-inch (4th generation), 4 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.136 iPad Pro 11-inch (4th generation), 5 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.137 iPad Air (5th generation) and iPad Air (4th generation), 1 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.138 iPad Air (5th generation) and iPad Air (4th generation), 2 of 5



DETAIL F



SECTION AD - AD



DETAIL K





DETAIL H

NOTICE OF PROPRIETARY PROPERTY
THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSION OR USE OF THIS DRAWING CONSTITUTES THE RECIPIENT'S AGREEMENT TO THE FOLLOWING:
1. NOT TO REPRODUCE THIS DRAWING IN WHOLE OR IN PART.
2. NOT TO REVEAL THIS DRAWING OR ANY INFORMATION CONTAINED IN IT TO ANYONE OUTSIDE YOUR COMPANY.
3. NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART FOR ANY PURPOSE.
4. ALL RIGHTS RESERVED.
Apple Inc.
SIZE E
DRAWING NUMBER
REV.
SCALE NONE
SHT 2 OF 5

63.139 iPad Air (5th generation) and iPad Air (4th generation), 3 of 5



2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

63.140 iPad Air (5th generation) and iPad Air (4th generation), 4 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.141 iPad Air (5th generation) and iPad Air (4th generation), 5 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.142 iPad mini (6th generation), 1 of 6



 Copyright © 2025 Apple Inc. All Rights Reserved.

63.143 iPad mini (6th generation), 2 of 6



Copyright © 2025 Apple Inc. All Rights Reserved.

63.144 iPad mini (6th generation), 3 of 6



LOCATION	POLARITY TOWARD SURFACE OF ENCLOSURE
PM-FH-3	S
PM-CH-3	S
BVA-11	N
BVA-12	N
BVA-13	S
BVA-14	N
BVA-15	S
BVA-21	S
BVA-22	N
BVB-11	N
BVB-12	S
BVB-13	N
BVC-11	S
BVC-12	N
BVC-13	S
BVE-11	S
BVE-12	N
BVE-13	S
BVE-14	N
BVE-15	S
BVE-21	S
BVE-22	N
BVF-11	N
BVF-12	S
BVF-13	N

63.145 iPad mini (6th generation), 4 of 6



Copyright © 2025 Apple Inc. All Rights Reserved.

63.146 iPad mini (6th generation), 5 of 6



 Copyright © 2025 Apple Inc. All Rights Reserved.

63.147 iPad mini (6th generation), 6 of 6



Copyright © 2025 Apple Inc. All Rights Reserved.

63.148 iPad (9th generation), iPad (8th generation) and iPad (7th generation), 1 of 4



63.149 iPad (9th generation), iPad (8th generation) and iPad (7th generation), 2 of 4



63.150 iPad (9th generation), iPad (8th generation) and iPad (7th generation), 3 of 4



63.151 iPad (9th generation), iPad (8th generation) and iPad (7th generation), 4 of 4



63.152 iPad Pro 12.9-inch (5th generation), 1 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.153 iPad Pro 12.9-inch (5th generation), 2 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.154 iPad Pro 12.9-inch (5th generation), 3 of 5



63.155 iPad Pro 12.9-inch (5th generation), 4 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.156 iPad Pro 12.9-inch (5th generation), 5 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.157 iPad Pro 11-inch (3rd generation), 1 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.158 iPad Pro 11-inch (3rd generation), 2 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.159 iPad Pro 11-inch (3rd generation), 3 of 5



2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

63.160 iPad Pro 11-inch (3rd generation), 4 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.161 iPad Pro 11-inch (3rd generation), 5 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.162 iPad Pro 12.9-inch (4th generation), 1 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.163 iPad Pro 12.9-inch (4th generation), 2 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.164 iPad Pro 12.9-inch (4th generation), 3 of 5



63.165 iPad Pro 12.9-inch (4th generation), 4 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.166 iPad Pro 12.9-inch (4th generation), 5 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.167 iPad Pro 11-inch (2nd generation), 1 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.168 iPad Pro 11-inch (2nd generation), 2 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.169 iPad Pro 11-inch (2nd generation), 3 of 5



2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

63.170 iPad Pro 11-inch (2nd generation), 4 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.171 iPad Pro 11-inch (2nd generation), 5 of 5



Copyright © 2025 Apple Inc. All Rights Reserved.

63.172 iPad Air (3rd generation), 1 of 3



Copyright © 2025 Apple Inc. All Rights Reserved.

63.173 iPad Air (3rd generation), 2 of 3



63.174 iPad Air (3rd generation), 3 of 3



Copyright © 2025 Apple Inc. All Rights Reserved.

63.175 iPad Air (3rd generation) with Cellular, 1 of 3



Copyright © 2025 Apple Inc. All Rights Reserved.

63.176 iPad Air (3rd generation) with Cellular, 2 of 3



63.177 iPad Air (3rd generation) with Cellular, 3 of 3



Copyright © 2025 Apple Inc. All Rights Reserved.

63.178 iPad mini (5th generation), 1 of 3



Copyright © 2025 Apple Inc. All Rights Reserved.

63.179 iPad mini (5th generation), 2 of 3



Copyright © 2025 Apple Inc. All Rights Reserved.

63.180 iPad mini (5th generation), 3 of 3



63.181 iPad mini (5th generation) with Cellular, 1 of 3



Copyright © 2025 Apple Inc. All Rights Reserved.

63.182 iPad mini (5th generation) with Cellular, 2 of 3



63.183 iPad mini (5th generation) with Cellular, 3 of 3



Copyright © 2025 Apple Inc. All Rights Reserved.

63.184 iPad Pro 12.9-inch (3rd generation), 1 of 3



 Copyright © 2025 Apple Inc. All Rights Reserved.

63.185 iPad Pro 12.9-inch (3rd generation), 2 of 3



Copyright © 2025 Apple Inc. All Rights Reserved.

63.186 iPad Pro 12.9-inch (3rd generation), 3 of 3



Copyright © 2025 Apple Inc. All Rights Reserved.

63.187 iPad Pro 11-inch (1st generation), 1 of 3



Copyright © 2025 Apple Inc. All Rights Reserved.

63.188 iPad Pro 11-inch (1st generation), 2 of 3



2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

63.189 iPad Pro 11-inch (1st generation), 3 of 3



Copyright © 2025 Apple Inc. All Rights Reserved.

63.190 iPad Pro 12.9-inch (2nd generation)



Copyright © 2025 Apple Inc. All Rights Reserved.

63.191 iPad Pro 12.9-inch (2nd generation) with Cellular



Copyright © 2025 Apple Inc. All Rights Reserved.

63.192 iPad Pro 12.9-inch (2nd generation) Magnet/Hall Effect Sensors, 1 of 2



Copyright © 2025 Apple Inc. All Rights Reserved.

63.193 iPad Pro 12.9-inch (2nd generation) Magnet/Hall Effect Sensors, 2 of 2



Copyright © 2025 Apple Inc. All Rights Reserved.

63.194 iPad Pro 10.5-inch



Copyright © 2025 Apple Inc. All Rights Reserved.

63.195 iPad Pro 10.5-inch with Cellular



Copyright © 2025 Apple Inc. All Rights Reserved.

63.196 iPad Pro 10.5-inch Magnet/Hall Effect Sensors, 1 of 2



Copyright © 2025 Apple Inc. All Rights Reserved.

63.197 iPad Pro 10.5-inch Magnet/Hall Effect Sensors, 2 of 2



63.198 iPad (5th and 6th generation) with Cellular



Copyright © 2025 Apple Inc. All Rights Reserved.

63.199 iPad (5th and 6th generation) Magnet/Hall Effect Sensors, 1 of 2



63.200 iPad (5th and 6th generation) Magnet/Hall Effect Sensors, 2 of 2



Copyright © 2025 Apple Inc. All Rights Reserved.

63.201 iPad Pro 9.7-inch



Copyright © 2025 Apple Inc. All Rights Reserved.

63.202 iPad Pro 9.7-inch with Cellular



Copyright © 2025 Apple Inc. All Rights Reserved.

63.203 iPad Pro 9.7-inch Magnet/Hall Effect Sensors, 1 of 2



63.204 iPad Pro 9.7-inch Magnet/Hall Effect Sensors, 2 of 2



63.205 iPad Pro 12.9-inch (1st generation)



Copyright © 2025 Apple Inc. All Rights Reserved.

63.206 iPad Pro 12.9-inch (1st generation) with Cellular



63.207 iPad Pro 12.9-inch (1st generation) Magnet/Hall Effect Sensors, 1 of 2



63.208 iPad Pro 12.9-inch (1st generation) Magnet/Hall Effect Sensors, 2 of 2







SPINE MAGNETS DETAIL
POLARITY SHOWN NORMAL TO HOUSING SURFACE AT CONTACT C/L (19.3° FROM HORIZONTAL)
DIMENSIONS TO CENTER SIDE CONTACT C/L
"N" = NORTH
"S" = SOUTH

NOTICE OF PROPRIETARY PROPERTY:
THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING:
(i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE
(ii) NOT TO REPRODUCE OR COPY IT
(iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART
(iv) ALL RIGHTS RESERVED

Apple Inc.
SIZE D | DRAWING NUMBER | REV.
SCALE: NONE | SHT 3 OF 3

63.209 iPad mini 4



Copyright © 2025 Apple Inc. All Rights Reserved.

63.210 iPad mini 4 with Cellular



Copyright © 2025 Apple Inc. All Rights Reserved.

63.211 iPad mini 4 Magnet/Hall Effect Sensors



63.212 iPad Air 2



63.213 iPad Air 2 with Cellular



Copyright © 2025 Apple Inc. All Rights Reserved.

63.214 iPad mini 3 and iPad mini 2



63.215 iPad mini 3 and iPad mini 2 with Cellular



63.216 iPad Air



63.217 iPad Air with Cellular



Copyright © 2025 Apple Inc. All Rights Reserved.

63.218 iPad mini



Copyright © 2025 Apple Inc. All Rights Reserved.

63.219 iPad mini with Cellular



Copyright © 2025 Apple Inc. All Rights Reserved.

63.220 iPad (4th generation)



Copyright © 2025 Apple Inc. All Rights Reserved.

63.221 iPad (4th generation) with Cellular



Copyright © 2025 Apple Inc. All Rights Reserved.

63.222 iPod touch (7th generation) and iPod touch (6th generation)



63.223 iPod touch (5th generation)



Copyright © 2025 Apple Inc. All Rights Reserved.

63.224 Apple Watch Ultra 3 & Apple Watch Ultra 2, 1 of 3

NOTES:

1. CASE DOES NOT INTERFERE WITH CLICK OR ROTATION FUNCTION OF DIGITAL CROWN
   CASE DOES NOT APPLY FORCE ON DIGITAL CROWN
   CASE DOES NOT OBSTRUCT FACE OF CROWN
2. CASE DOES NOT OBSTRUCT THE WATCH ACOUSTIC OPENINGS AND ALTIMETER
   AND MUST NOT DEGRADE ACOUSTIC OR WATER EJECTION PERFORMANCE
3. CASE DOES NOT OBSTRUCT THE WATCH CHARGING INTERFACE
4. CASE DOES NOT OBSTRUCT THE WATCH OPTICAL SENSORS
5. CASE DOES NOT EXTEND INTO WATCH SENSOR WINDOWS
6. CASE DOES NOT CONTACT THE WATCH COVER GLASS
   AND DOES NOT OBSTRUCT THE GAP AROUND THE COVER GLASS
7. CASE DOES NOT CONTACT ELECTRICAL SENSORS
8. CASE DOES NOT INTERFERE WITH CLICK FUNCTION OF BUTTON
9. NO METAL CASES ALLOWED DUE TO ANTENNA FUNCTION.
   CASE MUST BE MADE OF RF-TRANSPARENT MATERIAL
10. CASE DOES NOT CONTAIN FERROMAGNETIC MATERIAL
11. CASE DOES NOT TRAP WATER BETWEEN CASE AND ANTENNA SPLIT

OVERALL DIMENSIONS AND CALLOUTS



NOTICE OF PROPRIETARY PROPERTY:
THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING:
(i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE
(ii) NOT TO REPRODUCE OR COPY IT
(iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART
(iv) ALL RIGHTS RESERVED

Apple Inc.

SIZE	DRAWING NUMBER	REV.
D		01

SCALE: NONE SHT 1 OF 3

63.225 Apple Watch Ultra 3 & Apple Watch Ultra 2, 2 of 3



Copyright © 2025 Apple Inc. All Rights Reserved.

63.226 Apple Watch Ultra 3 & Apple Watch Ultra 2, 3 of 3



Copyright © 2025 Apple Inc. All Rights Reserved.

63.227 Apple Watch Series 11 & Apple Watch Series 10, 46 mm

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. CASE DOES NOT INTERFERE WITH CLICK OR ROTATION FUNCTION OF DIGITAL CROWN
   CASE DOES NOT APPLY FORCE ON DIGITAL CROWN
   CASE DOES NOT OBSTRUCT FACE OF CROWN
2. CASE DOES NOT OBSTRUCT THE WATCH ACOUSTIC OPENINGS AND ALTIMETER AND MUST NOT DEGRADE ACOUSTIC OR WATER EJECTION PERFORMANCE
3. NO METAL CASES ALLOWED DUE TO ANTENNA FUNCTION
4. CASE DOES NOT OBSTRUCT THE WATCH CHARGING INTERFACE
5. CASE DOES NOT OBSTRUCT THE WATCH OPTICAL SENSORS
6. CASE DOES NOT EXTEND BEYOND WATCH SENSOR WINDOWS
7. CASE DOES NOT CONTACT THE WATCH COVER GLASS
8. CASE DOES NOT CONTACT ELECTRICAL SENSORS
9. CASE DOES NOT INTERFERE WITH CLICK FUNCTION OF BUTTON
10. CASE DOES NOT CONTAIN FERROMAGNETIC MATERIAL



POINT	X	Y
D-A	3.66	17.97
D-B	3.71	12.95
D-C	3.98	9.95
D-D	4.65	7.83
D-E	5.82	6.12
D-F	7.45	4.84
D-G	9.49	4.07
D-H	12.31	3.73
D-I	16.10	3.66





SECTION A - A









POINT	X	Y
A	0.00	23.00
B	0.02	13.99
C	0.34	9.54
D	1.39	6.17
E	3.38	3.38
F	6.17	1.39
G	9.53	0.34
H	13.69	0.02
I	19.88	0.00



SECTION B - B



POINT	Y	Z
S-A	6.83	9.70
S-B	5.61	9.69
S-C	4.32	9.60
S-D	3.05	9.29
S-E	1.86	8.63
S-F	0.88	7.61
S-G	0.23	6.31
S-H	0.00	4.85
S-I	0.23	3.39
S-K	0.88	2.09
S-J	1.86	1.07
S-L	3.05	0.41
S-M	4.32	0.10
S-N	5.61	0.01
S-O	6.83	0.00



NOTICE OF PROPRIETARY PROPERTY:
THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING:
(i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE
(ii) NOT TO REPRODUCE OR COPY IT
(iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART
(iv) ALL RIGHTS RESERVED

Apple Inc.
SIZE D | DRAWING NUMBER | REV.
SCALE: NONE | SHT 1 OF 1

NX GENERATED

63.228 Apple Watch Series 11 & Apple Watch Series 10, 42 mm



POINT	X	Y
D-A	3.64	14.03
D-B	3.68	11.75
D-C	3.93	9.05
D-D	4.54	7.17
D-E	5.61	5.67
D-F	7.11	4.57
D-G	9.00	3.94
D-H	11.81	3.67
D-I	14.22	3.64

POINT	X	Y
A	0.00	21.03
B	0.02	13.03
C	0.35	8.42
D	1.57	5.03
E	3.19	2.95
F	5.33	1.40
G	8.78	0.29
H	13.22	0.01
I	18.22	0.00

POINT	Y	Z
S-A	6.83	9.70
S-B	5.61	9.69
S-C	4.32	9.60
S-D	3.05	9.29
S-E	1.86	8.63
S-F	0.88	7.61
S-G	0.23	6.31
S-H	0.00	4.85
S-I	0.23	3.39
S-K	0.88	2.09
S-J	1.86	1.07
S-L	3.05	0.41
S-M	4.32	0.10
S-N	5.61	0.01
S-O	6.83	0.00

NOTICE OF PROPRIETARY PROPERTY:
THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING:
(i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE
(ii) NOT TO REPRODUCE OR COPY IT
(iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART
(iv) ALL RIGHTS RESERVED

63.229 Apple Watch SE 3 & Apple Watch SE 2, 44 mm



Copyright © 2025 Apple Inc. All Rights Reserved.

63.230 Apple Watch SE 3 & Apple Watch SE 2, 40 mm



Copyright © 2025 Apple Inc. All Rights Reserved.

63.231 Apple Watch Series 9, 45 mm



63.232 Apple Watch Series 9, 41 mm



63.233 Apple Watch Ultra, 1 of 3

NOTES:

1. CASE DOES NOT INTERFERE WITH CLICK OR ROTATION FUNCTION OF DIGITAL CROWN
   CASE DOES NOT APPLY FORCE ON DIGITAL CROWN
   CASE DOES NOT OBSTRUCT FACE OF CROWN
2. CASE DOES NOT OBSTRUCT THE WATCH ACOUSTIC OPENINGS AND ALTIMETER AND MUST NOT DEGRADE ACOUSTIC OR WATER EJECTION PERFORMANCE
3. CASE DOES NOT OBSTRUCT THE WATCH CHARGING INTERFACE
4. CASE DOES NOT OBSTRUCT THE WATCH OPTICAL SENSORS
5. CASE DOES NOT EXTEND INTO WATCH SENSOR WINDOWS
6. CASE DOES NOT CONTACT THE WATCH COVER GLASS
7. CASE DOES NOT CONTACT ELECTRICAL SENSORS
8. CASE DOES NOT INTERFERE WITH CLICK FUNCTION OF BUTTON
9. NO METAL CASES ALLOWED DUE TO ANTENNA FUNCTION
10. CASE DOES NOT CONTAIN FERROMAGNETIC MATERIAL

OVERALL DIMENSIONS AND CALLOUTS



NOTICE OF PROPRIETARY PROPERTY:
THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING:
(i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE
(ii) NOT TO REPRODUCE OR COPY IT
(iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART
(iv) ALL RIGHTS RESERVED

Apple Inc.

SIZE	DRAWING NUMBER	REV.
D	APPLE WATCH ULTRA	01
SCALE: NONE	SHT 1 OF 3	

63.234 Apple Watch Ultra, 2 of 3

RIGHT SIDE PROFILES



OTHER PROFILES

CORNER PROFILES
VIEWED FROM TOP

SIDE PROFILE
VIEWED FROM RIGHT

CROWN SCOOP PROFILE
VIEWED FROM TOP



NOTICE OF PROPRIETARY PROPERTY:
THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING:
(i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE
(ii) NOT TO REPRODUCE OR COPY IT
(iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART
(iv) ALL RIGHTS RESERVED

Apple Inc.

SIZE	DRAWING NUMBER	REV.
D	APPLE WATCH ULTRA	01
SCALE:	NONE	SHT 2 OF 3

Copyright © 2025 Apple Inc. All Rights Reserved.

63.235 Apple Watch Ultra, 3 of 3



Copyright © 2025 Apple Inc. All Rights Reserved.

63.236 Apple Watch Series 8, 45 mm



Copyright © 2025 Apple Inc. All Rights Reserved.

63.237 Apple Watch Series 8, 41 mm



Copyright © 2025 Apple Inc. All Rights Reserved.

63.238 Apple Watch Series 7, 45 mm



Copyright © 2025 Apple Inc. All Rights Reserved.

63.239 Apple Watch Series 7, 41 mm



63.240 Apple Watch Series 6, 44 mm



Copyright © 2025 Apple Inc. All Rights Reserved.

63.241 Apple Watch Series 6, 40 mm



Copyright © 2025 Apple Inc. All Rights Reserved.

63.242 Apple Watch SE, 44 mm



Copyright © 2025 Apple Inc. All Rights Reserved.

63.243 Apple Watch SE, 40 mm



Copyright © 2025 Apple Inc. All Rights Reserved.

63.244 Apple Watch Series 5, 44 mm



63.245 Apple Watch Series 5, 40 mm



Copyright © 2025 Apple Inc. All Rights Reserved.

63.246 Apple Watch Series 5 Ceramic, 44 mm



63.247 Apple Watch Series 5 Ceramic, 40 mm



Copyright © 2025 Apple Inc. All Rights Reserved.

63.248 Apple Watch Series 4, 44 mm



63.249 Apple Watch Series 4, 40 mm



Copyright © 2025 Apple Inc. All Rights Reserved.

63.250 Apple Watch Series 3 Ceramic, 42 mm



Copyright © 2025 Apple Inc. All Rights Reserved.

63.251 Apple Watch Series 3 Ceramic, 38 mm



Copyright © 2025 Apple Inc. All Rights Reserved.

63.252 Apple Watch Series 3 Metal, 42 mm



Copyright © 2025 Apple Inc. All Rights Reserved.

63.253 Apple Watch Series 3 Metal, 38 mm



63.254 Apple Watch Series 2 Ceramic, 42 mm



Copyright © 2025 Apple Inc. All Rights Reserved.

63.255 Apple Watch Series 2 Ceramic, 38 mm



Copyright © 2025 Apple Inc. All Rights Reserved.

63.256 Apple Watch Series 2 Metal, 42 mm



63.257 Apple Watch Series 2 Metal, 38 mm



Copyright © 2025 Apple Inc. All Rights Reserved.

63.258 Apple Watch Series 1 and Apple Watch (1st generation), 42 mm



63.259 Apple Watch Series 1 and Apple Watch (1st generation), 38 mm



2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

63.260 Apple Vision Pro, 1 of 8

REV	ECO#	DESCRIPTION OF REVISION

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. NO METAL CONTACT WITH PRODUCT.
2. DO NOT OBSTRUCT PORTS.
3. CASE DOES NOT INTERFERE WITH CLICK OR ROTATION FUNCTION OF BUTTON, DIGITAL CROWN, OR FIT DIAL. CASE DOES NOT APPLY FORCE ON BUTTON, DIGITAL CROWN, OR FIT DIAL.
4. 2N MAX ALLOWABLE FORCE APPLIED TO OUTER TEXTILE/FACETRACK PERIMETER.
5. RELATIVE MAGNETIC PERMEABILITY OF ANY METAL USED ON CASE: 1.05 MAX, PER ASTM A342/A342M-14.
6. MINIMIZE CONTACT WITH GLASS ON DISPLAY, OPTICAL MODULES, AND CLIP-ON LENSES. IF CONTACT IS REQUIRED, USE SOFT NON-ABRASIVE MATERIALS TO AVOID SCRATCHING.
7. DO NOT TOUCH LIGHTPIPE.
8. 4N MAX ALLOWABLE FORCE APPLIED TO CUSHION FROM USER SIDE.

UNIT SHALL NOT BE POWERED ON OR UNDER OPERATING CONDITIONS WHILE STORED INSIDE THE CASE.

















TABLE OF CONTENTS	
SHEET	CONTENT
1	OVERVIEW
2	LIGHTSEAL BOUNDARY
3	LIGHTSEAL CONTACT
4	DUAL LOOP BAND
5	VISION PRO SMALL SOLO KNIT BAND
6	VISION PRO LARGE SOLO KNIT BAND
7	VISION PRO SMALL DUAL KNIT BAND
8	VISION PRO LARGE DUAL KNIT BAND

METRIC

Apple Inc.

DRAWTER DATE

DESIGNER DATE

DIMENSIONS ARE IN MILLIMETERS
TOLERANCES

DO NOT SCALE DRAWINGS

THIRD ANGLE PROJECTION

NOTICE OF PROPRIETARY PROPERTY:
THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING:
(i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE
(ii) NOT TO REPRODUCE OR COPY IT
(iii) NOT TO REVERSE ENGINEER OR PUBLISH IT IN WHOLE OR PART
(iv) ALL RIGHTS RESERVED

TITLE

VISION PRO
STORAGE CASE
DESIGN GUIDE

DRAWING NUMBER REV.

SIZE D

SCALE NONE SHT OF

NX GENERATED

63.261 Apple Vision Pro, 2 of 8

LIGHT SEAL BOUNDARY REQUIREMENTS



DEEPEST LIGHT SEAL



WIDEST • TALLEST LIGHT SEAL

DESCRIPTION	LIGHTSEAL + FACE CUSHION (mm)		
	WIDTH	DEPTH	HEIGHT
LARGEST IN ALL DIMENSIONS	161.35 MMC	98.4 MMC	104.26 MMC
SMALLEST IN ALL DIMENSIONS	147.57 LMC	72.38 MMC	94.07 LMC





NOTICE OF PROPRIETARY PROPERTY:
THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING:
(i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE
(ii) NOT TO REPRODUCE OR COPY IT
(iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART
(iv) ALL RIGHTS RESERVED

Apple Inc.

SIZE D | DRAWING NUMBER | REV.

SCALE: NONE | SHT | OF

NX GENERATED

63.262 Apple Vision Pro, 3 of 8

LIGHT SEAL CONTACT REQUIREMENTS
VISION PRO OMITTED FOR CLARITY





NOTICE OF PROPRIETARY PROPERTY:
THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING
(i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE
(ii) NOT TO REPRODUCE OR COPY IT
(iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART
(iv) ALL RIGHTS RESERVED

Apple Inc.
SIZE D | DRAWING NUMBER | REV.
SCALE: NONE | SHT | OF

NX GENERATED

63.263 Apple Vision Pro, 4 of 8



	SMALL	MEDIUM	LARGE
UPPER BAND LENGTH (MM)	335 ± 0.7%	343 ± 0.7%	352 ± 0.7%
LOWER BAND LENGTH (MM)	328 ± 1.5%	366 ± 1.5%	411 ± 1.5%

Copyright © 2025 Apple Inc. All Rights Reserved.

63.264 Apple Vision Pro, 5 of 8

VISION PRO • SMALL SOLO KNIT BAND BOUNDARY REQUIREMENTS



DEEP LIGHT SEAL SMALL BAND



WIDE LIGHT SEAL SMALL BAND



LIGHTSEAL OMITTED FOR CLARITY





NOTICE OF PROPRIETARY PROPERTY:
THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING:
(i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE
(ii) NOT TO REPRODUCE OR COPY IT
(iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART
(iv) ALL RIGHTS RESERVED

Apple Inc.
SIZE D
DRAWING NUMBER
REV.
SCALE: NONE
SHT
OF

NX GENERATED

63.265 Apple Vision Pro, 6 of 8



63.266 Apple Vision Pro, 7 of 8



Copyright © 2025 Apple Inc. All Rights Reserved.

63.267 Apple Vision Pro, 8 of 8



63.268 Apple Vision Pro Battery

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. DO NOT OBSTRUCT PORT.
2. DO NOT OBSTRUCT LED.
3. NO METAL CONTACT.
4. BEND RADIUS REQUIREMENT.
5. RECOMMEND TO MAINTAIN AT LEAST 25% SURFACE EXPOSURE FOR HEAT DISSIPATION.















METRIC	Apple Inc.
DRAFTER / DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVERSE ENGINEER OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER / DATE	
DIMENSIONS ARE IN MILLIMETERS TOLERANCES	TITLE: VISION PRO BATTERY
DO NOT SCALE DRAWINGS	DRAWING NUMBER / REV.
THIRD ANGLE PROJECTION	SIZE D / SCALE NONE / SHT 1 OF 1

NX GENERATED

Copyright © 2025 Apple Inc. All Rights Reserved.

63.269 Apple Vision Pro Audio Strap

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. DIMENSIONS REFER TO LEFT AUDIO STRAP. RIGHT AUDIO STRAP IS MIRRORED UNLESS OTHERWISE SPECIFIED.
2. DO NOT OBSTRUCT PORTS.
3. NO METAL CONTACT WITH ELASTOMER PORTION OF AUDIO STRAP.
4. MATERIAL CONTACT WITH CONNECTOR AND FACE PLATE MAX HARDNESS: 320 HV.
5. MAXIMUM NORMAL PULL FORCE ON CONNECTOR: 350 N.



LEFT AUDIO STRAP

RIGHT AUDIO STRAP









METRIC	Apple Inc.
DRAFTER / DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER / DATE	
DIMENSIONS ARE IN MILLIMETERS TOLERANCES	TITLE: AUDIO STRAPS FOR VISION PRO
DO NOT SCALE DRAWING	DRAWING NUMBER / REV.
THIRD ANGLE PROJECTION	SIZE D / SCALE NONE / SHT 1 OF 1

NX GENERATED

Copyright © 2025 Apple Inc. All Rights Reserved.

63.270 ZEISS Optical Inserts, 1 of 4

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. DIMENSIONS REFER TO LEFT OPTICAL INSERT WITH RIGHT SIDE OPTICAL INSERT BEING A SYMMETRICAL PART UNLESS OTHERWISE SPECIFIED.
2. NO METAL CONTACT WITH PRODUCT.

[3] MINIMIZE CONTACT WITH LENS.

OVERALL DIMENSIONS AND CALLOUTS





LEFT OPTICAL INSERT



RIGHT OPTICAL INSERT





METRIC	Apple Inc.
DRAWTER / DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER / DATE	
DIMENSIONS ARE IN MILLIMETERS TOLERANCES	TITLE: OPTICAL INSERTS FOR VISION PRO
DO NOT SCALE DRAWINGS	DRAWING NUMBER / REV.
THIRD ANGLE PROJECTION / SIZE D	SCALE: NONE / SHT 1 OF 4

NX GENERATED

63.271 ZEISS Optical Inserts, 2 of 4



Copyright © 2025 Apple Inc. All Rights Reserved.

63.272 ZEISS Optical Inserts, 3 of 4

FRAME PROFILE



LENS DIMENSIONS



NOTICE OF PROPRIETARY PROPERTY:
THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING:
(i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE
(ii) NOT TO REPRODUCE OR COPY IT
(iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART
(iv) ALL RIGHTS RESERVED

Apple Inc.
SIZE D | DRAWING NUMBER | REV.
SCALE: NONE | SHT 3 OF 4

NX GENERATED

63.273 ZEISS Optical Inserts, 4 of 4

LEFT MAGNET ARRAY



RIGHT MAGNET ARRAY



MAGNET POLARITY FOR EACH MAGNET		
MAGNET	POLARITY TOWARD TOP SIDE	POLARITY TOWARD BOTTOM SIDE
M1	N	S
M2		
M3		
M4		
M5		
M6		
M7		
M8	S	N
M9		
M10		
M11		
M12		
M13		
M14		
M15		
M16		
M17		
M18	N	S
M19		
M20		
M21		
M22	S	N
M23		
M24		
M25		
M26		
M27		
M28		
M29	N	S
M30		
M31		

MAGNET POLARITY FOR EACH MAGNET		
MAGNET	POLARITY TOWARD TOP SIDE	POLARITY TOWARD BOTTOM SIDE
M1	S	N
M2		
M5		
M8		
M9		
M12		
M15		
M18	N	S
M19		
M22		
M23		
M26		
M29		
M30		
M15		
M16		
M17		
M18	S	N
M19		
M20		
M21		
M22	N	S
M23		
M24		
M25		
M26		
M27		
M28		
M29	S	N
M30		
M31		

NOTICE OF PROPRIETARY PROPERTY:
THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING
(i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE
(ii) NOT TO REPRODUCE OR COPY IT
(iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART
(iv) ALL RIGHTS RESERVED

Apple Inc.
SIZE D | DRAWING NUMBER | REV.
SCALE: NONE | SHT 4 OF 4

NX GENERATED

63.274 MagSafe Charging Case for AirPods Pro 3, 1 of 3

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. ACCESSORIES INTRUDING INTO SHADED REGIONS WILL NEGATIVELY AFFECT PRODUCT PERFORMANCE.
2. TO ENSURE FULL FUNCTIONALITY, DO NOT OBSTRUCT THIS AREA WITH METAL OR OTHER CONDUCTIVE MATERIAL.
3. TO ENSURE FULL FUNCTIONALITY WITH MINIMAL IMPACT TO QI CHARGING PERFORMANCE, MINIMIZE ANY MATERIAL THICKNESS.
4. TO ENABLE CHARGING VIA APPLE WATCH CHARGER, IT IS RECOMMENDED THERE BE NO MATERIAL BETWEEN BACK OF DEVICE AND WATCH CHARGER.
5. PROTECTIVE CASES OR COVERS MAY DETUNE OR IMPACT RF & WIRELESS CHARGING PERFORMANCE.
   IMPACT IS HIGHLY DEPENDENT ON MATERIAL AND MATERIAL THICKNESS.
   HIGHLY RECOMMEND AVOIDING METAL MATERIAL AND FOLLOWING GUIDELINES IN THIS DOCUMENT TO MINIMIZE IMPACT.



SECTION A - A











DETAIL B
SCALE 5:1



SECTION C - C
LANYARD LOOP INTERNAL DIMENSIONS

METRIC	Apple Inc.
DRAWTER / DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER / DATE	
DIMENSIONS ARE IN MILLIMETERS TOLERANCES	TITLE
DRAWING NUMBER	REV.
DO NOT SCALE DRAWINGS	
THIRD ANGLE PROJECTION	SIZE D / SCALE NONE / SHT 1 OF 3

NX GENERATED

63.275 MagSafe Charging Case for AirPods Pro 3, 2 of 3



63.276 MagSafe Charging Case for AirPods Pro 3, 3 of 3



NOTICE OF PROPRIETARY PROPERTY:
THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING:
(i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE
(ii) NOT TO REPRODUCE OR COPY IT
(iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART
(iv) ALL RIGHTS RESERVED

Apple Inc.
SIZE D | DRAWING NUMBER | REV.
SCALE: NONE | SHT 3 OF 3

NX GENERATED

63.277 AirPods Pro 3

NOTES: (UNLESS OTHERWISE SPECIFIED)

[1] ACCESSORIES INTRUDING INTO SHADED REGION WILL NEGATIVELY AFFECT PRODUCT PERFORMANCE

[2] ACCESSORIES MUST NOT COVER THESE METAL SURFACES













METRIC	Apple Inc.
DRAFTER / DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER / DATE	TITLE
DIMENSIONS ARE IN MILLIMETERS TOLERANCES X.X ±0.2 X.XX ±0.10 X.XXX ±0.050 ANGLES ±0.5° DO NOT SCALE DRAWINGS	DRAWING NUMBER / REV.
THIRD ANGLE PROJECTION / SIZE C	SCALE NONE / SHT 1 OF 1

NX GENERATED

Copyright © 2025 Apple Inc. All Rights Reserved.

63.278 Wireless Charging Case (USB-C) for AirPods 4, 1 of 3

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. ACCESSORIES INTRUDING INTO SHADED REGIONS WILL NEGATIVELY AFFECT PRODUCT PERFORMANCE.
2. TO ENSURE FULL FUNCTIONALITY, DO NOT OBSTRUCT THIS AREA WITH METAL OR OTHER CONDUCTIVE MATERIAL.
3. TO ENSURE FULL FUNCTIONALITY WITH MINIMAL IMPACT TO QI CHARGING PERFORMANCE, MINIMIZE ANY MATERIAL THICKNESS.
4. TO ENABLE CHARGING VIA APPLE WATCH CHARGER, IT IS RECOMMENDED THERE BE NO MATERIAL BETWEEN BACK OF DEVICE AND WATCH CHARGER.
5. PROTECTIVE CASES OR COVERS MAY DETUNE OR IMPACT RF & WIRELESS CHARGING PERFORMANCE.
   IMPACT IS HIGHLY DEPENDENT ON MATERIAL AND MATERIAL THICKNESS.
   HIGHLY RECOMMEND AVOIDING METAL MATERIAL AND FOLLOWING GUIDELINES IN THIS DOCUMENT TO MINIMIZE IMPACT.
6. PROTECTIVE CASES OR COVERS MAY IMPACT PAIRING AND FACTORY RESET FUNCTIONS ON CHARGING CASE FOR AIRPODS 4.
7. PROTECTIVE CASES OR COVERS MAY IMPACT PAIRING, FACTORY RESET, AND SERIAL NUMBER LOOKUP FUNCTIONS ON WIRELESS CHARGING CASE FOR AIRPODS 4 (ANC).
8. ONLY APPLICABLE TO WIRELESS CHARGING CASE FOR AIRPODS 4 (ANC).



SECTION A - A









METRIC	Apple Inc.
DRAFTER / DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER / DATE	
DIMENSIONS ARE IN MILLIMETERS TOLERANCES	TITLE: CHARGING CASE FOR AIRPODS 4 AND WIRELESS CHARGING CASE FOR AIRPODS 4 (ANC)
DO NOT SCALE DRAWINGS	DRAWING NUMBER / REV.
THIRD ANGLE PROJECTION / SIZE D	SCALE: NONE / SHT 1 OF 3

NX GENERATED

63.279 Wireless Charging Case (USB-C) for AirPods 4, 2 of 3



63.280 Wireless Charging Case (USB-C) for AirPods 4, 3 of 3





NOTICE OF PROPRIETARY PROPERTY:
THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING:
(i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE
(ii) NOT TO REPRODUCE OR COPY IT
(iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART
(iv) ALL RIGHTS RESERVED

Apple Inc.

SIZE D | DRAWING NUMBER | REV.

SCALE: NONE | SHT 3 OF 3

NX GENERATED

63.281 AirPods 4

NOTES: (UNLESS OTHERWISE SPECIFIED)

[1] ACCESSORIES INTRUDING INTO SHADED REGIONS WILL NEGATIVELY AFFECT PRODUCT PERFORMANCE

[2] ACCESSORIES MAY NOT COVER THESE METAL SURFACES













METRIC	Apple Inc.
DRAWTER: APPLE INC. DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER: APPLE INC. DATE	
DIMENSIONS ARE IN MILLIMETERS TOLERANCES	TITLE: AIRPODS 4
DO NOT SCALE DRAWINGS	DRAWING NUMBER / REV.
THIRD ANGLE PROJECTION	SIZE D / SCALE NONE / SHT 1 OF 1

NX GENERATED

Copyright © 2025 Apple Inc. All Rights Reserved.

63.282 MagSafe Charging Case (USB-C) for AirPods Pro (2nd generation), 1 of 3

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. ACCESSORIES INTRUDING INTO SHADED REGIONS WILL NEGATIVELY AFFECT PRODUCT PERFORMANCE.
2. TO ENSURE FULL FUNCTIONALITY, DO NOT OBSTRUCT THIS AREA WITH METAL OR OTHER CONDUCTIVE MATERIAL.
3. TO ENSURE FULL FUNCTIONALITY WITH MINIMAL IMPACT TO QI CHARGING PERFORMANCE, MINIMIZE ANY MATERIAL THICKNESS.
4. TO ENABLE CHARGING VIA APPLE WATCH CHARGER, IT IS RECOMMENDED THERE BE NO MATERIAL BETWEEN BACK OF DEVICE AND WATCH CHARGER.
5. PROTECTIVE CASES OR COVERS MAY DETUNE OR IMPACT RF & WIRELESS CHARGING PERFORMANCE.
   IMPACT IS HIGHLY DEPENDENT ON MATERIAL AND MATERIAL THICKNESS.
   HIGHLY RECOMMEND AVOIDING METAL MATERIAL AND FOLLOWING GUIDELINES IN THIS DOCUMENT TO MINIMIZE IMPACT.



SECTION A - A









DETAIL B
SCALE 5:1





SECTION C - C
INTERNAL DIMENSIONS OF LANYARD LOOP

METRIC	Apple Inc.
DRAWTER / DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER / DATE	
DIMENSIONS ARE IN MILLIMETERS TOLERANCES	TITLE: AIRPODS PRO GEN 2 WIRELESS CASE, USB-C
DO NOT SCALE DRAWINGS	DRAWING NUMBER / REV.
THIRD ANGLE PROJECTION / SIZE D / SCALE NONE	SHT 1 OF 3

NX GENERATED

Copyright © 2025 Apple Inc. All Rights Reserved.

63.283 MagSafe Charging Case (USB-C) for AirPods Pro (2nd generation), 2 of 3



Copyright © 2025 Apple Inc. All Rights Reserved.

63.284 MagSafe Charging Case (USB-C) for AirPods Pro (2nd generation), 3 of 3



Copyright © 2025 Apple Inc. All Rights Reserved.

63.285 MagSafe Charging Case for AirPods Pro (2nd generation), 1 of 3

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. ACCESSORIES INTRUDING INTO SHADED REGIONS WILL NEGATIVELY AFFECT PRODUCT PERFORMANCE.
2. TO ENSURE FULL FUNCTIONALITY, DO NOT OBSTRUCT THIS AREA WITH METAL OR OTHER CONDUCTIVE MATERIAL.
3. TO ENSURE FULL FUNCTIONALITY WITH MINIMAL IMPACT TO QI CHARGING PERFORMANCE, MINIMIZE ANY MATERIAL THICKNESS.
4. TO ENABLE CHARGING VIA APPLE WATCH CHARGER, IT IS RECOMMENDED THERE BE NO MATERIAL BETWEEN BACK OF DEVICE AND WATCH CHARGER.
5. PROTECTIVE CASES OR COVERS MAY DETUNE OR IMPACT RF & WIRELESS CHARGING PERFORMANCE.
   IMPACT IS HIGHLY DEPENDENT ON MATERIAL AND MATERIAL THICKNESS.
   HIGHLY RECOMMEND AVOIDING METAL MATERIAL AND FOLLOWING GUIDELINES IN THIS DOCUMENT TO MINIMIZE IMPACT.



SECTION A - A









DETAIL B
SCALE 5:1





SECTION C - C
INTERNAL DIMENSIONS OF LANYARD LOOP

METRIC	Apple Inc.
DRAWTER / DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER / DATE	
DIMENSIONS ARE IN MILLIMETERS TOLERANCES	TITLE: AIRPODS PRO GEN 2 WIRELESS CHARGING CASE
DO NOT SCALE DRAWINGS	DRAWING NUMBER / REV.
THIRD ANGLE PROJECTION / SIZE D	SCALE: NONE / SHT

NX GENERATED

63.286 MagSafe Charging Case for AirPods Pro (2nd generation), 2 of 3



63.287 MagSafe Charging Case for AirPods Pro (2nd generation), 3 of 3



NOTICE OF PROPRIETARY PROPERTY:
THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING:
(i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE
(ii) NOT TO REPRODUCE OR COPY IT
(iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART
(iv) ALL RIGHTS RESERVED

Apple Inc.
SIZE D | DRAWING NUMBER | REV.
SCALE: NONE | SHT

63.288 AirPods Pro (2nd generation)



63.289 MagSafe Charging Case for AirPods (3rd generation)



Copyright © 2025 Apple Inc. All Rights Reserved.

63.290 AirPods (3rd generation)

REV	ECO#	DESCRIPTION OF REVISION

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. ACCESSORIES INTRUDING INTO SHADED REGION WILL NEGATIVELY AFFECT PRODUCT PERFORMANCE
2. ACCESSORIES MUST NOT COVER THESE METAL SURFACES



METRIC	Apple Inc.
DRAFTER: APPLE — DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER: APPLE — DATE	TITLE: AirPods (3rd generation)
DIMENSIONS ARE IN MILLIMETERS TOLERANCES X.X ±0.2 X.XX ±0.10 X.XXX ±0.050 ANGLES ±0.5° DO NOT SCALE DRAWINGS	DRAWING NUMBER — REV. 01
THIRD ANGLE PROJECTION — SIZE C	SCALE: NONE — SHT 1 OF 1
NX GENERATED	

Copyright © 2025 Apple Inc. All Rights Reserved.

63.291 AirPods Max, 1 of 6

COMPONENT DEFINITION

NOTES: (UNLESS OTHERWISE SPECIFIED)

1. MEASURE MAGNETIC FLUX USING FLUX PROBE WITH CUPS ROTATED TO 'ON-HEAD' POSITION (AS SHOWN)
2. NO METAL CONTACT WITH PRODUCT
3. DO NOT OBSTRUCT PORTS
4. DO NOT OBSTRUCT OPTICAL WINDOWS
5. DO NOT APPLY PERSISTENT FORCE TO NOISE CONTROL BUTTON OR DIGITAL CROWN
6. DO NOT APPLY PERSISTENT FORCE TO CANOPY, CUSHION, OR ELASTOMER SKIN ON HEADBAND
7. DO NOT APPLY POINT LOADS TO CANOPY, CUSHION, OR ELASTOMER SKIN ON HEADBAND
8. DO NOT RESTRICT MOTION OF EAR CUP WITH RESPECT TO HEADBAND
9. DO NOT RESTRICT MOTION OF SLIDING ARMS ON HEADBAND













METRIC	Apple Inc.
DRAWTER / DATE	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER / DATE	
DIMENSIONS ARE IN MILLIMETERS TOLERANCES	TITLE: AIRPODS MAX
DO NOT SCALE DRAWINGS	DRAWING NUMBER / REV.
THIRD ANGLE PROJECTION	SIZE D / SCALE NONE / SHT 1 OF 7

NX GENERATED

63.292 AirPods Max, 2 of 6



Copyright © 2025 Apple Inc. All Rights Reserved.

63.293 AirPods Max, 3 of 6



63.294 AirPods Max, 4 of 6



Copyright © 2025 Apple Inc. All Rights Reserved.

63.295 AirPods Max, 5 of 6



Copyright © 2025 Apple Inc. All Rights Reserved.

EARCUP, LEFT OVERALL DIMENSIONS



2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

63.297 Wireless Charging Case for AirPods Pro (1st generation)



Copyright © 2025 Apple Inc. All Rights Reserved.

63.298 AirPods Pro (1st generation)

REV	ECO#	DESCRIPTION OF REVISION

NOTES: (UNLESS OTHERWISE SPECIFIED)

[1] ACCESSORIES INTRUDING INTO SHADED REGIONS WILL NEGATIVELY AFFECT PRODUCT PERFORMANCE

[2] ACCESSORIES MUST NOT COVER THESE METAL SURFACES





METRIC	Apple Inc.
DRAFTER: APPLE INC. — DATE: 03/05/20	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO REPRODUCE OR COPY IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED
DESIGNER: APPLE INC. — DATE: 03/05/20	
DIMENSIONS ARE IN MILLIMETERS TOLERANCES	TITLE: AIRPODS PRO
	DRAWING NUMBER — REV. 01
DO NOT SCALE DRAWINGS	
THIRD ANGLE PROJECTION — SIZE C	SCALE: NONE — SHT 1 OF 1

NX GENERATED

Copyright © 2025 Apple Inc. All Rights Reserved.

63.299 Wireless Charging Case for AirPods



Copyright © 2025 Apple Inc. All Rights Reserved.

63.300 AirPods (2nd generation) and AirPods (1st generation)

NOTES: (UNLESS OTHERWISE SPECIFIED)

[1] ACCESSORIES INTRUDING INTO SHADED REGIONS WILL NEGATIVELY AFFECT PRODUCT PERFORMANCE.

[2] ACCESSORIES MUST NOT COVER THESE METAL SURFACES.







METRIC	Apple Inc.
APPLE INC. 01/10/17	NOTICE OF PROPRIETARY PROPERTY: THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF APPLE INC. THE POSSESSOR AGREES TO THE FOLLOWING: (i) TO MAINTAIN THIS DOCUMENT IN CONFIDENCE (ii) NOT TO COPY OR REPRODUCE IT (iii) NOT TO REVEAL OR PUBLISH IT IN WHOLE OR PART (iv) ALL RIGHTS RESERVED TITLE: AIRPODS
THIRD ANGLE PROJECTION	SIZE D · SCALE NONE · SHT 1 OF 1

NX GENERATED

Copyright © 2025 Apple Inc. All Rights Reserved.

63.301 Apple MagSafe Charger (1 m) and Apple MagSafe Charger (2 m)



63.302 Apple MagSafe Charger



Copyright © 2025 Apple Inc. All Rights Reserved.

63.303 AirTag



63.304 Apple TV 4K (3rd generation)



Copyright © 2025 Apple Inc. All Rights Reserved.

63.305 Siri Remote (3rd generation)



Copyright © 2025 Apple Inc. All Rights Reserved.

Revision History

Added Content

- Cases (page 36)
  - Image Quality (page 76)
- Headset Plug (3.5 mm) (page 318)
- Device Dimensional Drawings (page 328)
  - iPad Pro 13-inch (M5) and iPad Pro 13-inch (M4), 1 of 5 (page 426)
  - iPad Pro 11-inch (M5) and iPad Pro 11-inch (M4), 1 of 5 (page 431)

Updated Content

- Device Dimensional Drawings (page 328)
  - iPhone 17 Pro Max, 1 of 4 (page 333)
  - iPhone 17 Pro, 1 of 4 (page 337)
  - Apple Vision Pro, 1 of 8 (page 592)
- Cases (page 36)
  - Device Models (page 50)
- Smart Covers (page 85)
- Headsets (page 97)
- Accessory Power (USB-C) (page 162)
- MagSafe Attach (page 193)
- Headset Remote and Microphone Transmitter (page 287)

2025-12-08 | Copyright © 2025 Apple Inc. All Rights Reserved.

Apple Inc.
Copyright © 2025 Apple Inc.
All rights reserved

Terms and Conditions ("Terms")

These Guidelines are made available to you for informational purposes only. If you make or distribute any accessory for an Apple device based on or in connection with these Guidelines ("Accessories"), you agree to the following covenants, terms and conditions:

All intellectual property rights in and to the Guidelines, and all technology described therein, are retained by Apple Inc. ("Apple"). You acknowledge and agree that Apple is not granting you, and nothing contained herein shall constitute or be construed or interpreted as a grant, by implication, estoppel or otherwise, of any license, covenant, immunity, release or right under or with respect to any intellectual property rights of Apple, including without limitation any rights to make, use, have made, sell, import, or otherwise relating in any way to any Apple device or technology described in or relating to the Guidelines.

You agree to follow Apple's Guidelines For Using Apple Trademarks and Copyrights as published on Apple's website at www.apple.com/legal/guidelinesfor3rdparties.html ("IP Guidelines") and as may be modified from time to time. You agree not to use the marks "Apple," the Apple Logo, "Mac", "iPhone," "iPod touch," "iPad," "Apple Watch," " WATCH" or any other marks belonging or licensed to Apple in any way except as expressly authorized in writing by Apple in each instance or as permitted in the IP Guidelines. You agree that all goodwill arising out of your authorized use of Apple's marks shall inure to the benefit of and belong to Apple.

You agree to indemnify, hold harmless, and, at Apple's option, defend, Apple against any claims, causes of action, losses, liabilities, damages, fines, settlements, costs, fees, and expenses (including attorney and other professional fees and expenses) arising out of: (i) your use of the Guidelines, including without limitation, any claims that any Accessory, or the combination of any Accessory with any software, technology, intellectual property, device, apparatus or assembly not supplied by Apple, infringes any patent, copyright, trade secret or other intellectual property right; (ii) the manufacture, use, promotion, distribution, sale, offer for sale, import, other distribution or exploitation or performance of any product, case, cover, band, charging stand, or other Accessory or product incorporating any Accessory, including any personal injury or product liability claims; or (iii) any failure to comply with any of the Guidelines. You will not, without Apple's prior written consent, make any admissions of liability, enter into any settlement that imposes any obligation on Apple, or publicize any settlement details relating to Apple. In addition, for any claims related to these Terms where you do not have an indemnification obligation, you shall provide all reasonable assistance to Apple and/or its counsel in connection with the defense, remedy or mitigation of such claims.

Applicable laws or regulations may impose additional restrictions or requirements on Accessories or products that incorporate the Accessories. You represent and warrant that you are in full compliance with all applicable laws, regulations, and policies in the United States and in any other location in which you engage, in whole or in part, in any activity related to the design, manufacture, marketing, sale or offer for sale, use, or other distribution of Accessories or products that incorporate the Accessories. You agree to promptly notify Apple of any complaints or threats of complaints regarding products that incorporate the Accessories with respect to any such regulatory requirements, in which case Apple may limit or terminate your ability to make, sell or purchase additional Accessories.

You expressly acknowledge and agree that access to the Guidelines is at your sole and entire risk and that you are solely responsible and liable for any harm or damage to any Apple product arising out of any breach by you of these covenants, terms and conditions. THE GUIDELINES ARE PROVIDED "AS IS" AND WITHOUT REPRESENTATION, WARRANTY, UPGRADES OR SUPPORT OF ANY KIND. APPLE AND APPLE'S DISTRIBUTORS, AFFILIATES, LICENSOR(S) AND SUPPLIER(S) ("APPLE PARTIES") EXPRESSLY DISCLAIM ALL REPRESENTATIONS, WARRANTIES AND CONDITIONS, EXPRESS OR IMPLIED, INCLUDING THE IMPLIED WARRANTIES AND CONDITIONS OF MERCHANTABILITY, OF SATISFACTORY QUALITY, OF FITNESS FOR A PARTICULAR PURPOSE, OF NON-INFRINGEMENT AND OF ACCURACY. NONE OF THE APPLE PARTIES WARRANTS THAT THE GUIDELINES OR ANY ACCESSORY WILL MEET YOUR REQUIREMENTS, THAT DEFECTS IN THEM WILL BE CORRECTED OR THAT THEY WILL BE COMPATIBLE WITH FUTURE APPLE PRODUCTS. NO ORAL OR WRITTEN INFORMATION OR ADVICE GIVEN BY ANY APPLE PARTY OR AN APPLE AUTHORIZED REPRESENTATIVE WILL CREATE A WARRANTY.

EXCEPT TO THE EXTENT SUCH A LIMITATION IS PROHIBITED BY LAW, IN NO EVENT WILL ANY APPLE PARTY BE LIABLE FOR ANY INCIDENTAL, SPECIAL, INDIRECT, CONSEQUENTIAL, EXEMPLARY OR PUNITIVE DAMAGES, INCLUDING LOST PROFITS, LOST REVENUES OR BUSINESS INTERRUPTIONS, ARISING OUT OF OR RELATING TO THE GUIDELINES UNDER A THEORY OF CONTRACT, WARRANTY, TORT (INCLUDING NEGLIGENCE), PRODUCTS LIABILITY OR OTHERWISE, EVEN IF ANY APPLE PARTY HAS BEEN ADVISED OF THE POSSIBILITY OF SUCH DAMAGES, AND NOTWITHSTANDING THE FAILURE OF ESSENTIAL PURPOSE OF ANY REMEDY. IN NO EVENT WILL THE APPLE PARTIES' TOTAL LIABILITY TO YOU FOR ALL DAMAGES AND CLAIMS UNDER OR RELATED TO THE GUIDELINES EXCEED THE AMOUNT OF US$50.00.

These Terms will be governed by and construed and enforced under the laws of the United States and the State of Delaware, except that the arbitration clause and any arbitration hereunder shall be governed by the Federal Arbitration Act, Chapters 1 and 2. The United Nations Convention on Contracts for the International Sale of Goods shall not apply to these Terms. All disputes arising out of or in connection with these Terms shall be finally settled under the Rules of Arbitration of the International Chamber of Commerce by one arbitrator appointed in accordance with such rules, and shall be conducted according to the International Bar Association Rules on the Taking of Evidence in International Arbitration. The arbitration shall take place in San Francisco, California. The arbitration shall be conducted in English. The award shall be rendered within six months of the commencement of the arbitration, unless the arbitrator determines that the interest of justice requires that such limit be extended.